

City of Madison

Proposed Rezoning, Preliminary and Final Plat

Project Name

Second Addition to Grandview Commons

Location

457 North Star Drive et al

Applicant

Jeff Rosenberg-MREC VH Madison Investors/ Dan Day - D'Onofrio Kotke & Assoc

From: PUD-GDP & To: Amended

PUD-SIP

PUD(PD)GDP-SIP

Proposed Use

101 single-family lots, 6 two-family


lots and 5 outlots

Public Hearing Date Plan Commission


18 February 2013

Common Council

26 February 2013



For Questions Contact: Tim Parks at: 261-9632 or tparks@cityofmadison.com or City Planning at 266-4635



Scale: 1" = 400'

City of Madison, Planning Division: RPJ: Date: 07 February 2013



City of Madison

Proposed Rezoning, Preliminary and Final Plat

Project Name

Second Addition to Grandview Commons

Location

457 North Star Drive et al

Applicant

Jeff Rosenberg-MREC VH Madison Investors/ Dan Day - D'Onofrio Kotke & Assoc

From: PUD-GDP & To: Amended

PUD-SIP

PUD(PD)GDP-SIP

Proposed Use

101 single-family lots, 6 two-family

lots and 5 outlots


Public Hearing Date

Plan Commission


18 February 2013

Common Council

26 February 2013



For Questions Contact: Tim Parks at: 261-9632 or tparks@cityofmadison.com or City Planning at 266-4635




Scale: 1'' = 400'

City of Madison, Planning Division: RPJ: Date: 07 February 2013



City of Madison

457 North Star Drive et al



Date of Aerial Photography: Spring 2010



LAND USE APPLICATION Madison Plan Commission

215 Martin Luther King Jr. Blvd; Room LL-100 PO Box 2985; Madison, Wisconsin 53701-2985 Phone: 608.266.4635 | Facsimile: 608.267.8739

- The following information is required for all applications for Plan Commission review except subdivisions or land divisions, which should be filed using the <u>Subdivision Application</u>.
- A separate Urban Design Commission application is no longer required for projects requiring both Urban Design Commission and Plan Commission approvals.
- This form may also be completed online at http://www.cityofmadison.com/developmentcenter/landdevelopment
- All Land Use Applications should be filed with the Zoning Administrator at the above address.

| FOR OFFICE USE ONLY: | | | | | | |
|----------------------|------------------------|--|--|--|--|--|
| Amt. Paid | Receipt No. | | | | | |
| Date Received | | | | | | |
| Received By | | | | | | |
| Parcel No. | | | | | | |
| Aldermanic District | | | | | | |
| GQ | | | | | | |
| Zoning District | | | | | | |
| For Co | For Complete Submittal | | | | | |
| Application | Letter of Intent | | | | | |
| Photos | Legal Descript. | | | | | |
| Plan Sets | Zoning Text | | | | | |
| Alder Notification | Waiver | | | | | |
| Ngbrhd. Assn Not. | Waiver | | | | | |
| Date Sign Issued | | | | | | |
| Project A | rea in Acres: 18.48 | | | | | |

| 1. Project Address: | 1. Project Address: 457 North Star Drive | | | Project Area in Acres: 18.48 | | |
|--|--|---------------------------|--------------|------------------------------|----------------------------|--|
| Project Title (if any): | Second Addition | to Grandview Common | s | • | | |
| 2. This is an application | on for (Check all | that apply to your Land | d Use App | ication): | | |
| | nendment from Pl | | | · | d PUD:GDP/SIP | |
| | ent to Approved F | | | | to Approved PD-SIP Zoning | |
| - • | • • | | , | | to Approved r b-sir zoning | |
| | - | ion to an Approved Cond | aitionai Use | • | | |
| Demolition Perr | nit | | | | | |
| ☐ Review of Mino | r Alteration to Pla | nned Development by t | ne Plan Coi | nmission O | nly | |
| | | | | | | |
| Applicant, Agent 8 | ኔProperty Owne | r Information: | | | | |
| Applicant's Name: Jeff F | Rosenberg | (| Company: M | REC VH M | adison Investors, LLC. | |
| Street Address: 6801 S | South Town Drive | City/State: | Madison, | WI | Zip: 53713 | |
| Telephone: (608) 226-3 | 100 Fax: | 226-0600 و ⁶⁰⁸ | Email: | jrosenberg | @veridianhomes.com | |
| Project Contact Person: | Brian Munson | (| company: V | andewalle 8 | & Associates | |
| Street Address: 120 Ea | ast Lakeside Stree | t City/State: | Madison, | WI | _{Zip:} 53715 | |
| | 988 Fax: | (608)255-0814 | Email: | bmunson@ | ②vandewalle.com | |
| Telephone: (608) 255-3 | | | | | | |
| · | :ant): | | | | | |
| Telephone: (608) 255-3' Property Owner (if not applic Street Address: | cant): | City/State: | | | Zip: | |
| Property Owner (if not applic Street Address: | | City/State: | | | Zip: | |
| Property Owner (if not applic | | City/State: | | | Zip: y, twin homes | |

| 5. I | Required Submittals: |
|------|---|
| V | Site Plans, fully dimensioned and describing pertinent project details, submitted as follows below and depicting all lo lines; existing, altered, demolished and/or proposed buildings; parking areas and driveways; sidewalks; the location of any new signs; existing and proposed utility locations; building elevations, materials and floorplans, and; landscaping • Seven (7) copies of a full-sized plan set drawn to a scale of 1 inch = 20 feet (collated, stapled and folded) • Twenty (20) copies of the plan set reduced to fit onto 11 X 17-inch paper (collated, stapled and folded) • For projects also being reviewed by the Urban Design Commission, twelve (12) additional 11 X 17-inch copies. • One (1) copy of the plan set reduced to fit onto 8 ½ X 11-inch paper |
| V | REVISED! – Letter of Intent: <i>Twelve (12) copies</i> describing this application in detail including, but not limited to: existing conditions; the project schedule; names of persons involved (contractor, architect, civil engineer, etc.); details of the project, including proposed uses, building square footage, number of dwelling units, auto and bike parking stalls, etc. hours of operation; value of land; project cost; any public subsidy requested, and; number of construction and full-time equivalent jobs created. For projects also being reviewed by the Urban Design Commission, provide <i>twelve (12) additional copies</i> of the letter. |
| V | Filing Fee: Refer to the Land Use Application Information & Fee Schedule. Make checks payable to: City Treasurer. |
| V | Electronic Submittal: All applicants are required to submit copies of all items submitted in hard copy with their application (including this application form, the letter of intent, complete plan sets, etc.) as Adobe Acrobat PDF files on a non-returnable CD to be included with their application materials, or by e-mail to pcapplications@cityofmadison.com |
| In A | Addition, The Following Items May Also Be Required With Your Application: |
| V | Legal Description of Property: For any application for rezoning, the description must be submitted as an <u>electronic word document</u> via CD or e-mail. For applications requesting rezoning to more than one district, a separate description of each district shall be submitted. |
| | For any applications proposing Demolition or Removal of existing buildings, the following items are required: Prior to the filing of an application, the applicant or his/her agent is required to notify a list of interested persons registered with the City 30 or 60 days prior to filing their application using the online notification tool found at: https://www.cityofmadison.com/developmentCenter/demolitionNotification/ A photo array (6-12 photos) of the interior and exterior of the building(s) to be demolished or removed. A written assessment of the condition of the building(s) to be demolished or removed is highly recommended. Approval of a Reuse & Recycling Plan by the City's Recycling Coordinator is required prior to issuance of permits. |
| V | A Zoning Text shall accompany <u>all</u> Planned Development District (PD/PCD/PUD) applications. |
| 6. | Applicant Declarations: |
| V | Conformance with adopted City plans: The site is located within the limits of the Sprecher Neighborhood Plan, which recommends Low Density Residential for this property |
| V | Pre-application Notification: Section 28.12 of the Zoning Code requires that the applicant notify the district alder and any nearby neighborhood and business associations in writing no later than 30 days prior to filing this request. List the alder person, neighborhood association(s), and business association(s) AND the dates you sent the notices: Alder Cnare, McClellan Park Neighborhood Association (October 11, 2012) |
| | → If a waiver has been granted to this requirement, please attach any correspondence to this effect to this form. |
| П | Pre-application Meeting with Staff: Prior to preparation of this application, the applicant is required to discuss the |

proposed development and review process with Zoning and Planning Division staff; note staff persons and date.

___ Date: 11/1.\2

→ The applicant attests that this form is accurately completed and all required materials are submitted:

Planning Staff: DAT

Name of Applicant Brian Munson

Authorizing Signature of Property Owner

Relation to Property Owner Agent

Date 12.12.12

By: Veridian Homes JULL

Zoning Staff: Matt Tucker



Wednesday, December 12, 2012

Brad Murphy 215 Martin Luther King Jr. Blvd. Suite 100 Madison, WI 53710

Re:

PUD: GDP/SIP Amendment Grandview Commons Re-plat

Mr. Murphy,

Attached please find a Planned Unit Development: General Development Plan/Specific Implementation request for a lot rebalancing for a portion of the un-built lot and Plan amendment to the Ridge View Homes District within the Grandview Commons Neighborhood.

The first amendment rebalances the lot mix within the re-plat area. The rebalancing effort is a response to the ongoing implementation of the project and the changes in housing desires within the small multi-family and single family markets. This amendment is coupled with a Re-Plat submittal amending the single family lots and districts along with the multi-family lots along Dominion Drive. Unit counts within the area are proposed to be amended from 101 single family and 20 multi-family to 101 single family and 12 twin home units through a combination of lot line adjustments, removal of alleys, and changes to he multi-family building type; per the attached exhibits. While this amendment results in a slightly lower unit count it maintains the underlying single family character and small lot multi-family components of this section of the neighborhood and represents a minor alteration to the overall neighborhood mix.

The second amendment reduces the minimum lot width (measured at the setback) to accommodate a 51' wide minimum lot width for front accessed homes within the Ridge View Homes district. The balance of the lot size requirements, including the minimum 5,000 square foot lot size, are retained.

These two amendments will allow the project to respond to the market conditions while still creating a diverse walkable neighborhood featuring a variety of homes and price points.

We look forward to working with everyone on the completion of this request.

Sincerely,


Brian Munson Principal

Cc:

Jeff Rosenberg, Veridian Homes Alder Lauren Cnare, District 3

McClellan Park Neighborhood Association

120 East Lakeside Street • Madison, Wisconsin 53715 • 608.255.3988 • 608.255.0814 Fax 342 North Water Street • Milwaukee, Wisconsin 53202 • 414.421.2001 • 414.732.2035 Fax www.vandewalle.com



Grandview Commons Second Addition

Single Family (Alley Loaded) **Multi-Family** Garden Homes Twin Homes Cottage Homes Condo/Apartments Village Homes Neighborhood Center Residential Village Homes II Neighborhood Center Mixed Use Courtyard Homes Parks & Open Space Single Family (Front Loaded) Stormwater Management Ridge View Homes Manor Homes Estate Homes

Adopted Plan







Grandview Commons Second Addition



Existing Zoning






Vandewalle & Associates, Inc. © 2012



Grandview Commons Second Addition







Second Addition to Grandview Commons

MInor Alteration Zoning Tracking

| | District | Existing Units | Proposed Units |
|--|---|----------------|----------------|
| Block 1 Existing Plat | | | |
| Lots 41-56 O.L. 2 | Garden Homes Alley | 16 | |
| Proposed Plat Lots 663-676 | Ridge View Homes | | 14 |
| Block 2 Existing Plat | | | |
| Lots 62, 67-71, 76-79 Lots 63-66, 72-75 O.L. 3 | Cottage Homes Village Homes II Alley | 10 8 | |
| Proposed Plat Lots 677-690 | Ridge View Homes | | 14 |
| Block 3 Existing Plat | | | |
| Lots 62-79 Lot 154 O.L. 9 | Village Homes I Condominium/Apartments Alley | 20 10 | |
| Proposed Plat Lots 731-742, 746-756 Lots 743-745 O.L. 38 | Village Homes I Twin Homes Alley | | 23 |
| Block 4 | | | |
| Existing Plat Lot 157 | Condominium/Apartments | 10 | |
| Proposed Plat Lots 757-759 | Twin Homes | | 6 |
| Block 5 | | | |
| Existing Plat Lots 112-129 O.L. 8 | Village Homes II Alley | 18 | |
| Proposed Plut Lots 707-730 O.L. 36 O.L. 37 | Garden Homes Alley Alley | | 24 |
| Block 6 Existing Plat | | | |
| Lots 80-85 Lots 86-90 Lots 91-96 O.L. 4 O.L. 5 O.L. 6 O.L. 7 | Cottage Homes Garden Homes Village Homes II Stormwater Management Private Open Space Alley Private Open Space | 6 5 6 | |
| Proposed Plat Lots 691-706 O.L., 4 O.L., 35 | Ridge View Homes Stormwater Management Private Open Space | | 16 |
| Block 7 | | | |
| Existing Plat Lots 7-18 O.L. 1 | Manor Homes Stormwater Management | 12 | |
| Proposed Plat Lots 653-662 | Manor Homes | | 10 |
| O.L. 34 | Manor Flomes Stormwater Management | | 10 |
| Overall Total | | 121 | 113 |

Vandewalle & Associates December 12, 2012

District Descriptions Garden Homes District

Revised:

December 13, 2002 December 12, 2012

Description

This district will form the highest density single-family residential district, featuring alley loaded garages, reduced setbacks, proportioned architectural detailing, and pedestrian focused streetscapes.

Permitted Uses

Single Family Detached Homes Detached, Attached Garages

Lot Requirements

Minimum Lot Area Minimum Lot Width Minimum Corner Lot Width Minimum Front Yard Setback Maximum Front Yard Setback Minimum Side Yard Setback

Minimum Corner Lot Side Yard Setback

Sum of Side Yard Setbacks Minimum Building Separation Minimum Garage Rear Yard Setback Maximum Garage Rear Yard Setback

Minimum Garage Side Yard Setback Minimum Paved Surface Setback Maximum Building Height

Maximum Impervious Surface Ratio Maximum Floor Area Ratio

Off-Street Parking and Loading Accessory Building Regulations 3,240 square feet

45 feet 48 feet 16 feet 20 feet

> 3 feet with a maintenance and access easement to the adjoining property 10 feet from the street side right of way

10 feet minimum

10 feet 2 feet

4' on exterior lots 8' on interior lots

3 feet 2 feet 35 feet 80% .70

two off-street stalls minimum

accessory buildings not allowed, except

VILLAGE HOMES I DISTRICT

Revised:

December 13, 2002 December 12, 2012

Description

This district will form the transitional density between the alley-loaded districts and front-loaded Ridge View Homes. These sites feature alley-loaded garages, reduced setbacks, proportioned architectural detailing, and pedestrian focused streetscapes.

Permitted Uses

Single Family Detached Homes Detached, Attached Garages

Lot Requirements

Minimum Lot Area Minimum Lot Width Minimum Corner Lot Width Minimum Front Yard Setback Maximum Front Yard Setback Minimum Side Yard Setback

Minimum Corner Lot Side Yard Setback

Sum of Side Yard Setbacks Minimum Building Separation Minimum Garage Rear Yard Setback Maximum Garage Rear Yard Setback

Minimum Garage Side Yard Setback Minimum Paved Surface Setback Maximum Building Height

Maximum Impervious Surface Ratio Maximum Floor Area Ratio

Off-Street Parking and Loading

Accessory Building Regulations

4,275 square feet

45 feet 48 feet 18 feet 22 feet

> 3 feet with a maintenance and access easement to the adjoining property 10 feet from the street side right of way

10 feet minimum

10 feet 2 feet

4' on exterior lots 8' on interior lots

3 feet 2 feet 35 feet 70%

two off-street stalls minimum

accessory buildings not allowed, except

RIDGE VIEW HOMES DISTRICT

Revised:

January 17, 2003 December 12, 2012

Description

These units feature reduced setbacks, setback garage facades, and architectural detailing, designed to further the pedestrian focus of the neighborhood.

Permitted Uses

Single Family Detached Homes Detached, Attached Garages

Lot Requirements

Minimum Lot Area 5,000 square feet
Minimum Lot Width 51 feet
Minimum Front Yard Setback 20 feet
Maximum Front Yard Setback 25 feet
Minimum Side Yard Setback 5 feet
Minimum Corner Lot Side Yard Setback 10 feet from the s

Minimum Corner Lot Side Yard Setback 10 feet from the street side right of way Sum of Side Yard Setbacks 10 feet minimum

Minimum Building Separation 10 feet
Minimum Rear Yard Setback 20 feet

Allowed Rear Yard Deck Encroachment 10 feet
Garage Setback The garage must

The garage must be set back a minimum of 2 feet from the front façade of the house. There shall be no more than (2) single width, or (1) double width garage

door(s) per elevation

Bulk Mass The garage wing shall not exceed 50% of

the total structure width

Maximum Building Height 35 feet
Maximum Impervious Surface Ratio 60%
Maximum Floor Area Ratio .60

Off-Street Parking and Loading two off-street parking stalls minimum
Accessory Building Regulations accessory buildings not allowed, except

MANOR HOMES DISTRICT

Revised:

January 17, 2003 September 21, 2004 December 12, 2012

Description

Manor Homes form the bulk of the medium range single-family residential. These sites feature a range of architectural styles, front-loaded garages, setback garage facades, and reduced setbacks.

Permitted Uses

Single Family Detached Homes Detached, Attached Garages

Lot Requirements

Minimum Lot Area 6,900 square feet
Minimum Lot Width 69 feet
Minimum Corner Lot Width 74 feet
Minimum Front Yard Setback 20 feet
Maximum Front Yard Setback 24 feet
Minimum Side Yard Setback 5 feet

Minimum Corner Lot Side Yard Setback 10 feet from the street side right of way

Sum of Side Yard Setbacks 10 feet
Minimum Building Separation 10 feet
Minimum Rear Yard Setback 28 feet
Allowed Rear Yard Deck Encroachment 10 feet

Garage Setback Front facing garages must be set back a

minimum of 2 feet from the front facade

of the house.

There shall be no more than (2) single width, or (1) double width garage door(s) per elevation, except (1) additional single width door may be added if setback a minimum of two feet from the facade of the other garage doors, or side entry

loaded.

Bulk Mass The garage wing shall not exceed 50% of

the total structure width

Maximum Building Height 35 feet
Maximum Impervious Surface Ratio 40%
Maximum Floor Area Ratio .50

Off-Street Parking and Loading two off-street parking stalls minimum

TWIN HOME DISTRICT

Revised:

July 16, 2004

December 12, 2012

Description

This two-family residential district features alley-loaded garages, reduced setbacks, pedestrian focused streetscape elements, and single-family style architecture. These lots may be split in half to create zero lot line units, divided along the common wall. Future lot splits will require additional submittals (CSM, Plat), but are allowed for lots within this district, provided that no additional units are created.

Permitted Uses

Two Family Residential Homes Zero Lot Line Attached Residential Detached Garages

Lot Area

Minimum Lot Area

3,000 square feet

note: Zero lot line homes only Two-unit lot minimum 6,000 square feet

Floor Area Ratio

Maximum Floor Area Ratio

.70

Yard Requirements

| Minimum Lot Width (two unit lot) | 60 feet |
|--|-----------|
| Minimum Lot Width (zero lot line) | 30 feet |
| Minimum Corner Lot Width | 65 feet |
| Minimum Corner Lot Width (zero lot line) | 32.5 feet |
| Minimum Front Yard Setback | 16 feet |
| Maximum Front Yard Setback | 20 feet |
| Minimum Side Yard Setback | 5 feet |
| Minimum Side Yard Setback(zero lot line) | 0 feet |
| | |

note: zero lot line requires additional fire wall ratings for attached units; to

be determined at time of building permit application

Minimum Corner Lot Side Yard Setback 10 feet from the street side right of way

Minimum Building Separation 10 feet between adjoining lots

Minimum Alley Garage Rear Yard Setback 2 feet Minimum Alley Garage Side Yard Setback 3 feet

Off-Street Parking and Loading Two off-street parking stalls per unit

Maximum Impervious Surface Ratio 70% Maximum Floor Area Ratio .65

Off-Street Parking and Loading two off-street parking stalls per unit Accessory Building Regulations accessory buildings not allowed, except

General Requirements

Definition of Family

The definition of family is the definition outlined in the Madison General Ordinances for the TR-C3 district.

Permitted Encroachments

Front porches, balconies, stoops, open porches and covered walkways may encroach a maximum of 6' into a front yard setback.

Corner lot porches, and bay windows may not encroach the vision triangle. The triangle is defined by: the intersection of the curbs at the corner, and a point 30 feet back along each curb from the corner.

Bay windows may encroach front yard setbacks and will require approval by the Architectural Control Committee.

Roof eaves may not extend over a property line or a utility easement.

Garden walls or fences shall be no more than 4' in height and will require approval by the Architectural Control Committee. Walls and fences located within the vision triangle shall not exceed 30" in height. Fences located between adjoining homes (bridging the ten foot building separation) are required to be perpendicular to the property line, and must include a 46" wide gate for fire accessibility.

Plantings or fences installed may not block site drainage or preclude fire access to the building sides or rear yard.

Legal Description

All of Lots 7-18, 41-56, 62-79, 80-96, 112-129, 134-154, 157, Outlots 1-3 and Outlots 5-9, Grandview Commons, as recorded in Volume 58-005A of plats, on pages 19-33, as Document Number 3583911, Dane County Registry, located in the Northwest Quarter of the Northeast Quarter of Section 11 and in the Southwest Quarter of the Southeast Quarter of Section 2, Township 7 North, Range 10 East, City of Madison, Dane County, Wisconsin