

# City of Madison

# Proposed Rezoning and Final Plat

Project Name Grandview Commons Replat No. 2

Location 467-507 North Star Drive and 452 & 504 Pluto Drive


Applicant Jeff Rosenberg – MREC VH Madison, LLC/ Brian Munson – Vandewalle & Associates

From: PD(SIP) To: Amended PD(GDP-SIP)


Proposed Use Replat 6 lots approved for two-family dwellings-twin into 12 single-family lots

Public Hearing Date Plan Commission 20 April 2015

Common Council 05 May 2015




For Questions Contact: Tim Parks at: 261-9632 or tparks@cityofmadison.com or City Planning at 266-4635



Scale: 1" = 400'

City of Madison, Planning Division: RPJ: Date: 15 April 2015





Date of Aerial Photography : Spring 2013



# AND USE APPLICATION

- x All Land Use Applications should be filed with the Zoning Administrator at the above address.
- x The following information is required for all applications for Plan Commission review except subdivisions or land divisions, which should be filed using the Subdivision Application.
- x This form may also be completed online at: www.cityofmadison.com/developmentcenter/landdevelopment

	CIT OF WINDSON
Madison n	
215 Martin Luther King Jr. Blvd; Room LL-100 PO Box 2985; Madison, Wisconsin 53701-2985 Phone: 608.266.4635   Facsimile: 608.267.8739	FOR OFFICE USE ONLY:  Amt. Paid 1, 700 Receipt No. 00/2 4%  Date Received 1/18/15 000 2  Received By 34
x All Land Use Applications should be filed with the Zoning Administrator at the above address.	Parcel No. Aldermanic District 3 Lawren Chave Zoning District PD Special Requirements Zoned PD, Eng hold
x The following information is required for all applications for Plan Commission review except subdivisions or land divisions, which should be filed using the <u>Subdivision Application</u> .	Review Required By:
x This form may also be completed online at: www.cityofmadison.com/developmentcenter/landdevelopment	Urban Design Commission Plan Commission Common Council Other: Form Effective: February 21, 2013
1. Project Address: 452 Pluto Street	
Project Title (if any): Grandview Commons Twin Home Ar	nendment
2. This is an application for (Check all that apply to your Land  \)	Jse Application):
Zoning Map Amendment from PUD:SIP to	o Amended PD-GDP/SIP
	Major Amendment to Approved PD-SIP Zoning
Review of Alteration to Planned Development (By Plan Com	mission)
<ul> <li>Conditional Use, or Major Alteration to an Approved Conditi</li> </ul>	onal Use
Demolition Permit	
Other Requests:	
3. Applicant, Agent & Property Owner Information:	
	y: MREC VH Madison LLC.
f and the second	Addison, WI Zip: 53713
	Email: <u>irosenberg@veridianhomes.com</u>
Project Contact Person: Brian Munson Compar	y: Vandewalle & Associates
Street Address: 120 East Lakeside Street City/State: N	Aadison, WI Zip: <u>53715</u>
Telephone: (608) 255-3988 Fax: (608) 255-0814	mail: <u>bmunson@vandewalle.com</u>
Proporty Owner (if not applicant)	
Property Owner (if not applicant):  Street Address:	7:
Street Address: City/State:	Zip:

### 4. Project Information:

Provide a brief description of the project and all proposed uses of the site: Replat of twin home lots to single family

Development Schedule: Commencement

2015

Completion 2020

### 5. Required Submittal Information

All Land Use applications are required to include the following:

- Project Plans including:\*
  - Site Plans (fully dimensioned plans depicting project details including all lot lines and property setbacks to buildings; demolished/proposed/altered buildings; parking stalls, driveways, sidewalks, location of existing/proposed signage; HVAC/Utility location and screening details; useable open space; and other physical improvements on a property)
  - Grading and Utility Plans (existing and proposed)
  - Landscape Plan (including planting schedule depicting species name and planting size)
  - Building Elevation Drawings (fully dimensioned drawings for all building sides, labeling primary exterior materials)
  - Floor Plans (fully dimensioned plans including interior wall and room location)

#### Provide collated project plan sets as follows:

- Seven (7) copies of a full-sized plan set drawn to a scale of 1 inch = 20 feet (folded or rolled and stapled)
- Twenty Five (25) copies of the plan set reduced to fit onto 11 X 17-inch paper (folded and stapled)
- One (1) copy of the plan set reduced to fit onto 8 ½ X 11-inch paper
- \* For projects requiring review by the Urban Design Commission, provide Fourteen (14) additional 11x17 copies of the plan set. In addition to the above information, all plan sets should also include: 1) Colored elevation drawings with shadow lines and a list of exterior building materials/colors; 2) Existing/proposed lighting with photometric plan & fixture cutsheet; and 3) Contextual site plan information including photographs and layout of adjacent buildings and structures. The applicant shall bring samples of exterior building materials and color scheme to the Urban Design Commission meeting.
- Letter of Intent: Provide one (1) Copy per Plan Set describing this application in detail including, but not limited to:
  - **Project Team**
  - **Existing Conditions**
  - Project Schedule
  - Proposed Uses (and ft<sup>2</sup> of

Planning Staff: DAT

Name of Applicant Mac UH MANO

**Authorizing Signature of Property Owner** 

- **Building Square Footage**
- Number of Dwelling Units
- Auto and Bike Parking Stalls
- Coverage & Usable Open
- Value of Land
- **Estimated Project Cost**
- Number of Construction & Full-Time Equivalent Jobs

Date: 1.8.15

,	each)  Hours of Operation	Space Calculations  •	Created Public Subsidy Requested						
	Filing Fee: Refer to the Land Use Application Information & Fee Schedule. Make checks payable to: City Treasurer.								
	<b>Electronic Submittal:</b> All applicants are required to submit copies of all items submitted in hard copy with their application as Adobe Acrobat PDF files on a non-returnable CD to be included with their application materials, or by e-mail to <a href="mailto:pcapplications@cityofmadison.com">pcapplications@cityofmadison.com</a> .								
	Additional Information may be required, depe	nding on application. Refer to the <u>Supplemer</u>	ital Submittal Requirements.						
6. Applicant Declarations									
	Pre-application Notification: The Zoning Coneighborhood and business associations in alderperson, neighborhood association(s), an Alder Cnare, McClellan Park Neighborhood As	writing no later than 30 days prior to F d business association(s) AND the dates you	ILING this request. List the						
	Æ If a waiver has been granted to this requi	rement, please attach any correspondence t	to this effect to this form.						
	<b>Pre-application Meeting with Staff:</b> Prior to proposed development and review process v								

Date: 1.8.15 Zoning Staff: DAT

Relationship to Property:

The applicant attests that this form is accurately completed and all required materials are submitted:



February 18, 2015

Katherine Cornwell
Department of Planning & Development
City of Madison
215 Martin Luther King, Jr. Blvd.
Madison, WI 53710-2985

RE:

**Grandview Commons** 

PD-GDP/SIP Major Amendment

#### Dear Katherine,

The following document and illustrative graphics outline the request to rezone the un-built twin homes lots within the Grandview Commons Neighborhood to single family alley accessed lots.

We look forward to working with the City on the review and implementation of this project.

Sincerely,

Brian Munson Principal APPLICANT:

MREC VH Madison, LLC. 6801 South Town drive Madison, WI 53713 Phone: 608.226.3100

Fax: 608.226.0600 Jeff Rosenberg

irosenberg@veridianhomes.com

**DESIGN TEAM:** 

Engineering: Planning:

D'Onofrio Kottke

7530 Westward Way

Madison, WI 53717

Phone: 608.833.7530

Fax: 608.833.1089

Vandewalle & Associates

120 East Lakeside Street

Madison, Wisconsin 53715

Phone: 608.255.3988

Fax: 608.255.0814

Dan Day Brian Munson

<u>dday@donofrio.cc</u> <u>bmunson@vandewalle.com</u>

**Existing Conditions:** 

Existing Zoning: PD-SIP

Twin Homes District (12 units)

Proposed Zoning: Amended PD-GDP/SIP

Cottage Homes District (12 units)

Addresses/PIN: 452 Pluto Street 0710-024-3714-5

 467 North Star Drive
 0710-024-3712-9

 471 North Star Drive
 0710-024-3713-7

 504 Pluto Street
 0710-111-2026-0

 503 North Star Drive
 0710-111-2027-8

 507 North Star Drive
 0710-111-2028-6

Aldermanic District: District 3: Alder Cnare

Neighborhood Association: McClelland Park Neighborhood

Neighborhood Plan: Low Density Residential

Notifications: Alder Cnare December 30, 2014

McClelland Park Neighborhood December 30, 2014
DAT Presentation January 8, 2015

Legal Description: See Attached

Lot Area: 1.44 acres

Filing Fee: A check in the amount of \$1,700 made out to City of Madison

Treasurer is enclosed for the Filing and Notification Fees.

Proposed Use: Single Family: 12 lots

# Existing: 6 Twin Home Lots (12 Units) O.L. 38 O.L. 36 D.L. 12 VANDEWALLE & ASSOCIATES INC.

# Proposed: 12 Cottage Home Lots



# There are no objections to this plat with respect to Secs. 236.15, 236.16, 236.20 and 236.21(1) and (2), Wis. Stats, as provided by s. 236.12, Wis. Stats.

# GRANDVIEW COMMONS REPLAT NO. 2

DOCUMENT NUMBER 5034529, DANE COUNTY REGISTRY, LOCATED IN THE NORTHWEST QUARTER OF THE NORTHEAST QUARTER OF SECTION 11 AND IN THE SOUTHWEST QUARTER OF THE SOUTHEAST QUARTER OF SECTION 2, ALL IN TOWNSHIP 7 NORTH, RANGE 10 EAST, CITY OF MADISON, DANE COUNTY, WISCONSIN

Department of Administration

All lots (997-1008) within this plot are subject to public easements for drainage purposes which shall be 5
feet in width measured from the property line to the interior of each lot comments shall not be required
on property lines shared with outlots or public streats. In buildings, drivewbys, or retaining wills shall
be placed in any easement for drainage purposes. Fences may be placed in the easement only if they do not
impade the anticipated flow of woter.

The intra-block drainage easements shall be graded with the construction of each principle structure in accordance with the approved storm water drainage plan on file with the City Engineer and the Zaning Administrator, as amended in accordance with the Madison General Ordinances.

Note: In the event of a City of Modison Pion Commission and/or Common Council approved redivision of a previously subdivided property. The underlying bublic essements for droinage purposes are released and replicated by these urrent approved subdivision.

- 5. Notes on Grandier Commons Plat:

   All buildings and cutteror recreation area shall comply with MGD Sec. 16.23(3)(d) Highway Noise Land Use Provisions policies and ordinance.
   Subsoil information indicates that basements of structures with the plat may encounter bedrock. The sub-surface conditions report, dated November 11, 2011 is on file with the City Engineer.
   Upon review and approval of each conditional use proposal for multi-familylates, provisions for off-street parking are expected to exceed the minimum R4 requirements of the zoning ordinance.
   As of the date of plat recordation there is an active quarry operation on the lands located to the north and west of this plat.

- ond west of this plot.

  6. This plot is subject to the following recorded instruments:

   Declaration of Conditions, Covenants and Restrictions recorded as Doc.

  707.

   Declaration of Conditions, Covenants and Restrictions recorded as Doc.

  708.

   Declaration of Conditions, Covenants and Restrictions recorded as Doc.

  709.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  809.

  80


- 7. Distances shown along curves are chard lengths.


CURVE TABLE									
CURVE HUMBER	LOT	RADIUS (FEET)	CHORD (FEET)	ARC (FEET)	CHORD BEARING	CENTRAL ANGLE	TANGENT BEARING		
1		740.00	143.77	144.00	NO7*50'11"E	011°08'58"	IN-S13*24'40"W		
	997	740.00	43.81	43.82	N11*42'53"E	003*23'34"	OUT-NO2° 15′ 42″E		
	998	740.00	36.03	36.03	NO8"37'24"E	002*47'24"			
	999	740.00	36.03	36.03	NO2°50'00'E	002*47'24"			
	1000	740.00	28.11	28.11	NO3+21'00"E	011'08'58"			
2		25.00	32.77	35.74	N43°12′44″E	081.54'04"			
3		25.00	35.31	39.21	547*19'47"E	089"51'50"	OUT-S02°23′52″E		
4		845.00	76.75	76.78	500°12′19″W	005*12'22"	OUT-S02*48'30"W		
5		800.00	102.35	102.42	509°36′04″W	007*20'06"	IN-505°56'01'W		
	999	800.00	10.88	10.88	506°19′24″W	000° 46′ 46″	OUT-513*16'07"W		
	998	800.00	41.29	41.29	\$08°11'30"W	002*57'24"			
	997	800.00	50.23	50.24	511°28′10″W	003*35'54			
6		25.00	32.49	35.37	N48°09'20"W	081*03'40"	OUT-NO7*37'30"W		
6 7		740.00	138.97	139.18	N13°00'47"W	010*46'34"	OUT-N18*24'04"W		
	1005	740.00	31.07	31.08	NO8" 49 ' 41 "W	002"24"22"			
	1006	740.00	36.03	36.03	N11°25'34"W	002.47'24"			
	1007	740.00	36.03	36.03	N14*12'58"W	002°47′24″			
	1008	740.00	36.03	36.03	N17*00'22"W	010°46′34″			

#### LEGEND


- Found 1-1/4" Iron Rebar
- Found 3/4" Iron Rebar

All other lot corners are marked with  $3/4\,^{\prime\prime}\mathrm{x}$  18  $^{\prime\prime}$  solid round iron rebor stakes, weighing 1.50 lbs/ft.





HON-EXCLUSIVE DRAINAGE EASEMENT DETAIL



#### D'ONDFRIO KOTTKE AND ASSOCIATES, INC.

7530 Westward Way, Madison, WI 53717 YOUR NATURAL RESOURCE FOR LAND DEVELOPMENT FN: 15-07-103

There are no objections to this plat with respect to Secs. 236.15, 236.16, 236.20 and 236.21(1) and (2), Wis. Stats, as provided by s. 236.12, Wis. Stats. Department of Administration

# GRANDVIEW COMMONS REPLAT NO. 2

A REPLAT OF LOTS 743, 744 745, 757, 758 AND 759, GRANDVIEW COMMONS REPLAT NO. 1, AS RECORDED IN VOLUME 60-020B OF PLATS ON PAGES 102-105 AS DOCUMENT NUMBER 5034529, DANE COUNTY REGISTRY, LOCATED IN THE NORTHWEST QUARTER OF THE NORTHEAST QUARTER OF SECTION 11 AND IN THE SOUTHWEST QUARTER OF THE SOUTHEAST QUARTER OF SECTION 2, ALL IN TOWNSHIP 7 NORTH, RANGE 10 EAST, CITY OF MADISON, DANE COUNTY, WISCONSIN

#### LEGAL DESCRIPTION

1. Brett T. Stoffregon, Registered Land Surveyor S-2742 do hereby certify that in full compliance with the provisions of Chapter 236 of the Wisconsin State Statutes and the Subdivision Regulations of the City of Madison, and under the direction of the owners listed below. I have surveyed, divided and mapped "Grandview Commans Replat No. 2" and that such plat correctly represents all the exterior boundaries and the Subdivision of the land surveyed as is described os follows:

Lots 743, 744 745, 757, 758 and 759, Grandview Commons Replat No. 1, recorded in Volume 60-0208 of Plats on pages 102-105 as Document Number 5034529, Dane County Registry, located in the Northwest Guarter of the Northwest Ouarter of Section 1 and in the Southwest Ouarter of Section 2, all in Township 7 North, Range 10 East, City of Madison, Dane County, Wisconsin. Containing 62,690 square feet (1.439 acres).

Dated this 28th day of January, 2015.

Stoffregan, Professional Land Surveyor S-2742



#### OWNER'S CERTIFICATE

MREC VH Madison, LLC a limited liability company duly organized and existing under and by virtue of the laws of the State of Misconsin. as owner, does hereby certify that said limited liability company coused the land described on this plat to be surveyed. divided, mapped and dedicated as represented on this plat.

MREC VH Madison. LLC does further certify that this plat is required by \$236.10 or \$236.12 Wisconsin Statutes to be submitted to the following agencies for approval or objection:

Department of Administration Common Council: City of Madison Dane County Zoning and Land Regulation Committee

NREC VH Madison, LLC By:Veridian Homes JV, LLC, Member and Project Manager

Jeff Rosenberg, Authorized Signatory

#### MORTGAGEE CERTIFICATE

First Business Bank, a corporation duly organized and existing under and by virtue of the laws of the State of Wisconsin mortagese of lands contained in this plat, does hereby consent to the above Dwner's Certificate and to the surveying, dividing, mapping and dedication of the lands described on this plat.

In witness where, sold First Business Bank has caused these presents to be signed by its corporate officer(s) listed below on this day of . 2015.

First Business Bonk

STATE OF WISCONSIN) COUNTY OF DANE ) S.S

Personally came before me this \_\_\_day of \_\_\_\_\_, 2015, the above named officer(s) of the above named First Business Bank, to me known to be the person(s) who executed the foregoing instrument and acknowledged the same.

My Commission\_\_\_\_ Notary Public, Dane County, Wisconsin

#### MADISON COMMON COUNCIL CERTIFICATE

Dated this\_\_\_\_day of\_\_\_\_

Maribeth Witzel-Rebl. City Clerk, City of Madison, Dane County, Wisconsin

#### COUNTY TREASURER'S CERTIFICATE

Adam Gallagher, being the duly elected, qualified, and acting treasurer of the County of Dane, do hereby certify that in accordance with the records in my office, there are no unpoid taxes or special assessments as of this \_\_\_\_\_\_day of \_\_\_\_\_, 2015 affecting the land included in "Grandview Commons Replat No. 2".

Adam Gallagher, Treasurer, Dane County, Wisconsin

#### CITY OF MADISON TREASURER'S CERTIFICATE

David M. Gawenda, City Treasurer, City of Madison, Dane County, Wisconsin

REGISTER OF DEEDS CERTIFICATE

Received for recording this \_\_\_\_\_\_day of\_\_\_\_\_\_\_, 2
and recorded in Volume \_\_\_\_\_\_of Plats on Pages\_\_\_\_\_\_as Document Number\_\_\_\_\_ 

Kristi Chlebowski. Dane County Register of Deeds


D'ONOFRIO KOTTKE AND ASSOCIATES, INC.

7530 Westward Way, Madison, WI 53717 YOUR NATURAL RESOURCE FOR LAND DEVELOPMENT FN: 15-07-103

SHEET 2 OF 2

# Original Adopted Zoning: Twin Homes

Final Plat Numbers 470-479 60-70' wide by 95-100' deep minimum alley access garage



**Twin Home District Locations** 

#### Description

Twin homes offer alley-loaded attached housing at the single-family residential scale. These units consist of paired single-family units and will be available in rental and condominium ownership arrangements.

Net Acreage 1.1 acres
Proposed Dwelling Units 20 units

Net Density 18.4 dwelling units/acre

#### **Character Guidelines**

- Balconies, entry bays, and front porches are recommended to enhance the human scale of the public street façade.
- Porches, stoops, and bays are allowed and encouraged to encroach into the front yard setback to allow for increased porch width and to encourage the inclusion of porches or entry bays onto each house.
- Varied building setbacks are encouraged to create a more organic streetscape in which there are slight variations between buildings along the length of the street.
- As the buildings are moved closer to the street and to each other, special attention should be taken to design details, house details, and landscaping to ensure that the public street façade is of proper pedestrian scale.
- Front entries of each house should be oriented towards the public street frontage.
- To ensure that the alley width does not become visually similar to the street width, alley-loaded garages should be set back no more than four feet from the rear property line for exterior lots, and eight feet from the rear property line for interior lots. The varied setback ensures that the entrances to



the alley system are clearly defined as an alley and visually separated from the street intersections. This clear delineation of the alley versus street will help minimize cut through traffic and reduce travel speeds within the alley. This setback will further allow for sufficient space for items such as garbage and snow storage without allowing for additional parking spaces in the alley between the alley and the garage facade.

Varied garage setbacks along the alley are encouraged to create a more interesting streetscape and avoid cramped, monotonous, and claustrophobic alleyways.



### TWIN HOME DISTRICT

Revised:

July 16, 2004

#### Description

This two-family residential district features alley-loaded garages, reduced setbacks, pedestrian focused streetscape elements, and single-family style architecture. These lots may be split in half to create zero lot line units, divided along the common wall. Future lot splits will require additional submittals (CSM, Plat), but are allowed for lots within this district, provided that no additional units are created.

#### **Definition of Family**

The definition of family is the definition outlined in <u>Section 28.03(2)</u> Madison General Ordinances for the R-3 district.

#### Permitted Uses

Two Family Residential Homes Zero Lot Line Attached Residential Detached Garages

#### Lot Area

Minimum Lot Area 3,000 square feet

note: Zero lot line homes only

Two-unit lot minimum 6,000 square feet

Floor Area Ratio

Maximum Floor Area Ratio .70

Yard Requirements

Minimum Lot Width (two unit lot) 60 feet Minimum Lot Width (zero lot line) 30 feet Minimum Corner Lot Width 65 feet Minimum Corner Lot Width (zero lot line) 32.5 feet Minimum Front Yard Setback, 16 feet Maximum Front Yard Setback <u> 20 feet</u> Minimum Side Yard Setback 5 feet Minimum Side Yard Setback (zero lot line) 0 feet

note: zero lot line requires additional fire

wall ratings for attached units; to be determined at time of building

permit application

Minimum Corner Lot Side Yard Setback 10 feet from the street side right of way

<u>Minimum Building Separation</u> <u>10 feet between adjoining lots</u>

Minimum Alley Garage Rear Yard Setback2 feetMinimum Alley Garage Side Yard Setback3 feet

Off-Street Parking and Loading Two off-street parking stalls per unit

Maximum Impervious Surface Ratio70%Maximum Floor Area Ratio.65

Off-Street Parking and Loading two off-street parking stalls per unit

Accessory Building Regulations accessory buildings not allowed, except detached garages

VERIDIAN HOMES GRANDVIEW COMMONS

#### Permitted Encroachments

Front porches, balconies, stoops, open porches and covered walkways may encroach a maximum of 6' into a 16-18' front yard setback.

Front Yard Setbacks of 20' must utilize 6-8' porch encroachment.

Corner lot porches, and bay windows may not encroach the vision triangle. The triangle is defined by: the intersection of the curbs at the corner, and a point 30 feet back along each curb from the corner.

Roof eaves may not extend over a property line or a utility easement.

Garden walls or fences shall be no more than 4' in height and will require approval by the Architectural Control Committee. Walls and fences located within the vision triangle shall not exceed 30" in height.

Fences located between adjoining homes (bridging the ten foot building seperation) are required to be perpedicular to the property line, and must include a 46" wide gate for fire accessibility.


Plantings or fences installed may not block site drainage or preclude fire access to the building sides or rear yard.

# **Proposed Zoning:**

### COTTAGE HOMES

Final Plat Numbers: 62, 67-71, 76-79, 339-343, 354-390, 400-403, 422-425, 466-469, 495-498, 529-532, 997-1008

35' wide by 95' deep 45' wide corner lots alley-access garage



# **Cottage Homes District Locations**

#### Description


Cottage Homes form the second component of alley-loaded single-family lots, and creates transitions from the Garden Homes to the Village Homes. Cottage Home sites contain a minimum of 3,325 square feet and average between 3,400 and 3,500 square feet. Architectural proportions and detailing within the district introduce additional housing styles, sizes and types into the alley-loaded product.

Net Acreage 7.1 acres
Proposed Dwelling Units 72 units

Net Density 10.1 dwelling units/acre

#### **Character Guidelines**

- Balconies, entry bays, and front porches are recommended to enhance the human scale of the public street façade.
- Porches, stoops, and bays are allowed to encroach into the front yard setback to allow for increased porch width and to encourage the inclusion of porches or entry bays onto each house.
- Varied building setbacks are encouraged to create a more organic streetscape in which there are slight variations between buildings along the length of the street.
- As the buildings are moved closer to the street and each other, special attention should be taken to design details, house details, and landscaping to ensure that the public street façade is of proper pedestrian scale.
- Front entries of each house should be oriented towards the public street frontage.
- To ensure that the alley width does not become visually similar to the street width, alley-loaded garages should be set back no more than four feet from the rear property line for exterior lots, and eight feet from the rear property line for interior lots. The varied setback ensures that the entrances to the alley system are clearly defined as an alley and visually separated from the street intersections. This clear




delineation of the alley versus street will help minimize cut through traffic and reduce travel speeds within the alley. This setback will further allow for sufficient space for items such as garbage and snow storage without allowing for additional parking spaces in the alley between the alley and the garage facade.

- One additional parking space outside of the garage may be placed alongside the garage, with any parking beyond three stalls being accommodated on-street.
- Varied garage setbacks along the alley are encouraged to create a more interesting streetscape and avoid cramped, monotonous, and claustrophobic alleyways.

All Cottage Homes along North Star Drive must include a roofed porch element on a portion of the front facade.

## **Lot Schematics**



## COTTAGE HOMES DISTRICT

Revised:

December 13, 2002

#### Description

This district forms a medium density single-family residential district, featuring alley-loaded garages, reduced setbacks, proportioned architectural detailing, and pedestrian focused streetscapes.

### Definition of Family

The definition of family is the definition outlined in <u>Section 28.03(2)</u> Madison General Ordinances for the R-1 district.

#### Permitted Uses

Single Family Detached Homes Detached, Attached Garages

#### Number of Units & Density Standards

Number of Units 72 units
Net Acreage 7.1 acres

Maximum Net Density 10.1 dwelling units/acre

Lot Requirements

Minimum Lot Area 3,325 square feet

Minimum Lot Width 35 feet
Minimum Corner Lot Width 45 feet
Minimum Front Yard Setback 16 feet
Maximum Front Yard Setback 20 feet

Minimum Side Yard Setback 3 feet with a maintenance and access easement to the

adjoining property

Minimum Corner Lot Side Yard Setback 10 feet from the street side right of way

Sum of Side Yard Setbacks 10 feet minimum

Minimum Building Separation

10 feet

Minimum Garage Rear Yard Setback

Maximum Garage Rear Yard Setback

4' on exterior lots
8' on interior lots

Minimum Garage Side Yard Setback 3 feet
Minimum Paved Surface Setback 2 feet
Maximum Building Height 35 feet
Maximum Impervious Surface Ratio 80%
Maximum Floor Area Ratio .70

Off-Street Parking and Loading two off-street stalls minimum

Accessory Building Regulations accessory buildings not allowed, except detached garages

#### Permitted Encroachments

Front porches, balconies, stoops, open porches and covered walkways may encroach a maximum of 6' into a 16-17' front yard setback.

Front Yard Setbacks of 18-20' must utilize 6-8' porch encroachment.

Corner lot porches, and bay windows may not encroach the vision triangle. The triangle is defined by: the intersection of the curbs at the corner, and a point 30 feet back along each curb from the corner.

Roof eaves may not extend over a property line or a utility easement.

Garden walls or fences shall be no more than 4' in height and will require approval by the Architectural Control Committee. Walls and fences located within the vision triangle shall not exceed 30" in height.

Fences located between adjoining homes (bridging the ten foot building seperation) are required to be perpedicular to the property line, and must include a 46" wide gate for fire accessibility.

Plantings or fences installed may not block site drainage or preclude fire access to the building sides or rear yard.

#### **LEGAL DESCRIPTION**

Lots 743, 744 745, 757, 758 and 759, Grandview Commons Replat No. 1, recorded in Volume 60-020B of Plats on pages 102-105 as Document Number 5034529, Dane County Registry, located in the Northwest Quarter of the Northeast Quarter of Section 11 and in the Southwest Quarter of the Southeast Quarter of Section 2, all in Township 7 North, Range 10 East, City of Madison, Dane County, Wisconsin. Containing 62,690 square feet (1.439 acres).

02/16/15