

Project Engineer Lisa Coleman 266-4093 Icoleman@cityofmadison.com **Project Limits Gregory Street** Baltzell Street to Sheldon Street Knickerbocker Street Gregory Street to Monroe Street Sprague Street Gregory Street to Monroe Street Sheldon Street Fox Avenue to Sprague Street Street **Existing Proposed** Project Type Reconstruction Last Surfaced Gregory 1979, Knickerbocker 1988, Sprague 1988, Sheldon 1988, 1995 Pavement Rating (out of 10) Gregory 3-4, Knickerbocker 3, Sprague 3-4, Sheldon 4-6 Curb Rating (out of 10) Gregory 3-4, Knickerbocker 2, Sprague 2, Sheldon 2-5 Widths Gregory 28', Knickerbocker 24', Sprague 24', Sheldon 28' Square up Sprague/Sheldon intersection Surface Type Asphalt Pavement over concrete Asphalt Pavement Sidewalk

Work Required: Replace existing sections of sidewalk as needed, no new walk

Storm Sewer	Existing	Proposed
Work Required	Replace older pipe & inlets as needed.	
Design Storm		10 year
Size	Varies, 12 inch to 3'x2' box	Varies
Material	Clay	Concrete
Year Installed	1921, 1923, 1950	2017
Sanitary Sewer	Existing	Proposed
Work Required	Complete Replacement (main & laterals to property lin	e)
Size	6-8 inch	8 Inch
Material	Clay	PVC
Year	1922-1923	2017
Water Main	Existing	Proposed
Work Required	Complete Replacement	-
Size	6-8 Inch	8 inch
Material	Cast Iron	Ductile Iron
Year	1916	2017
Rain Gardens	Existing	Proposed
Rain Gardens	none	at Request of Prop Owner
		on Knickerbocker, Sprague, Sheldon
		at suitable sites, must sign waiver.
Parking	Existing	Proposed
Parking Conditions	Parking on both sides Gregory, Sprague, Sheldon	Similar to existing
-	Parking on one side Knickerbocker	-
Street Lighting	Existing	Proposed
Street Lighting	On Wood Poles	no change

Cost

Total Cost \$3,775,600
Adjacent Property Assessments \$480,410
City Share \$3,295,190

Assessment Policy

Street Concrete Items (where existing) Owner 50% / City 50% Sanitary Sewer Lateral Replacements Owner 25% / City 75%

Terrace Stairs Owner 100% Private Storm Sewer Connects Owner 100%

Rain Gardens \$100 cost to owner if owner decides to participate

Assessments payable in one lump sum or over a period of 8 years, with 3% interest charged on unpaid balance All remaining contract items to be paid for by the City of Madison

Schedule

Mail Estimates of Assessments
Bid Contract
Tentative Start Date
Duration of Project
Duration Start Date
Duration of Project
Duration Date
Duration Date
December 2, 2016
January 13, 2017
March 27, 2017
Approx 5 months

Traffic Calming Asphalt speed humps Concrete Speed Humps (same locations)

Traffic Detours Project area open to local traffic only

See reverse for map

