EXHIBIT A

(not to scale)

EXISTING GENERATOR BUILDING BUILDING TO REMAIN

EXISTING MAN GATE TO REMAIN

EXISTING HVAC UNIT. TYP OF 2

EXISTING TRANSMITTER BUILDING BUILDING TO REMAIN

NEW AUTOMATIC TRANSFER SWITCH TO BE MOUNTED TO INSIDE OF EXISTING SHELTER. SEE DETAIL 5/E-2

EXISTING 12'-0" DOUBLE SWING GATE TO REMAIN

EXISTING SIDEWALK

EXISTING 280'-0" SELF-SUPPORT TOWER

EXISTING CHAINLINK FENCE TO REMAIN

EXISTING GRASS AREA

EXISTING ICE BRIDGE, TYP OF 2

NEW UNDERGROUND ELECTRICAL CONDUIT FROM NEW GENERATOR TO NEW AUTOMATIC TRANSFER SWITCH WITHIN VERIZON SHELTER SEE DETAIL 4/E-2

NEW 10'-0" X 15'-0" LEASE AREA

NEW 60KW, 120/208, 1 PHASE NATURAL GAS GENERATOR

NEW 8'-6" X 4'-6" CONCRETE PAD FOR NEW NATURAL GAS GENERATOR, SEE 2 & 3/C-2 FOR DETAILS

CADWELD NEW #2 AWG TO EXISTING TOWER GROUND RING

EXISTING VERIZON EQUIPMENT SHELTER TO BE UTILIZED

EXISTING SIDEWALK

5'

ENLARGED SITE PLAN ①
SCALE: 1"=15'-0"

NORTH