

**Official Project Name****Project Engineer** Mike Cechvala (266-4913)**Project Limits** Jenifer Street from Williamson to Spaight  
Livingston Street from Williamson to South End

<b>Street</b>	<b>Existing</b>	<b>Proposed</b>
Project Type	(Jenifer, Livingston)	Reconstruction (curbs remain on Livingston)
Last Surfaced	1977, 1976	
Pavement Rating	3,5	
Curb Rating	5,8	
Width	40', 30'	40', 30'
Surface Type	Asphaltic (except for cul de sac)	Asphaltic

<b>Sidewalk</b>	<b>Existing</b>	<b>Proposed</b>
Work Required	5'-4" Concrete	Replace As Necessary

<b>Storm Sewer</b>	<b>Existing</b>	<b>Proposed</b>
Work Required		Little to none
Design Storm		10 Year
Size	No storm mains, concrete flume	N/A
Material	VC	Concrete
Year	1894-1909	2008

<b>Sanitary Sewer</b>	<b>Existing</b>	<b>Proposed</b>
Work Required		Complete Replacement
Size	6 Inch (Substandard)	8 Inch
Material	VC	PVC
Year	1905	2008

<b>Water Main</b>	<b>Existing</b>	<b>Proposed</b>
Work Required		Complete Replacement
Size	Double 4" & 8", 6"	8", Single main on Jenifer
Material	Ductile Iron	PVC
Year	1900-1921, 1928	2008

<b>Parking</b>	<b>Existing</b>	<b>Proposed</b>
Parking Conditions	J - Both sides summer, alt. side winter 8-4 L - South side	Same Same

<b>Street Lighting</b>	<b>Existing</b>	<b>Proposed</b>
Street Lighting	On Steel Poles	Same

<b>Cost</b>	
Total Cost	\$885,600
Adjacent Property Assessments	\$46,651
City Share	\$838,949

**Assessment Policy**

Street Concrete Items Owner 50% / City 50%  
 Sanitary Sewer Lateral Replacemer Owner 25% / City 75%  
 Assessments payable in one lump sum or over a period of 8 years, with 5% interest charged on unpaid balance  
 All remaining contract items to be paid for by the City of Madison

**Schedule**

Start Date 2-Jun-08  
 Length of Project 3 Months

**Traffic Calming** Not Included

**Traffic Detours** Street will remain open to local traffic only with driveway closings of no more than 20 days. Williamson Street will be open for the majority of the project with minor delays and will have several weekends of one lane operation with flaggers for sewer construction. A bus detour is planned using Paterson Street.

**Real Estate Requirements** Not Required**Correspondence** Kemper Maas, 732 Jenifer Street, How will parking be addressed?