

Badger Rusk Shared-Use Path & N. Rusk Avenue Assessment District – 2025

Project Engineer Reid Stiteley 608-266-4093 Alder: Knox Jr. (14)

Project Limits W. Badger Rd from pedestrian overpass to N. Rusk Ave
N. Rusk Ave from W. Badger Rd to Nygard St

Street	Existing	Proposed
Project Type: Reconstruction & Path		
Last Surfaced	Surfaced 1993 (W. Badger Rd) Surfaced 1996 (N. Rusk Ave)	2025
Pavement Rating	7 out of 10 (W. Badger Rd) 3 out of 10 (N. Rusk Ave)	Replace asphalt pavement
Curb Rating	3 out of 10 (W. Badger Rd)	Install new curb and gutter on N. Rusk Ave and north side of W. Badger Rd
Surface Type	Asphalt	4.5" Asphalt
Width/Lanes	36' / 2-way traffic (W. Badger Rd) 32' / 2-way traffic (N. Rusk Ave)	26' / 2-way traffic (W. Badger Rd) 32' / 2-way traffic (N. Rusk Ave)

Shared-Use Path	Existing	Proposed
Last Surfaced	N/A	2025
Surface Type	N/A	3" Asphalt
Width	N/A	10' off-street path

Storm Sewer	Existing	Proposed
Work Required: Replace storm sewer main and inlets as needed		
Size	12" & 24"	12", 15", & 24"
Material	RCP	RCP
Year	1980-1988	2025

Sanitary Sewer	Existing	Proposed
Work Required: Replace sanitary main and laterals (N. Rusk Ave only)		
Size	8"	8"
Material	Vitrified Clay	PVC
Year	1969	2025

Water Main	Existing	Proposed
Work Required: No water work is planned		
Size	12'	N/A
Material	Ductile Iron	N/A
Year	1969	N/A

Parking
Existing Parking Conditions: Parking on west side of N. Rusk Ave
Proposed Parking: Parking to remain on west side of N. Rusk Ave

Lighting & Signals	Existing	Proposed
Street Lighting	On utility maintained poles	Existing street lights to remain
Path Lighting	N/A	Install lighting for shared-use path
Signals	N/A	Install RRFB (W. Badger Rd)

Tree Removals
2 planned tree removal due to path conflicts:
56 Sirloin Strip – Sugar Maple and 56 Sirloin Strip – Black Cherry

Costs

Total Cost	\$1,614,835.75
Adjacent Property Assessments	\$73,171.58
Federal Funding	\$666,960.00
City Share	\$874,704.17

Assessment Policy

Assessment Policy Item	City Share	Property Owners' Share
10' Pavement Replacement*	0%	100%
Asphalt Pavement - Remaining Width	100%	0%
Shared-Use Path	100%	0%
Driveway Aprons	50%	50%
Curb & Sidewalk	0%	100%
Sidewalk Ramps	100%	0%
Path Lighting & Signals	100%	0%
Sanitary & Storm Sewer Main	100%	0%
Sanitary Laterals to Property Line	75%	25%
Private Storm Sewer Connections	0%	100%

*Pavement Replacement assessed per linear ft. of frontage

Assessments payable in one lump sum or over a period of 8 years, with 5% interest charged on unpaid balance

Alder Knox Jr. has requested the Board to consider extending the standard 8 year pay back period to up to 15 years for this project.

Schedule

Anticipated Start Date June 2025
Project duration Approximately 4 Months

Correspondence

None

