Rockstream Drive Assessment District Project Engineer	t - 2020 Andrew Zwieg ph: 266-9219 email: azw	vieg@cityofmadison.com
Project Limits	Rockstream Dr Extension to Maple Grove Dr and Ambleside Dr to extended to Rockstream Dr (see map on reverse)	
Alder: 7 Moreland		
Street	Existing	Proposed
Project Type: New street construction.		
Last Surfaced	NA	NA
Pavement Rating	NA	New Pavement
Curb Rating	NA	New Curb & Gutter
Width	NA	Varies 32'-36'
Shoulder	NA	None
Surface Type	NA	Asphalt
Sidewalk & Terraces		
Terraces	NA	Varies 7'-9' RT & 9'-11' LT
Sidewalks	NA	10' shared-use path west side of Rockstream, 5' sidewalk east side; Ambleside 5' sidewalk on both sides
Storm Sewer	Existing	Proposed
Work Required: Install new storm sewer.	<b>J</b>	· F · · · · ·
Size	NA	New Pipes
Material	NA	Concrete
Year	NA	2020
Storm Water	Existing	Proposed
Work Required: Install new storm sewer to ca		
Biofiltration Basins	NA	The storm water will enter a new ponds constructed along Rockstream Drive by a developer as part of contract #8402. Stormwater at the intersection of Rockstream Drive and Ambleside Drive will enter Badger Mill Creek.
Sanitary Sewer	Existing	Proposed
Work Required: Install new sanitary sewer.		
Size	NA	New 8" Pipes
Material	NA	PVC
Year	NA	2020
Water Main	Existing	Proposed
Work Required: Relocate a portion of existing		
Size	8" Pipes	8" Pipes
Material	Ductile Iron	Ductile Iron
Year	2003	2020
Parking		
Existing Parking Conditions: NA Proposed Parking: Parking On Both Sides of t	he Street	
		Burnard
Street Lighting	Existing NA	Proposed  New Street Lights (Alliant Energy Owned)
Area Street Lighting Pedestrian Lighting	NA NA	NA
<b>5 5</b>	IVA	IVA
Land Purchases Street right-of-way has been purchased.		
, ,		
Trees		
developed and driveway entrances are establ		ntings planned. Trees will be planted once the lots are
Assessment Policy	Ourses 4000/ / Ott - 00/*	
Asphalt Pavement/Gravel Base	Owner 100% / City 0%*	
Curb & Gutter Sidewalk	Owner 100% / City 0%* Owner 100% / City 0%*	
Sidewaik Driveway Aprons	Owner 100% / City 0%* Owner 100% / City 0%*	
Street Lighting	Owner 100% / City 0% Owner 100% / City 0%*	
Sanitary Sewer	Owner 100% / City 0% Owner 100% / City 0%*	
Water Main	N/A	
Water Main Laterals	N/A	
Storm Sewer/Storm Water Management	Owner 33.33% / City 66.67%*	
Assessments payable in one lump sum or over	er a period of 8 years, with 3% interest charge hich will incur a cost to be paid. The assessm	d on unpaid balance ents that are due for these properties were separately
Schedule		
Advertise for bids	Fall 2020	
Anticipated Construction Start	March 2020	
Approximate Duration	Approx. 6 months	

Costs

Total Cost: \$2,320,000.00 Assessments: \$1,730,496.77 City Engineering Cost: \$589,503.23

## Correspondence

