



LANDSCAPING NOTES:

1. CONTRACT IS IN A FLOOD WAY. NO ADDITIONAL FILL MAY BE ADDED EXCEPT AS NOTED ON THE GRADING PLAN.
2. THE CONTRACTOR SHALL PARK ALL EQUIPMENT IN THE SOUTHEAST CORNER OF THE PARKING LOT DURING NON WORK HOURS.
3. SEE SPECIAL PROVISIONS FOR LANDSCAPE WATERING, DROUGHT, MAINTENANCE, AND WARRANTY REQUIREMENTS.
4. ALL PLANTING BEDS SHALL HAVE RIVER WASHED STONE MULCH OVER FILTER FABRIC AND ALUMINUM EDGING STAKED IN PLACE, SEE DETAIL 4 SHEET 7. MATCH EXISTING COLORS AND STYLES

Contract 6895 Landscaping Schedule

SYMBOL	BOTANICAL NAME	COMMON NAME	INSTALLED SIZE	ROOT	MATURE SIZE	QTY.	Remarks
AF	<i>Acer x freemanii</i> 'Sienna'	Sienna Glen Freeman Maple	2" Cal.	B.B.	50' H x 35' W	2	new
AR	<i>Acer rubrum</i> 'Autumn Spire'	Autumn Spire Red Maple	2" Cal.	B.B.	50' H x 35' W	1	new, see note 2
QM	<i>Quercus rubra</i>	Northern Red Oak	2" Cal.	B.B.	50' H x 35' W	5	new
X3		Existing Crabapple				1	see notes 1 & 3
JL	<i>S. reticulata</i> 'Ivory Silk'	Ivory Silk Japanese Tree Lilac			15' H x 25' W	7	new
JB	<i>J. virginiana</i> 'Blue Arrow'	Blue Arrow Juniper	4-5' High	5 Gallon	10-12' H x 3-4' W	29	new
JS	<i>Juniperus sabina</i> 'Buffalo'	Buffalo Savin Juniper	12-18" High	Container	18" H x 5' W	8	new
GS	<i>S. japonica</i> 'Goldmound'	Goldmound Spirea	1' H	Container	2' H x 2' W	6	new
WS	<i>S. albiflora</i>	Japanese White Spirea	1' H	Container	2' H x 2' W	6	new

1. Existing trees damaged by drought conditions need to be replaced to meet landscaping requirements of the Zoning Ordinance.
2. Existing Maple tree has been removed, install new type "AR" as indicated on the landscape plan.
3. Remove existing dead Crabapple tree, replace with one type "JL" Ivory Silk Japanese Tree Lilac.