Blue Harvest Lane, Feather Edge Drive, & Soaring Sky Run Assessment District - 2023

Project Engineer Reid Stitelev 608-266-4093 Alder: Duncan (District 1)

Project Limits Blue Harvest Ln (new) & Feather Edge Dr (extension): Meadow Rd to Soaring Sky Run

Soaring Sky Run (extension): Feather Edge to undeveloped lot

Existing Street Proposed Project Type: New Construction

Soaring Sky Run - 2019 (crack seal) Last Surfaced Extend

Pavement Rating 8 out of 10 Extend pavement Curb Rating 9 out of 10 Extend curb Surface Type Asphalt Asphalt Width/Lanes 28' - 2 way Match Existing

Sidewalk

Install new sidewalk along south side of Feather Edge Dr. Extend existing sidewalk on Soaring Sky Run.

Shared-Use Path

Install new 10' asphalt path from Mid Town Rd to north Municipal Limits, connect spur to Soarking Sky Run, and along south side of Blue Harvest Ln to Meadow Rd.

Install new storm on Blue Harvest In and Feather Edge Dr. Extend existing storm, install new box culvert, and install stormwater basin on Soarking Sky Run. Install new

pipe culverts for shared-use path.

12", 15", 18", 24", 3'x6' box culvert

Material RCP RCP Year 2004 2024

12"

Existing Sanitary Sewer Proposed

Extend sanitary main on Soaring Sky Run. 12" 8" Size PVC PVC Material Year 2012 2024

Water Main **Existing** Proposed

Extend water main on Soaring Sky Run. 8" 8" Material Ductile Iron Ductile Iron 2002 2024 Year

Parking

Existing Parking Conditions: On-street parking adjacent to curb

Proposed Parking: Parking on both sides

Existing Street Lighting & Signals Proposed URD Street Lighting (Alliant) Install lighting for shared-use path. Separate URD Street lighting by Alliant Street Lighting Signals None None Tree Removals

No anticipated removals at this time

Costs

Total Cost \$2,174,000.00 Adjacent Property Assessments \$145,946.08

Future City Parks Asessment (single parcel) City Share \$2,028,053.92

Assessment Policy

New street construction 50% of new street

Assessments payable in one lump sum or over a period of 8 years, with 4% interest charged on unpaid balance

Schedule

Anticipated Start Date Spring 2024

Approximately 5 Months Project duration

Correspondence None See attached project map