ALLIANT ENERGY(ELECTRIC)

ICE AGE JUNCTION PATH

CG-30D TYP

EX R/W

EX R/W

R/L PNR LOOP

CG-30D MOUNTABLE

SEE LANDSCAPING PLANS FOR TREE AND PLANTER AREAS DETAILS

PARK AND RIDE LOT

APPROX. 9 STALLS (1 ACCESSIBLE)
EV READY: 1 EV STALL TO BE INSTALLED WITH PROJECT.

CG-18D TYP, INTERIOR ISLANDS

MAINTENANCE VEHICLE PARKING AREA

CURB BOX

ELECTRICAL

COMFORT STATION

SAN SERVICE
INV: 1063.99'

BIKE RACKS

2" COPPER SERVICE LATERAL

CG-30D

CG-30A

BUS SHELTER

CITY BUS

TRANSIT AREA

ARTICULATED BRT BUS

SAS#2

SAS#1

SAS2156-008

R/L PNR

PROPOSED WET POND

PROPOSED INFILTRATION CELL #1

PROPOSED INFILTRATION CELL #2

STORM SEWER CONTINUES NORTH

CONNECT TO EXISTING WATER MAIN STUB

CG30ID

MARKINGS FOR BUS POSITIONING AND BYPASS MOVEMENT (TYP)

MADISON GAS AND ELECTRIC (ELECTRIC)

MATCH EXISTING SIDEWALK

SAS2156-008
EX RIM ELEV: 1071.84
PROP RIM ELEV: 1072.33
S 8"PVC IE: 1057.34
E 8" PVC IE: 1057.14

SANITARY SEWER LATERAL CONNECTION, ADJUST MANHOLE RIM TO GRADE

SIGNALIZED INTERSECTION

MADISON WATER UTILITY (WATER)

CHARTER (FIBER OPTIC)

MINERAL POINT TO JUNCTION ROAD CONNECTOR

SITE PLAN LEGEND

- REINFORCED CONCRETE PLATFORM
- CONCRETE PLATFORM RAMP, SLOPED WALKWAY
- CONCRETE PAVEMENT, SEE GENERAL NOTES FOR STRUCTURE
- X-INCH HMA PAVEMENT
- X-INCH CONCRETE PAVEMENT, COLORED RED
- CONCRETE SIDEWALK 5-INCH
- CONCRETE SIDEWALK 7-INCH
- SODDING
- RAILROAD CROSSING TREATMENT
- CURB RAMP DETECTABLE WARNING FIELD NATURAL PATINA
- ADA CLEAR AREA (PAID AS SIDEWALK)
- LOCAL ROUTE BOARDING AREA
- X-INCH CONCRETE, COLORED AND STAMPED
- TREES

CD	CONCRETE DRIVEWAY 7-INCH
G-24	CONCRETE GUTTER 24-INCH (PAVED INTEGRAL TO LANE, SEE DETAIL)
CGXXID	CONCRETE CURB & GUTTER INTEGRAL XX-INCH TYPE D
CG30IJ	CONCRETE CURB & GUTTER INTEGRAL 30-INCH TYPE J (MOUNTABLE)
CG-XX	TYPE XX CONCRETE CURB & GUTTER
CP	CONCRETE CURB PEDESTRIAN
CPE6 CPE24	CONCRETE CURB PLATFORM EXTENSION 6-INCH OR 24-INCH
CS	CONCRETE STEPS
BR	BICYCLE RACK CONCRETE-MOUNTED
AP	HMA PAVEMENT

MARK	REVISION	DATE	BY

Designed By: AECOM Date: 2022-07-14 Scale: 1 IN:50 FT
60631225P

60631225P

CITY OF MADISON, DANE COUNTY, WI

CONTRACT NO: 60631225C

SITE PLAN: WESTERN TERMINAL

BUS RAPID TRANSIT

CITY OF MADISON

60631225P

P-0W

FILE NAME : C:\PWWORKING\AECOM_DS20_NA_2019\JESSICA.LANCELLE@AECOM.COM\DMS86348\05020B-PN.DWG
LAYOUT NAME - Plan 1 IN 50 FT
LAST PLOT DATE - 2022-07-14