



**Official Project Name** Cherokee Dr Utilities with Resurfacing Assm't Dist-2013

**Project Engineer** LeAnne Hannan 266-4057

**Project Limits** Midvale Blvd-Nakoma Rd  
Ald. Brian Solomon

<b>Street</b>	<b>Existing</b>	<b>Proposed</b>
Project Type		Resurfacing
Last Surfaced	2000	
Pavement Rating	4, 5	
Curb Rating	6	
Width	16 & 20 in boulevard, 32 in undivided	same
Surface Type	Asphaltic	Asphaltic
Traffic (Average Vehicles per Day)	Not available	Same

<b>Sidewalk</b>	<b>Existing</b>	<b>Proposed</b>
Work Required		Replace As Necessary

<b>Storm Sewer</b>	<b>Existing</b>	<b>Proposed</b>
Work Required		relocate from median to street between Midvale & Waban, add. Install at Oneida to prevent runoff into park
Design Storm		10 Year
Size	12" & 36" Arch	54" (Midvale-Waban) 27" (Oneida)
Material	RCP & ARCH	RCP
Year	1950 & 1953	2013

<b>Sanitary Sewer</b>	<b>Existing</b>	<b>Proposed</b>
Work Required		no work
Size	18-20", 8"	
Material	VP PVC	
Year	1935 & 2000	

<b>Water Main</b>	<b>Existing</b>	<b>Proposed</b>
Work Required		Replace 4" main (Yuma to Chippewa EB) new main (Waban to Yuma EB) and eliminate alley main
Size	4", 6", 8"	8 Inch
Material	SPCI_UL, SAND CAST IRON	
Year	1931, 1933, 1937, 1949	2013

<b>Parking</b>	<b>Existing</b>	<b>Proposed</b>
Parking Conditions	Parking Both Sides	Same

<b>Street Lighting</b>	<b>Existing</b>	<b>Proposed</b>
Street Lighting	On MG&E wood poles	Same

**Cost**

Total Cost	\$1,140,000
Adjacent Property Assessments	\$74,340
City Share	\$1,065,660

**Assessment Policy**  
 Street Concrete Items Owner 50% / City 50%  
 Assessments payable in one lump sum or over a period of 8 years, with 3% interest charged on unpaid balance  
 All remaining contract items to be paid for by the City of Madison

**Schedule**

Start Date	17-Jun-13
Length of Project	2-2.5 months

complete before school starts

**Traffic Calming** Not Included

**Traffic Detours** none

**Real Estate Requirements** Not Required

**Tree Information**

trimming prior to construction, if any removals are required,  
property owner will be contacted

**Correspondence**

---

4030 Cherokee--asked for explanation of assessment and we identified  
an error which was corrected.

4110--questioned why sidewalk was to be replaced, it is heaved and the red  
granite sidewalk cannot be sawcut so it must be replaced.

4218--general questions and identified that they will need handicap access