

Contract Name

CANNONBALL PATH PHASE 1 AND WATER MAIN - 2010

Date

2/23/2011

Change Order No.

CO 2

Contract No.

6133

Project No.

53W0499

Change Order Project No.

53W0499

Change Order Description

Additional work needed to complete the project, but was not included in the bid items.

Account Numbers for this Change Order:

EW01-68273-810455-00-53W0499

Contractor SPEEDWAY SAND &amp; GRAVEL INC

8500 GREENWAY BLVD #202

MIDDLETON, WI 53562

You are authorized and directed to make the following changes in this contract:

Item No.	Description	Est. Qty	Unit	Unit Price	*N/B	Total
1	Furnish & install 10" Valves (See Attached)	2.00	EA	2,200.00	N	4,400.00
2	Furnish & install 10" Pipe (See Attached)	16.00	LF	120.00	N	1,920.00
3	Abandon Curb Box (See Attached)	1.00	EA	150.00	N	150.00
4	Additional Directional Drill (See Attached)	75.00	LF	337.82	N	25,336.50
5	Additional 12" Fittings (See Attached)	6.00	EA	1,230.00	N	7,380.00
6	Check Dams (See Attached)	2.00	EA	75.00	N	150.00
7	3" Clear Stone (See Attached)	15.90	TON	13.00	N	206.70
8	Grinding (See Attached)	2.00	HOURL	220.00	N	440.00
9	Overlay (See Attached)	135.00	SY	22.00	N	2,970.00
Net Change Order						42,953.20
The Original Contract Total						1,333,394.35
Sum of previous Change Orders						31,999.00
The new Contract Sum including this Change Order will be						1,408,346.55

This Contract is a:

Original Contract Time/Completion Date

Net Change in Contract Time by previous change order

Contract Time/Completion Date prior to this change order

Additional day(s) as a result of this Change Order

Contract time/completion date as a result of this change order

Calendar Days

Working Days

Completion Date

June 1, 2011

June 1, 2011

June 1, 2011

\* Mark if negotiated (N) or bid (B) unit price

Contractor's Acceptance

By

Title

Date

City's Approval (see reverse side for instructions)

Construction Inspector

Construction Supervisor

Engineer

Board of Public Works

OK  
MRO  
2/24/2011  
RA

Cannonball Path Ph. 1 and Water Main - 2010  
Contract #6133  
Change Order No. 2

Item #1: Furnish and install 10" valves – Two 10" valves were installed on the existing 10" water main on Post Rd. of the direction of the engineer for testing purposes.

Item #2: Furnish & install 10" pipe – A portion of existing 10" main was required to be cut out and replaced due to item #1.

Item #3: Abandon curb box – An old curb box was discovered on Sandwood Dr. that was no longer in use.

Item #4: Additional directional drill – The directional drill had to be extended due to poor soil condition and the restrictions of the project.

Item #5: Additional 12" fittings were needed due to a conflict with storm sewer.

Item #6: Check dams were added for erosions control on Sandwood and Westview.

Item #7: Clear stone for the check dams (item #6).

Item #8 & Item #9: Due to the work in Grandview and the age of the pavement, it was required to grind and overlay the pavement on this street.