

## SUMMARY OF PUBLIC WORK STANDARD SPECIFICATION REVISIONS TE – 2025

### STANDARD SPECIFICATIONS

611 Traffic Signal Controller Cabinet  
Add: Description, Materials, Construction Methods, Measurement and Payment

### BID ITEMS

#### New Items

60257, FURNISH & INSTALL 5 #6 AND 1 #8 WIRES IN EXISTING OR CONTRACTOR-INSTALLED CONDUIT, L.F.

60258, FURNISH & INSTALL 6 #6 AND 1 #8 WIRES IN EXISTING OR CONTRACTOR-INSTALLED CONDUIT, L.F.

60259, FURNISH & INSTALL 2 #8 AND 1 #8 WIRES IN EXISTING OR CONTRACTOR-INSTALLED CONDUIT, L.F.

60260, FURNISH & INSTALL 3 #8 AND 1 #8 WIRES IN EXISTING OR CONTRACTOR-INSTALLED CONDUIT, L.F.

60261, FURNISH & INSTALL 5 #8 AND 1 #8 WIRES IN EXISTING OR CONTRACTOR-INSTALLED CONDUIT, L.F.

60262, FURNISH & INSTALL 6 #8 AND 1 #8 WIRES IN EXISTING OR CONTRACTOR-INSTALLED CONDUIT, L.F.

60270, FURNISH & INSTALL TRAFFIC SIGNAL CONTROLLER CABINET, EACH

#### Revised Items

NONE

#### Deleted Items

NONE

### DETAIL DRAWINGS

#### REVISED DETAIL

SDD 6.04 LOOP LEAD DUCT DETAIL

Revise: Show lead-in under curb.

SDD 6.14 LB-3 BASE DETAIL

Revise: Base bolt circle size.

SDD 6.14A LB-3R BASE DETAIL

Revise: Base bolt circle size.

SDD 6.19 LB-8 BASE DETAIL

Revise: Base bolt circle size.

SDD 6.19A LB-8R BASE DETAIL

Revise: Base bolt circle size.

SDD 6.22 TYPE I HANDHOLE

Revise: Note to sweep/rise all new and existing conduit.

SDD 6.24 TYPE III HANDHOLE

Revise: Note to sweep/rise all new and existing conduit.

SDD 6.25 TYPE IV HANDHOLE

Revise: Note to sweep/rise all new and existing conduit.

SDD 6.26 TYPE V HANDHOLE

Revise: Note to sweep/rise all new and existing conduit.

SDD 6.26A TYPE VII HANDHOLE

Revise: Note to sweep/rise all new and existing conduit.

NEW DETAIL

SDD 6.48 BIKE LOOP DETAIL

DELETED DETAILS

NONE