



Official Project Name Hanson Road
Project Engineer LeAnne Hannan 266-4057

Project Limits Manufacturers Drive to Portage Road
 Note: approximately one half of the frontage is in the Town of Burke
 They have agreed to provide \$57,500 towards cost of improvement, this
 was based on a previous estimate that did not include extending the
 CMP's.

Ald. Joe Clausius

Street	Existing	Proposed
Project Type		Widening pavement
Last Surfaced	1969	
Pavement Rating	4	
Curb Rating	0	
Width	22'	30' w/4' crushed agg. Shoulder
Surface Type	Asphaltic	Asphaltic
Traffic (Average Vehicles per Day)	2300	Same

Sidewalk	Existing	Proposed
Work Required	none	none

Storm Sewer	Existing	Proposed
Work Required		extend
Design Storm		
Size	108"	108"
Material	CMP	CMP
Year	unknown	2010

Sanitary Sewer	Existing	Proposed
Work Required	none	none

Water Main	Existing	Proposed
Work Required	none	none

Parking	Existing	Proposed
Parking Conditions	none	Same

Street Lighting	Existing	Proposed
Street Lighting	MG&E poles	no change

Cost	
Total Cost	\$480,000
Town of Burke	\$57,500
City Share	\$422,500

Assessment Policy
no assessments

Schedule	
Start Date	2-Aug-10
Length of Project	approx 2 months

Traffic Calming Not Included

Traffic Detours none

Real Estate Requirements Not Required

Tree Information trimming prior to construction, if needed

Correspondence none