

Sketchworks
architecture llc

- THE RED SHED SALOON**
- TENANT ALTERATION**
- 508 STATE ST
MADISON, WI 53703**

NEW CONSTRUCTION


EXISTING CONSTRUCTION

- 1 GATE DOOR; BY RAILING MANUFACTURER
- 2 COUNTER PASS - THROUGH; COORDINATE WITH OWNER



[illegible]

© SKETCHWORKS
ARCHITECTURE 2023

A101



PRELIMINARY



A1 BAR
1/2" = 1'-0"

1 DRINKING COUNTER
1/2" = 1'-0"

EQUIPMENT SCHEDULE

NUMBER	QUANTITY	DESCRIPTION	MANUFACTURER	MODEL	DIMENSIONS			ELECTRICAL				GAS		WATER			PROVIDED / INSTALLED (OP-OI-CP-CI)	REMARKS
					WIDTH	DEPTH	HEIGHT	VOLTS	WATTS	AMPS	HP	SIZE	BTU OUTPUT	SANITARY	HOT WATER	COLD WATER		
EQ-001	2	3 COMPARTMENT REFRIGERATOR	BEVERAGE -AIR	MT72-1B	78 3/4"	33 5/8"	79 3/8"	0.3528/160	5,004 Kwh / 24h	13.6	(2) 1/2	7,230	10,845	No	No	No	INSTALLED	
EQ-002	1	GAS GRIDDLE	COOKING PERFORMANCE GROUP	35124GMCBMRNL	52"	32 1/8"	25 7/8"	115	184	1.6	1/3	60,000	80,000	No	No	No	INSTALLED	
EQ-003	1	CONTERTOP FRYER	AVANTCO	AVANTCO F202 30 LB	23"	18"	17"	208/240	5400/2200	26	-	-	-	No	No	No	INSTALLED	
EQ-004	1	REACH-IN DOUBLE REFRIGERATOR	TRUE	T-49-HC	54 1/8"	29 1/2"	83 5/16"	240	3,600	15	-	-	-	No	No	No	INSTALLED	
EQ-005	1	REACH-IN SINGLE REFRIGERATOR	TRUE	T-19FZ-HC	27"	24 1/2"	78 15/16"	-	-	15	-	-	-	No	No	No	INSTALLED	
EQ-006	1	3 COMPARTMENT SINK WITH DRAIN BOARDS	REGENCY	600S3162018G	88"	25 1/2"	44 3/4"	-	-	-	-	-	-	No	No	No	INSTALLED	
EQ-007	2	GLASS RACK	TBD	TBD	24"	25"	34"	-	-	-	-	-	-	No	No	No	INSTALLED	
EQ-008	4	TABLE STORAGE	TBD	TBD	24"	25"	34"	-	-	-	-	-	-	No	No	No	INSTALLED	
EQ-009	2	HAND SINK	TBD	TBD	24"	25"	34"	-	-	-	-	-	-	No	No	No	INSTALLED	
EQ-010	2	ICE BOX	TBD	TBD	24"	25"	34"	-	-	-	-	-	-	No	No	No	INSTALLED	
EQ-011	2	DISH RACK	TBD	TBD	24"	25"	34"	-	-	-	-	-	-	No	No	No	INSTALLED	

EQUIPMENT SCHEDULE REMARKS

NO.	REMARK
1	
2	
3	

EQUIPMENT AND FURNITURE PLAN GENERAL NOTES:

- A. ALL EQUIPMENT SHOWN AND / OR IDENTIFIED IS FOR CONCEPT ONLY. FINAL EQUIPMENT SELECTION TO BE PERFORMED BY TENANT, ARCHITECT AND GENERAL CONTRACTOR.
- B. EQUIPMENT SCHEDULE IS FOR BASIC PROJECT UNDERSTANDING AND IN NO WAY A COMPLETE LIST OF EQUIPMENT AND / OR THEIR SPECIFIC UTILITY REQUIREMENTS.
- C. EACH CONTRACTOR IS RESPONSIBLE FOR PROVIDING FINAL UTILITY SUPPLY TO EACH RESPECTIVE PIECE OF EQUIPMENT.
- D. COORDINATE ALL FURNISHED APPLIANCES AND EQUIPMENT WITH OWNER PRIOR TO FINAL CONSTRUCTION / FABRICATION.

HATCH PATTERN KEY:

NEW CONSTRUCTION


EXISTING CONSTRUCTION

FURNITURE SCHEDULE

NUMBER	QUANTITY	DESCRIPTION	MANUFACTURER	DIMENSIONS			MATERIALS				PROVIDED / INSTALLED (P-OI-CP-C)	REMARKS
				WIDTH	DEPTH	HEIGHT	FRAME	TOP	SEAT	BACK		
1	1	Office Chair	ABC Furniture Co.	18	18	36	Steel	Upholstered	Upholstered	Upholstered		
2	2	Desk	XYZ Woodworks	48	24	30	Wood	Wood	Wood	Wood		
3	1	Bookshelf	DEF Storage Solutions	36	12	72	Wood	Wood	Wood	Wood		
4	1	Table	GHI Furniture Co.	30	18	30	Wood	Wood	Wood	Wood		
5	1	Chair	JKL Furniture Co.	18	18	36	Steel	Upholstered	Upholstered	Upholstered		

FURNITURE SCHEDULE REMARKS

NO.	REMARK
1	
2	
3	



THE RED SHED SALOON

TENANT ALTERATION

**508 STATE ST
MADISON, WI 53703**

Project Status

[illegible]

PROJ. #:	23135-01
----------	----------


© SKETCHWORKS
ARCHITECTURE 2023

EQUIPMENT AND FURNITURE PLAN

AI102

(1


FURNITURE AND EQUIPMENT PLAN

$$1/4'' = 1'-0''$$



PRELIMINARY

GENERAL FINISH NOTES:


- A. ENSURE ALL MANUFACTURERS' RECOMMENDATIONS ARE MET FOR PREPARATION OF SUBSTRATE, INCLUDING MOISTURE CONTENT, CLEANLINESS AND APPLICATION OF PRIMERS IF NEEDED.
- B. INSTALL ADA COMPLIANCE ON ALL FINISH FLOORING HEIGHTS AND TRANSITIONS.
- C. PROVIDE PHYSICAL SUBMITTALS ON ALL COLOR AND MATERIAL SELECTIONS WITH OWNER AND ARCHITECT PRIOR TO CONSTRUCTION.
- D. INSTALL FLOORING UNDER ALL EQUIPMENT AND MILLWORK.
- E. PROVIDE TRANSITION STRIPS TO ALL DISSIMILAR FLOOR MATERIALS. TRANSITIONS OCCURRING AT DOORWAYS, CENTER THE TRANSITION ON OPENING UNLESS NOTED OTHERWISE.
- F. FIELD VERIFY ALL CABINET LAYOUTS AND COORDINATE DIMENSIONS WITH SELECTED APPLIANCES AND FIXTURES. PROVIDE END PANELS AT ALL EXPOSED CABINET ENDS.
- G. ALL, BUT NOT LIMITED TO, ELECTRICAL PANELS, FIRE EXTINGUISHER CABINETS (EXCEPT GLASS AND EXTINGUISHER), GRILLES, WALL / CEILING DIFFUSERS, WALL MOUNTED BOXES, AND ACCESS PANELS TO BE PAINTED THE SAME COLOR AS THE WALL / GWB CEILING WHICH THEY ARE MOUNTED.
- H. CONTRACTOR IS RESPONSIBLE FOR THE EFFECT OF PAINTING / NOT PAINTING ELEMENTS PER CODE REQUIREMENTS. CONTRACTOR TO INFORM ARCHITECT IMMEDIATELY IF THEY FIND THESE ACTIONS IN VIOLATION OF CODE.
- I. ALIGN GROUT LINES IN WALL TILE WITH THE GROUT LINES OF THE FLOOR TILE.
- J. OUTLETS, COVER PLATES, AND SWITCH PLATES ON VINYL WALL COVERING WALLS TO BE COVERED IN EXACT MATCHING VINYL WALL COVERING FOR AN UNINTERRUPTED WALL GRAPHIC.
- K. GENERAL COMMENT: COUNTERTOPS, OR PLASTIC LAMINATE CABINERY TO BE ____ UNLESS NOTED OTHERWISE.



C1 BAR ISLAND - EAST ELEVATION

$$\frac{1}{2}'' = 1'-0''$$


R1 BAR - WEST ELEVATION

$$\frac{1}{2}'' = 1'-0''$$


A1 BAR ISLAND - WEST ELEVATION

$$\frac{1}{2}'' = 1'-0''$$

THE RED SHED SALOON

TENANT ALTERATION

**508 STATE ST
MADISON, WI 53703**

Project Status

[illegible]

PROJ. #:

23135-01

© SKETCHWORKS
ARCHITECTURE 2023


INTERIOR ELEVATIONS

AI201


PRELIMINARY

GENERAL FINISH NOTES:


- A. ENSURE ALL MANUFACTURERS' RECOMMENDATIONS ARE MET FOR PREPARATION OF SUBSTRATE, INCLUDING MOISTURE CONTENT, CLEANLINESS AND APPLICATION OF PRIMERS IF NEEDED.
- B. INSTALL ADA COMPLIANCE ON ALL FINISH FLOORING HEIGHTS AND TRANSITIONS.
- C. PROVIDE PHYSICAL SUBMITTALS ON ALL COLOR AND MATERIAL SELECTIONS WITH OWNER AND ARCHITECT PRIOR TO CONSTRUCTION.
- D. INSTALL FLOORING UNDER ALL EQUIPMENT AND MILLWORK.
- E. PROVIDE TRANSITION STRIPS TO ALL DISSIMILAR FLOOR MATERIALS. TRANSITIONS OCCURRING AT DOORWAYS, CENTER THE TRANSITION ON OPENING UNLESS NOTED OTHERWISE.
- F. FIELD VERIFY ALL CABINET LAYOUTS AND COORDINATE DIMENSIONS WITH SELECTED APPLIANCES AND FIXTURES. PROVIDE END PANELS AT ALL EXPOSED CABINET ENDS.
- G. ALL, BUT NOT LIMITED TO, ELECTRICAL PANELS, FIRE EXTINGUISHER CABINETS (EXCEPT GLASS AND EXTINGUISHER), GRILLES, WALL / CEILING DIFFUSERS, WALL MOUNTED BOXES, AND ACCESS PANELS TO BE PAINTED THE SAME COLOR AS THE WALL / GWB CEILING WHICH THEY ARE MOUNTED.
- H. CONTRACTOR IS RESPONSIBLE FOR THE EFFECT OF PAINTING / NOT PAINTING ELEMENTS PER CODE REQUIREMENTS. CONTRACTOR TO INFORM ARCHITECT IMMEDIATELY IF THEY FIND THESE ACTIONS IN VIOLATION OF CODE.
- I. ALIGN GROUT LINES IN WALL TILE WITH THE GROUT LINES OF THE FLOOR TILE.
- J. OUTLETS, COVER PLATES, AND SWITCH PLATES ON VINYL WALL COVERING WALLS TO BE COVERED IN EXACT MATCHING VINYL WALL COVERING FOR AN UNINTERRUPTED WALL GRAPHIC.
- K. GENERAL COMMENT: COUNTERTOPS, OR PLASTIC LAMINATE CABINERY TO BE ____ UNLESS NOTED OTHERWISE.



C1 LOBBY / BAR - NORTH ELEVATION
1/2" = 1'-0"



C2 LOBBY / BAR - SOUTH ELEVATION
1/2" = 1'-0"




B1 LOBBY / BAR - EAST ELEVATION
1/4" = 1'-0"




A1 DRINK RAIL - ELEVATION
1/2" = 1'-0"



— RELOCATE EXISTING EXTERIOR AWNING AND SIGNAGE;
SEE INTERIOR ELEVATIONS FOR NEW LOCATION



1 REFRIGERATOR



2 DISHWASH - SINK
1/2" = 1'-0"

THE RED SHED SALOON

TENANT ALTERATION

**508 STATE ST
MADISON, WI 53703**

Project Status

[illegible]

PROJ. #:	23135-01
----------	----------

© SKETCHWORKS
ARCHITECTURE 2023

INTERIOR ELEVATIONS

AI202

PRELIMINARY