

HOMBURG

CONTRACTORS, INC.

5590 Monona Drive
Monona, WI 53716-3131
(608) 222-6597
fax (608) 244-9113

June 8, 2010

City of Madison - Engineering
Room 115
210 M. L. King Jr. Blvd.
Madison, WI 53703-3342

The following is a proposed change order to add the UW-Madison duct bank to the University Ave. Campus Drive Intersection project. This proposal is based on plan sheets E101, E102, and E103 dated 5-6-10. No specifications were included. This proposal includes the following items:

- Construction fencing for our work
- Install and remove temporary pedestrian bridge for South side of University
- Remove and replace the existing private light pole
- Sawcut and remove the concrete sidewalk, colored and stamped pavement, and drive apron
- Sawcut and remove bituminous pavement - at parking lot
- Remove standing curb
- Remove 12" RCP, install temporary plastic storm, and reinstall 12" RCP after backfilling duct bank
- Dewatering for our work
- Excavation and backfill for duct bank - import select backfill under pavement and sidewalk
- Shoring for our work
- Temporary support for utilities during trenching
- 6" of clearstone bedding
- Cut into the existing vaults for duct bank tie in
- Dowel rebar into existing vaults - to tie into new ducts
- Waterproof sawn openings, waterproof exterior of duct bank/vault joints
- Duct banks - including; conduit, spacers, paver blocks, rebar, concrete encasement
- Duct bank testing - pull mandrel, clean interior with a brush
- Furnish and install warning tape 12" below the surface
- Necessary overtime, manpower/equipment costs to complete prior to August 20, 2010
- Layout for our work

Lump Sum -----\$164,780.00

Surface Restoration

- 8" basecourse
- Bituminous patching at parking lot
- Standing curb - 6" x 18"
- 5" concrete sidewalk
- 7" concrete apron and sidewalk
- 7" colored and stamped concrete drive pavement
- Concrete testing
- Light pole base
- Reinstall light pole
- Furnish and place topsoil
- Furnish and place bark mulch
- Layout for our work

Lump Sum -----\$12,690.00

Alternate #1 - Replace the existing castings

- Remove standing curb
- Remove and salvage bark mulch and topsoil
- Remove the existing castings
- Install new castings and lids with R1792-JL "UW Primary, and UW Signal" labels
- Pour standing curb - 6" x 18"

Lump Sum -----\$3,550.00

Alternate #2 - Replace the existing casting lids only

- Remove the existing casting lids
- Install new lids with "UW Primary, and UW Signal" labels

Lump Sum -----\$1,200.00

Concrete replacement for sanitary lateral construction

- 7" stamped and colored concrete

Lump Sum -----\$1,650.00

Prices quoted do not include,

- frost excavation
- winter conditions
- rock excavation
- undercut/undercut backfill
- hazardous mat'l handling (asbestos, PCB, refrigerants, fluorescent light fixtures, contaminated soil, etc.)
- plans/permits
- erosion control inspection and maintenance when we are not actively working on-site
- temp. facilities

Please give me a call if you should have any questions.

Sincerely,



Michael R. Hackel, Project Manager
Homburg Contractors, Inc.

An 18% finance charge (1½% per month) per annum will be charged on the unpaid balance on accounts not paid within 30 days

As required by the Wisconsin construction lien law, builder hereby notifies owner that persons or companies furnishing labor or materials for the construction on owner's land may have lien rights on owner's land and buildings if not paid. Those entitled to lien rights, in addition to the undersigned builder, are those who contract directly with the owner or those who give the owner notice within 60 days after they first furnish labor or materials for the construction. Accordingly, owner probably will receive notices from those who furnish labor or materials for the construction, and should give a copy of each notice received to the mortgage lender, if any. Builder agrees to cooperate with the owner and his lender, if any, to see that all potential lien claimants are duly paid.