**Project Engineer** LeAnne Hannan 266-4057

**Project Limits** St. Paul Ave

Ald. Larry Palm

to Worthington Ave

**Existing Proposed** Street

Project Type unimproved improve w/c&g Last Surfaced 1948 **Pavement Rating** 5

**Curb Rating** 0 Width 18 32 Feet Surface Type Asphaltic Asphaltic Traffic (Average Vehicles per Day) 2000 Same

**Proposed** Sidewalk Existing

Work Required Replace As Necessary

**Storm Sewer Existing Proposed** 

add additional storm sewer Work Required 10 Year Design Storm Size 12 & 24 inch 12 - 24 inches

Material unknown Concrete 1958 2007 Year

**Sanitary Sewer** Existing **Proposed** 

Complete Replacement Work Required Size 6 Inch (Substandard) 8 Inch PVC Material VC Year 1943 2007

**Water Main Proposed Existing** 

1948

Work Required spot repairs Size 10 inch VΡ Material

Parking Existing **Proposed** 

**Parking Conditions** Parking Both Sides Same

**Street Lighting Existing Proposed** Street Lighting on wood poles Same (new light added 2006)

Cost

Year

**Total Cost** \$250,475 Adjacent Property Assessments \$70,999 City Share \$179,476

**Assessment Policy** 

Street shared cost, homeowner pays 100% of curb, new drive apron, 4' of roadway

homeowner pays 50% of cost to remove & replace exist. Conc apron

All remaining contract items to be paid for by the City of Madison

Assessments payable in one lump sum or over a period of 8 years, with 5% interest charged on unpaid balance Per Section 5B(6) of the Intergovernmental Agreement between Town of Blooming Grove and City of Madison, the City may assess properties within the Town for the improvement of Rethke Ave and the assessments shall NOT be deferred until the benfited parcel is annexed to the City.

## **Schedule**

Start Date 20-Aug-07 Length of Project 2 months

**Traffic Calming Traffic Detours** none **Real Estate Requirements** Not Required 3 trees may need to be removed. Forestry has been asked to evaluate them **Tree Information** Correspondence Michael Rodriquez

209 Rethke

Not Included

general questions-schedule, when it will be billed, etc.