

Official Project Name	Johns St & Emil St Utilities with Resurfacing Assm't Dist	
Project Engineer	Eric Dundee	266-4913
Project Limits	Johns Street (Olbrich Ave-Cottage Grove Rd)	
Ald. David Ahrens	Emil Street (Damon Rd-west end)	
Ald. John Strasser		
Street	Existing	Proposed
Project Type		Resurfacing
Last Surfaced	1998 (Johns & Emil)	
Pavement Rating	7 (Johns), 5 (Emil)	
Curb Rating	8 - Johns & Emil	
Width	30 (Johns), 36 (Emil)	same
Surface Type	Asphalt	Asphaltic
Traffic (Average Vehicles per Day)	N/A	Same
Sidewalk	Existing	Proposed
Work Required		Replace As Necessary
Storm Sewer	Existing	Proposed
Johns Street		
Work Required		Minor inlets and leads, CIPP
Design Storm		
Size	24"x38" & 15"	12"
Material	HERCP, VP	RCP
Year	1980, 1950	2015
Emil Street		
Work Required		New storm system
Design Storm		
Size		18"
Material		RCP
Year		2015
Rain Gardens	Existing	Proposed
Work Required		none
Sanitary Sewer	Existing	Proposed
Johns Street		
Work Required		Minor inlets and leads, CIPP
Size	10"	15"
Material	VP	PVC
Year	1948	2015
Emil Street		
Work Required		replacement
Size	8"	8"
Material	VP	PVC
Year	1958	2015
Water Main	Existing	Proposed
Work Required		Complete Replacement
Size	6"	8"
Material	Spun Cast Iron	ductile iron
Year	1948, 1957	2015
Parking	Existing	Proposed
Parking Conditions	none	Same
Street Lighting	Existing	Proposed
Street Lighting	On MG&E wood poles	Same

Cost

Total Cost	\$1,812,000	street \$566K, storm \$166K
Adjacent Property Assessments	\$116,435	sanitary \$525K, water \$525K
City Share	\$1,695,565	

Additional Work included in contract:

Stormwater Improv. (Badger Road)	\$420,000
----------------------------------	-----------

Assessment Policy

Street Concrete Items	Owner 50% / City 50%
Sanitary Sewer Lateral Replacements	Owner 25% / City 75%
Assessments payable in one lump sum or over a period of 8 years, with 3.5% interest charged on unpaid balance	
Rain Gardens, if installed	Owner 25% / City 75%
All remaining contract items to be paid for by the City of Madison	

Schedule

Start Date	mid to late March
Length of Project	60-75 day calendar days for each location

Traffic Calming	none
------------------------	------

Traffic Detours	none
------------------------	------

Real Estate Requirements	Not Required
---------------------------------	--------------

Tree Information	None
-------------------------	------

Correspondence

Conducted separate public informational meetings for each project location.