

UDC District 7 - LOI

URBAN DESIGN COMMISSION MEMBERS, This letter provides specific sections of the Urban Design District No.7 text as it applies to the proposed Madison College – South Campus. Specific portions of the zoning text Sec. 33.24(14) are copied below. Design comments are provided following each section in italic text.

(14) Urban Design District No. 7.

- a. Statement of Purpose. The purpose of these design requirements and guidelines is to provide clear direction for how property owners can make improvements to their properties to collectively improve the visual character and safety of Park Street. When applied, they will ensure against fragmented or incompatible development and will help prevent the negative visual and functional impacts of uncoordinated design decisions.

(14) (a) The Madison College - South Campus project will serve as a new anchor facility located at the southern end of Park Street at the entrance to the South Beltline Highway.

- b. Property Included in the District. The District shall include all properties having any frontage on South Park Street between the West Beltline Highway on the south and Regent Street on the north.

(b) The property for redevelopment is currently occupied by the State ETF Building. Located at the southern end of UDC District 7. The new facility will result in a building being built closer to the corner of Badger Road and the South Beltline access from Park Street. Parking will be located on the back side, southerly, side of the new facility.

- d. Basis for Design Review. In reviewing plans for development in the District, the Urban Design Commission shall consider the following requirements and guidelines as may be appropriate. The development shall meet the requirements and conform as much as possible to the guidelines. Both the requirements and guidelines apply to new construction, renovations, additions, and exterior alterations unless stated otherwise for a specific item.

(d) The proposed project is a new facility replacing the existing ETF Building. The project intent is to meet the spirit of UDC District 7 requirements while also meeting the needs of a commuter campus educational facility.

1. Building Setbacks and Orientation.

a. Requirements

- i. New buildings shall have a setback between one (1) to ten (10) feet from the front property line. Where new buildings are designed for existing block faces the building setback shall be consistent with adjoining buildings but shall not exceed ten (10) feet.

209 south water street milwaukee, wisconsin 53204 414 359 3060
2310 crossroads drive suite 2000 madison, wisconsin 53718 608 240 9900
205 north orange avenue suite 202 sarasota, florida 34236 941 444 8845

intelligent designs. inspired results. | www.prarch.com

Partners: Michael P. Brush, Martin P. Choren, Gregg R. Golden, Mark C. Herr, John J. Holz, Nicholas D. Kent, Steven A. Kieckhafer, Scott A. Kramer, Jason W. Puestow, David J. Raysich, Michael H. Scherbel, Larry A. Schneider, Michael J. Sobczak

(d) 1. a. i. The proposed building is moved much closer to the corner of Badger Road and the Park Street access to the South Beltline in comparison to the existing ETF building. This 'at the end' of Park Street project does not meet the setback requirements of the more urban areas along the central Park Street area; but, the building is sited closer to the street while allowing for both expansion and emergency/fire safety access. Outdoor seating and gathering is also provided between the building and the front property line to bring life and interest to the street edge.

- ii. In special cases, such as gas stations, setbacks can exceed ten (10) feet with provisions for walkways and landscaping that make these uses more attractive and inviting.

(d) 1. a. ii. While not a gas station, the proposed facility does serve a commuter/car orientated client community and the need to provide multi-sided access to a facility.

b. Guidelines

- i. The front yard setback should be designed to provide for amenities that will enhance the visual and pedestrian character of the street.

(d) 1. b. i. The façade facing the South Beltline access road from Park Street serves as a highly visible portion of the façade. The remaining three sides of the building are well developed as entries, screened service areas, bike parking and vehicle circulation lanes.

- iii. Walkways should be provided to connect the building entrance to the public sidewalk.

(d) 1. b. iii. New direct pedestrian and bike connections will be developed from the corner of Badger Road and Park Street. This new connection is proposed to both serve this new facility and the Badger Road area.

- iv. The front facade of the building and the primary entrance should face the primary street.

(d) 1. b. iii. New direct pedestrian and bike connections will be development from the corner of Badger Road and Park Street. This new connection is proposed to both serve this new facility and the Badger Road area.

2. Building Massing and Articulation.

a. Requirements

- i. All visible sides of the building shall be designed with details that complement the front facade. Side facades that are visible from the primary street shall receive complementary design attention.

(d) 2. a. i. All sides of the building are developed to the same design level. The palette of materials utilized at the Madison College – Truax Campus is emulated for this new facility; incorporating limestone, glass, metal panel, and brick.

- ii. Blank building walls with little detail or variety along primary facades shall be avoided. Improvements to these buildings shall include details at the street level to create a more comfortable pedestrian scale and character.

(d) 2. a. ii. No 'blank' façade walls are proposed. The use of limestone, glass and metal framing are the main elements used throughout. Canopies are implemented to create a more comfortable pedestrian scale.

- iii. Architectural details at the ground floor shall be provided to enhance the pedestrian character of the street. Details shall include window and door trim, recessed entries, awnings, and/or other features.

(d) 2. a. iii. The use of limestone, glass and metal framing are the main elements used at the pedestrian level. Major entry points are located under canopies, or are recessed into the building form.

- iv. Mechanical equipment shall be screened from view by using screen designs that are architecturally integrated with the building design.

(d) 2. a. iv. All mechanical equipment is screened.

b. Guidelines

- i. "Green" building design that promotes energy efficiency is encouraged.

(d) 2. b. i. Photovoltaic panels are being studied for the roof as a major 'green' element for this building.



ii. For large buildings, variation to the building face design should be provided through the use of materials and color, and/or by dividing the building into bays to break up large facades to create pedestrian interest at the street level. This is particularly important for existing large industrial and commercial buildings on Park Street.
(d) 2. b. ii The use of the Madison College 'standard' building palette combine with articulating major sections of the building serve to break up any large section of façade.

iv. Flat roofs are preferred for new mixed-use and commercial buildings.
(d) 2. b. iv. The majority of the roof is a 'flat' roof with a section of the roof facing Badger Road and Park Street angled up to better frame a main entry and indicate prominence.

v. A positive visual termination at the top of the building should be provided.

viii. Buildings should be designed as creations of their own time. Copying historic appearance and details is discouraged.

(d) 2. b. v. The majority of the roof is a 'flat' roof with a section of the roof facing Badger Road and Park Street angled up to better frame a main entry and indicate prominence.

vii. Buildings should be designed as creations of their own time. Copying historic appearance and details is discouraged.

(d) 2. b. vii. A current palette of materials is used and no copying of a historical style is intended.

xi. Creative architectural designs and details are encouraged so long as designs do not conflict or draw attention away from other buildings in the block.

(d) 2. b. xi. This building does not draw attention to, or away, from other buildings as it will always stand separate from other structures in this design district.

3. Building Height.

a. Requirements.

i. New buildings shall be at least two (2) stories in height, except as provided in Par. 10, 11, 12 or 13 or in the guidelines below.

(d) 3. a. i. The proposed building is a 'tall' two stories in height to a three level building at walk-out locations.

4. Windows and Entrances.

a. Requirements.

ii. Office buildings and other non-retail buildings should have at least forty (40) percent of the street wall devoted to windows.

(d) 4. a. ii. Exterior glazing will meet this requirement.

iii. Windows on the ground floor shall be transparent, and not be darkly tinted, colored or have a mirrored finish.

(d) 4. a. ii. Windows will not be darkly tinted.

b. Guidelines.

i. Building entrances should be designed as the focal point of the front facade.

(d) 4. b. i. Building entrances are designed as focal points to the facades with direct sidewalk access.

ii. Entrances to new buildings or additions located close to the sidewalk should include recessed entries to allow for pedestrian movement.

(d) 4. b. ii. Entries are either recessed or under covered entry points.

5. Materials and Colors.

a. Requirements.

i. Exterior materials shall be durable, high-quality materials and appropriate for external use.

(d) 5. a. i. Only durable, high-quality materials appropriate for an educational facility are being proposed.

b. Guidelines

i. Brick, stone and terra cotta are preferred primary materials for new buildings or additions.

(d) 5. b. i. Only durable materials are proposed.

iii. Color choice should complement the style and materials of the building's facade and provide a pleasing relationship with adjoining buildings.

(d) 5. b. iii. The proposed building stands separate from all other building in this district both in form and in function.

6. Signage.

a. Guidelines.

i. Preferred sign types include building mounted signs, window signs, projecting signs, and awning signs.

(d) 6. a. i. Signage will be wall mounted.

vii. Internally illuminated signs displaying illuminated copy should be designed so that when illuminated, the sign appears to have light-colored copy on a dark or non-illuminated background.

(d) 6. a. vii. Signage will be internally illuminated.

viii. Individually mounted backlit letters are an encouraged form of signage.

(d) 6. a. viii. Signage will consist of individual letters.

7. Parking and Service Areas.

a. Requirements.

i. Off-street parking facilities for new buildings shall be located behind or on the sides of the building and be at least ten (10) feet from the front property line.

(d) 7. a. i. Parking setback from the property line will vary per location in order to meet the need for 250 car stalls.

ii. At least one (1) tree island, planted with a tree and sized and landscaped pursuant to the Zoning Ordinance, shall be provided per twelve (12) parking spaces provided. This requirement is in addition to any other landscaping requirements of the Zoning Ordinance.

(d) 7. a. ii. Up to 12 car stalls will be designed between tree islands.

iii. All trash areas shall be screened from public view.

(d) 7. a. iii. At this time trash holding areas are planned to be within the building.

b. Guidelines.

ii. All parking areas should be well landscaped and appropriately lighted.

(d) 7. b. ii A full landscape plan as prepared by a licensed Landscape Architect will be developed. A full lighting plan as prepared by a lighting engineer will be prepared.

iii. All parking areas should include walkways to allow safe pedestrian access to the building entrance.

(d) 7. b. iii. All walkways from public transit, cars, bikes or pedestrian access is served by paved walkways.

v. Driveways along Park Street should be minimized to improve traffic flow and reduce pedestrian conflicts.

(d) 7. b. v. No driveways are proposed to Park Street

c. Pedestrian areas and customer parking areas should be separated from loading, service, and drive through areas.

i. If possible, trash areas should be located inside buildings.

(d) 7. c. i. Pedestrian walkways are separated from a screened two vehicle service dock. Trash is proposed to be held for removal from inside the building.

8. Landscaping and Open Space.

a. Guidelines.

iv. The use of rain gardens and bio-retention basins to collect runoff and filter pollutants is encouraged, where practical.

(d) 8. a. iv. Bio-retention areas and complete development open spaces is a part of the scope of this project.

v. Landscape islands, open spaces and porous pavements should be provided, where practical, for additional storm water infiltration.

(d) 8. a. v. The use of landscape islands and developed open spaces for students are within the scope of the project.

9. Site Lighting and Furnishings.

a. Requirements.

i. Full cut-off light fixtures shall be used to illuminate the site.

(d) 9. a. i. Full cut-off light fixtures shall be specified.

b. Guidelines.

- i. Pedestrian use areas should be adequately, but not excessively lit. Low-level building and landscape accent lighting is encouraged, where appropriate.

(d) 9. b. i. Low level accent lighting leading to main entry points will be developed.

- ii. Lighting and site furnishings (benches, trash receptacles, bicycle racks, etc.) should be designed to complement the character of the building and provide a pleasing relationship with adjoining properties and the public sidewalk.

(d) 9. b. ii. The site will be fully developed with complementing furniture for all the uses listed.

- iii. Bicycle storage facilities should be located near the building entrance.

(d) 9. b. iii. Bike racks will be designed per City of Madison requirements for quantity, styles and physical spacing.

- iv. Decorative, colored paving is encouraged for walkways and outdoor use areas.

(d) 9. b. iv. The use of decorative, colored paving has not been determined as a proper design element for this project.

Legal Description:

Lot Two (2), Certified Survey Map No. 4778 recorded in the Office of the Register of Deeds for Dane County, Wisconsin on October 10, 1985, in Volume 21 of Certified Survey Maps, Page 120, as Document No. 1903990, located in the City of Madison, Dane County, Wisconsin.


Excepting therefrom the land contained in Warranty Deed, recorded April 13, 2010 as Document No. 4647761.




Madison College - Goodman South Campus Plan Commission Submittal

December 13, 2017






File: W:\2017\170407_Madison College - South Campus\DWG\17-0407_Topo.dwg Layout: Site Plan User: WYSER - Z240 - W/D Plotted: Sep 19, 2017 - 4:01pm



LEGEND

[Symbol]	SIGN
[Symbol]	BOLLARD
[Symbol]	SANITARY MANHOLE
[Symbol]	SEWER CLEANOUT
[Symbol]	GAS VALVE
[Symbol]	FIRE HYDRANT
[Symbol]	WATER VALVE
[Symbol]	STORM MANHOLE
[Symbol]	INLETS
[Symbol]	STORM CATCH BASIN
[Symbol]	UTILITY POLE
[Symbol]	LIGHT POLE
[Symbol]	ELECTRICAL TRANSFORMER
[Symbol]	ELECTRICAL PANEL BOX
[Symbol]	UTILITY PEDESTAL
[Symbol]	UTILITY VAULT
[Symbol]	DECIDUOUS TREE
[Symbol]	PROPERTY LINE (PROVIDED BY OTHERS)
[Symbol]	RIGHT-OF-WAY LINE
[Symbol]	CENTERLINE
[Symbol]	EASEMENT LINE
[Symbol]	BUILDING FOOTPRINT
[Symbol]	EDGE OF CONCRETE
[Symbol]	EDGE OF ASPHALT
[Symbol]	RAILING
[Symbol]	STONE WALL
[Symbol]	SAN SAN SANITARY SEWER
[Symbol]	WAT WAT WATER MAIN
[Symbol]	STM STM STORM SEWER
[Symbol]	GAS GAS NATURAL GAS LINE
[Symbol]	COMM COMM COMMUNICATION LINE
[Symbol]	E E ELECTRIC LINE
[Symbol]	OHE OHE OVERHEAD ELECTRIC LINE
[Symbol]	ASPHALT PAVEMENT
[Symbol]	CONCRETE PAVEMENT
[Symbol]	1240 CONTOUR MAJOR
[Symbol]	1241 CONTOUR MINOR



WYSER
ENGINEERING



801 W. BADGER ROAD
MADISON, WI 53713

MADISON COLLEGE - SOUTH CAMPUS

CITY OF MADISON, DANE COUNTY, WI

Sheet Title: TOPOGRAPHIC & UTILITY MAP

GENERAL NOTES

1. FIELD WORK PERFORMED BY WYSER ENGINEERING, LLC. ON SEPTEMBER 8, 2017.
2. ELEVATIONS ARE BASED ON THE NORTH AMERICAN VERTICAL DATUM OF 1988 (NAVD88).
3. NORTH REFERENCE FOR THIS EXISTING CONDITIONS SURVEY AND MAP ARE BASED ON THE WISCONSIN COORDINATE REFERENCE SYSTEM, NAD 83 (2011) WISCONSIN GRID NORTH.
4. SUBSURFACE UTILITIES AND FIXTURES SHOWN ON THIS MAP HAVE BEEN APPROXIMATED BY LOCATING SURFACE FEATURES AND ACCESSORIES, DIGGERS HOTLINE FIELD MARKINGS AND EXISTING MAPS AND RECORDS.
5. BEFORE EXCAVATION, APPROPRIATE UTILITY COMPANIES SHOULD BE CONTACTED. FOR EXACT LOCATION OF UNDERGROUND UTILITIES, CONTACT DIGGERS HOTLINE, AT 1.800.242.8511 OR 811
6. THIS PARCEL IS SUBJECT TO ALL EASEMENTS AND AGREEMENTS, BOTH RECORDED AND UNRECORDED.
7. FEATURES HAVE BEEN LOCATED BY SURVEYOR IN FIELD THAT MAY HAVE ADVERSE TITLE ELEMENTS. AS TO WHICH ELEMENT ENCROACHMENT, CLAIM OF UNRECORDED EASEMENT, PRESCRIPTIVE EASEMENT, AND SO FORTH CAN NOT BE DETERMINED BY SURVEYOR.

BENCHMARK TABLE		
BM - #	ELEVATION	DESCRIPTION
BM - 1	888.94	TOP NUT OF HYDRANT LOCATED NEAR SOUTHWEST CORNER OF SITE ON EAST SIDE OF PERRY STREET
BM - 2	885.52	TOP NUT OF HYDRANT LOCATED NORTH OF PERRY STREET ENTRANCE TO MADISON FIRE DEPARTMENT STATION #6
BM - 3	882.29	TOP NUT OF HYDRANT LOCATED ON NORTH SIDE OF W. BADGER ROAD IN MEDIAN
BM - 4	878.13	TOP NUT OF HYDRANT LOCATED NEAR FENCELINE AT NORTHEAST CORNER OF SITE


Revisions:

No.	Date:	Description:

Graphic Scale	0' 15' 30' 45'
Wyser Number	17-0407
Set Type	TOPO UTIL MAP
Date Issued	09/19/2017
Sheet Number	V001

DIGGERS HOTLINE
Toll Free (800) 242-8511
Hearing Impaired TDD (800) 542-2289
www.DiggersHotline.com

File: W:\2017\170407_Madison College - South Campus\DWG\17-0407_Civil_Design.dwg Layout: Site Plan User: Don Plotted: Dec 12, 2017 - 4:45pm



LEGEND (PROPOSED)

	PROPOSED PROPERTY BOUNDARY
	EASEMENT
	BUILDING FOOTPRINT
	18" CURB AND GUTTER (PRIVATE)
	ASPHALT PAVEMENT
	CONCRETE PAVEMENT
	STORMWATER TREATMENT FACILITY



- GENERAL NOTES**
1. UNDERLYING SITE CONTOURS AND INFORMATION BASED ON TOPOGRAPHIC & UTILITY DATA AS SURVEYED BY WYSER ENGINEERING ON SEPTEMBER 8, 2017. WYSER ENGINEERING SHALL NOT BE HELD RESPONSIBLE FOR ANY ERRORS OR OMISSIONS THAT MAY ARISE AS A RESULT OF ERRONEOUS OR INCOMPLETE INFORMATION PROVIDED BY OTHERS. CONTRACTOR TO CONFIRM ALL ELEVATIONS, GENERAL DRAINAGE AND EARTHWORK REQUIREMENTS PRIOR TO CONSTRUCTION.
 2. THE BENCHMARK LOCATIONS ARE SHOWN FOR REFERENCE ONLY ON THIS PLAN. THE BENCHMARKS SHALL BE VALIDATED BY LICENSED LAND SURVEYOR PRIOR TO CONSTRUCTION. CONTRACTOR ASSUMES RISK ASSOCIATED WITH BENCHMARK ELEVATIONS UNTIL CONFIRMED.
 3. CONTRACTOR TO OBTAIN APPROPRIATE PERMITS FOR STREET OPENINGS & TO WORK WITHIN THE CITY'S LAND IF REQUIRED.
 4. WYSER ENGINEERING SHALL BE HELD HARMLESS AND DOES NOT WARRANT ANY DEVIATIONS BY THE OWNER OR CONTRACTOR FROM THE APPROVED CONSTRUCTION PLANS THAT MAY RESULT IN DISCIPLINARY ACTIONS BY REGULATORY AGENCIES.
 5. IF ANY ERRORS, DISCREPANCIES, OR OMISSIONS WITHIN THE PLAN BECOME APPARENT, IT SHALL BE BROUGHT TO THE ATTENTION OF THE ENGINEER PRIOR TO CONSTRUCTION SO THAT CLARIFICATION OR REDESIGN MAY OCCUR.
 6. ALL MUNICIPAL UTILITY CONNECTIONS, WORK IN ROW, PUBLIC OUTLOTS AND PUBLIC EASEMENTS SHALL BE IN ACCORDANCE WITH CITY OF MADISON STANDARD SPECIFICATIONS FOR PUBLIC WORKS CONSTRUCTION.

SITE INFORMATION BLOCK:

SITE ADDRESS: 801 WEST BADGER ROAD
 SITE ACREAGE: 194,683 SF (4.47 AC)
 USE OF PROPERTY: COMMERCIAL
 ZONING: COMMERCIAL CENTER (CC - MGO 28.068) AND URBAN DESIGN DISTRICT #7

SETBACKS:
 FRONT YARD: 70% OF STREET FACING BUILDING WALL SHALL BE SETBACK NO MORE THAN 85 FEET
 REAR YARD: 20- FEET
 SIDE YARD: 6- FEET

PARKING REQUIREMENTS: (MGO 28.141(4)(g))
 MINIMUM: 1 PER CLASSROOM + 1 PER 5 STUDENTS BASED ON THE MAXIMUM # OF STUDENTS ATTENDING CLASSES AT ANY ONE TIME - OR - AS ESTABLISHED IN A CAMPUS MASTER PLAN = 246
 MAXIMUM: 1 PER CLASSROOM + 1 PER 3 STUDENTS BASED ON THE MAXIMUM # OF STUDENTS ATTENDING CLASSES AT ANY ONE TIME - OR - AS ESTABLISHED IN A CAMPUS MASTER PLAN = 383

BICYCLE REQUIREMENTS: (MGO 28.141(4)(g))
 1 PER 5 STUDENTS BASED ON THE MAXIMUM # OF STUDENTS ATTENDING CLASSES AT ANY ONE TIME - OR - AS ESTABLISHED IN A CAMPUS MASTER PLAN = 205

NUMBER OF CLASSROOMS: 41
 MAXIMUM # OF STUDENTS ATTENDING CLASSES AT ONE TIME: 1,025

TOTAL NUMBER OF PARKING STALLS: 235
 SMALL STALLS (PERCENT OF TOTAL): 48 (20.4%)
 NUMBER OF STALLS DESIGNATED ACCESSIBLE: 8

TOTAL NUMBER OF BIKE STALLS: 46

MAXIMUM IMPERVIOUS LOT COVERAGE: 85%

EXISTING IMPERVIOUS SURFACE AREA: 100,915 SQ.FT. (51.8%)
 ROOFTOP: 19,010 SQ.FT.
 PAVED: 81,905 SQ.FT.

NEW IMPERVIOUS SURFACE AREA: 139,500 SQ.FT. (71.6%)
 ROOFTOP: 31,190 SQ.FT.
 PAVED: 108,310 SQ.FT.

DISTURBANCE LIMITS: 190,000 SQ. FT.



MADISON COLLEGE
 GOODMAN SOUTH CAMPUS
 CITY OF MADISON, DANE COUNTY, WI


801 WEST BADGER ROAD
 MADISON, WI 53713

Sheet Title: SITE PLAN

Revisions:		
No.	Date:	Description:

Graphic Scale	
Wysen Number	17-0407
Set Type	UDC
Date Issued	12/12/2017
Sheet Number	C100






LEGEND (PROPOSED)

- PROPERTY BOUNDARY
- - - EASEMENT
- ▭ BUILDING FOOTPRINT
- ▬ 18" CURB AND GUTTER
- ▨ ASPHALT PAVEMENT
- ▩ CONCRETE PAVEMENT
- 880 PROPOSED MAJOR CONTOUR
- 882 PROPOSED MINOR CONTOUR
- STM
- 881.25 EP
- - - DRAINAGE GRADE BREAK
- DRAINAGE ARROW

NORTH

- GENERAL NOTES**
1. UNDERLYING SITE CONTOURS AND INFORMATION BASED ON TOPOGRAPHIC & UTILITY DATA AS SURVEYED BY WYSER ENGINEERING ON SEPTEMBER 8, 2017. WYSER ENGINEERING SHALL NOT BE HELD RESPONSIBLE FOR ANY ERRORS OR OMISSIONS THAT MAY ARISE AS A RESULT OF ERRONEOUS OR INCOMPLETE INFORMATION PROVIDED BY OTHERS. CONTRACTOR TO CONFIRM ALL ELEVATIONS, GENERAL DRAINAGE AND EARTHWORK REQUIREMENTS PRIOR TO CONSTRUCTION.
 2. THE BENCHMARK LOCATIONS ARE SHOWN FOR REFERENCE ONLY ON THIS PLAN. THE BENCHMARKS SHALL BE VALIDATED BY LICENSED LAND SURVEYOR PRIOR TO CONSTRUCTION. CONTRACTOR ASSUMES RISK ASSOCIATED WITH BENCHMARK ELEVATIONS UNTIL CONFIRMED.
 3. CONTRACTOR TO OBTAIN APPROPRIATE PERMITS FOR STREET OPENINGS & TO WORK WITHIN THE CITY'S LAND IF REQUIRED.
 4. WYSER ENGINEERING SHALL BE HELD HARMLESS AND DOES NOT WARRANT ANY DEVIATIONS BY THE OWNER OR CONTRACTOR FROM THE APPROVED CONSTRUCTION PLANS THAT MAY RESULT IN DISCIPLINARY ACTIONS BY REGULATORY AGENCIES.
 5. IF ANY ERRORS, DISCREPANCIES, OR OMISSIONS WITHIN THE PLAN BECOME APPARENT, IT SHALL BE BROUGHT TO THE ATTENTION OF THE ENGINEER PRIOR TO CONSTRUCTION SO THAT CLARIFICATION OR REDESIGN MAY OCCUR.
 6. ALL MUNICIPAL UTILITY CONNECTIONS, WORK IN ROW, PUBLIC OUTLOTS AND PUBLIC EASEMENTS SHALL BE IN ACCORDANCE WITH CITY OF MADISON STANDARD SPECIFICATIONS FOR PUBLIC WORKS CONSTRUCTION.

WYSER ENGINEERING



801 WEST BADGER ROAD
MADISON, WI 53713


**MADISON COLLEGE
GOODMAN SOUTH CAMPUS**

CITY OF MADISON, DANE COUNTY, WI


Sheet Title: **DETAIL GRADING PLAN**

Revisions:		
No.	Date:	Description:

Graphic Scale




Wysen Number	17-0407
Set Type	UDC
Date Issued	12/12/2017
Sheet Number	C201




Toll Free (800) 242-8511 -or- 811
Hearing Impaired TDD (800) 542-2289
www.DiggersHotline.com

File: W:\2017\170407_Madison College - South Campus DWG\17-0407_Civil_Design.dwg Layout: Grading Plan User: Dan Plot: Dec 12, 2017 - 4:49pm



LEGEND (PROPOSED)

	PROPERTY BOUNDARY
	EASEMENT
	BUILDING FOOTPRINT
	18" CURB AND GUTTER
	ASPHALT PAVEMENT
	CONCRETE PAVEMENT
	PROPOSED MAJOR CONTOUR
	PROPOSED MINOR CONTOUR
	PROPOSED STORM SEWER
	SILT FENCE
	INLET PROTECTION
	DITCH CHECK



GENERAL NOTES


1. UNDERLYING SITE CONTOURS AND INFORMATION BASED ON TOPOGRAPHIC & UTILITY DATA AS SURVEYED BY WYSER ENGINEERING ON SEPTEMBER 8, 2017. WYSER ENGINEERING SHALL NOT BE HELD RESPONSIBLE FOR ANY ERRORS OR OMISSIONS THAT MAY ARISE AS A RESULT OF ERRONEOUS OR INCOMPLETE INFORMATION PROVIDED BY OTHERS. CONTRACTOR TO CONFIRM ALL ELEVATIONS, GENERAL DRAINAGE AND EARTHWORK REQUIREMENTS PRIOR TO CONSTRUCTION.
2. THE BENCHMARK LOCATIONS ARE SHOWN FOR REFERENCE ONLY ON THIS PLAN. THE BENCHMARKS SHALL BE VALIDATED BY LICENSED LAND SURVEYOR PRIOR TO CONSTRUCTION. CONTRACTOR ASSUMES RISK ASSOCIATED WITH BENCHMARK ELEVATIONS UNTIL CONFIRMED.
3. CONTRACTOR TO OBTAIN APPROPRIATE PERMITS FOR STREET OPENINGS & TO WORK WITHIN THE CITY'S LAND IF REQUIRED.
4. WYSER ENGINEERING SHALL BE HELD HARMLESS AND DOES NOT WARRANT ANY DEVIATIONS BY THE OWNER OR CONTRACTOR FROM THE APPROVED CONSTRUCTION PLANS THAT MAY RESULT IN DISCIPLINARY ACTIONS BY REGULATORY AGENCIES.
5. IF ANY ERRORS, DISCREPANCIES, OR OMISSIONS WITHIN THE PLAN BECOME APPARENT, IT SHALL BE BROUGHT TO THE ATTENTION OF THE ENGINEER PRIOR TO CONSTRUCTION SO THAT CLARIFICATION OR REDESIGN MAY OCCUR.
6. ALL MUNICIPAL UTILITY CONNECTIONS, WORK IN ROW, PUBLIC OUTLETS AND PUBLIC EASEMENTS SHALL BE IN ACCORDANCE WITH CITY OF MADISON STANDARD SPECIFICATIONS FOR PUBLIC WORKS CONSTRUCTION.

CONSTRUCTION SITE EROSION CONTROL REQUIREMENTS

1. ALL EROSION AND SEDIMENT CONTROL PRACTICES SHALL BE IMPLEMENTED IN ACCORDANCE WITH THE CURRENT WISCONSIN DEPARTMENT OF NATURAL RESOURCES (WDNR) EROSION AND SEDIMENT CONTROL TECHNICAL STANDARDS (dnr.wis.gov).
2. EROSION AND SEDIMENT CONTROL MEASURES SHALL BE INSTALLED PRIOR TO SITE DISTURBANCE.
3. ENGINEER / CITY OF MADISON / WDNR HAS THE RIGHT TO REQUIRE CONTRACTOR TO IMPLEMENT ADDITIONAL EROSION CONTROL MEASURES AS NECESSARY. CONTRACTOR MUST NOTIFY THE CITY OF MADISON BUILDING INSPECTOR TWO (2) WORKING DAYS IN ADVANCE OF ANY SOIL DISTURBANCE ACTIVITIES.
4. EROSION AND SEDIMENT CONTROL PRACTICES SHALL BE INSPECTED ONCE PER WEEK AND FOLLOWING ANY RAINFALL EVENT. INSPECTION REPORTING SHALL BE IN ACCORDANCE WITH MUNICIPAL REQUIREMENTS SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR.
5. IT IS THE CONTRACTOR'S RESPONSIBILITY TO MAINTAIN EROSION AND SEDIMENT CONTROL PRACTICES IN WORKING ORDER. EROSION CONTROL MEASURES SHALL BE REMOVED ONLY AFTER SITE CONSTRUCTION IS COMPLETE WITH ALL SOIL SURFACES HAVING AN ESTABLISHED VEGETATIVE COVER.
6. DEWATERING PRACTICES SHALL COMPLY WITH TECHNICAL STANDARD 1061.
7. DUST CONTROL SHALL BE MITIGATED IN ACCORDANCE WITH WDNR TECHNICAL STANDARD 1068.
8. ALL DISTURBED AREAS SHALL BE SEEDED AND MULCHED IMMEDIATELY FOLLOWING FINAL GRADING ACTIVITIES.
9. SEED MIX AND RATE SHALL BE, AT A MINIMUM, IN ACCORDANCE WITH WDNR TECHNICAL STANDARD 1059.
10. PRIOR TO CONSTRUCTION, CONTRACTOR SHALL PROVIDE VEGETATION PLAN FOR ENGINEER / OWNER APPROVAL. VEGETATION PLAN AND BIORETENTION INSTALLATION SHALL BE IN ACCORDANCE WITH WDNR TECHNICAL STANDARD 1004.
11. CONTRACTOR TO PROVIDE SOLID LID OR METAL PLATE ON ALL OPEN MANHOLES DURING CONSTRUCTION TO MINIMIZE SEDIMENT FROM ENTERING THE STORM SEWER SYSTEM.
12. THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING A COPY OF THE MUNICIPAL EROSION CONTROL PERMIT AND WDNR NOI AND FOLLOWING ALL APPLICABLE REQUIREMENTS.

GRADING, SEEDING & RESTORATION NOTES

1. ALL GRADES SHOWN ARE FINAL FINISHED SURFACE GRADES.
2. AREAS TO BE SEEDED SHALL HAVE A MINIMUM 6 INCHES TOPSOIL UNLESS OTHERWISE NOTED.
3. RESTORATION SHALL OCCUR AS SOON AS PRACTICABLE AFTER THE DISTURBANCE, WITHIN 7 DAYS OF TOPSOILING.
4. AREAS NOT RESTORED WITH EROSION MATTING OR OTHER STABILIZATION MEASURES SHALL BE STABILIZED WITH MULCH.
5. APPLY ANIONIC POLYMER TO DISTURBED AREAS IF EROSION BECOMES PROBLEMATICAL.
6. INSTALL EROSION CONTROLS ON THE DOWNSTREAM SIDE OF STOCKPILES AND PROVIDE TEMPORARY SEEDING ON STOCKPILES WHICH ARE TO REMAIN IN PLACE FOR MORE THAN 7 DAYS.
7. CONTRACTOR SHALL CHISEL-PLOW OR DEEP TILL WITH DOUBLE TINES THE STORMWATER MANAGEMENT FACILITY JUST PRIOR TO SEEDING AND MULCHING TO PROMOTE INFILTRATION.
8. CONTRACTOR TO DEEP TILL ALL COMPACTED PERVIOUS SURFACES PRIOR TO SEEDING AND MULCHING.
9. MULCH SHALL BE WEED-FREE STRAW AND SHALL BE INSTALLED AT THE RATE OF 2 TONS PER ACRE PER SECTION 627 OF "STANDARD SPECIFICATIONS FOR HIGHWAY AND STRUCTURE CONSTRUCTION" (WISDOT 2014).
10. PERMANENT SEEDING SHALL NOT OCCUR BETWEEN SEPTEMBER 15TH AND APRIL 15TH. ALTERNATE SEEDING/PLANTING METHODS AND/OR EROSION PROTECTION MAY BE NECESSARY FOR SEEDING/PLANTING THAT OCCURS DURING THAT TIME. COORDINATE WITH THE OWNER AS NECESSARY.
11. TEMPORARY STABILIZATION SHALL CONSIST OF ONE OR MORE OF THE FOLLOWING OPTIONS:
 - a. TEMPORARY SEEDING CONSISTING OF ANNUAL RYE GRASS APPLIED AT A RATE OF 1.5 LBS PER 1000 SQUARE FEET.
 - b. WISDOT PAL CLASS I TYPE B URBAN EROSION CONTROL MAT.
12. ALL SLOPES EXCEEDING 5:1 SHALL USE PRESCRIPTIVE COMPLIANCE INCLUDING SLOPE INTERRUPTION PER WDNR TECH. STD. 1071, SOIL STABILIZATION (PERMANENT SEEDING AND CLASS I, TYPE B EROSION MATTING ON SLOPES OR CLASS II, TYPE B MATTING IN DRAINAGE SWALES) AND LIMITING THE MAX PERIOD OF BARE SOIL TO 60 DAYS FOR LAND DISTURBANCE BETWEEN SEPTEMBER 16 AND MAY AND 30 DAYS FOR LAND DISTURBANCE BETWEEN MAY 2 AND SEPTEMBER 15.



MADISON COLLEGE
GOODMAN SOUTH CAMPUS
CITY OF MADISON, DANE COUNTY, WI
Sheet Title:
GRADING & EROSION CONTROL PLAN


801 WEST BADGER ROAD
MADISON, WI 53713

Revisions:



No.	Date:	Description:

Graphic Scale	
Wysen Number	17-0407
Set Type	UDC
Date Issued	12/12/2017
Sheet Number	C200

DIGGERS HOTLINE
 Toll Free (800) 242-8511 -or- 811
 Hearing Impaired TDD (800) 542-2289
 www.DiggersHotline.com



LEGEND (PROPOSED)



GENERAL NOTES

- UNDERLYING SITE CONTOURS AND INFORMATION BASED ON TOPOGRAPHIC & UTILITY DATA AS SURVEYED BY WYSER ENGINEERING ON SEPTEMBER 8, 2017. WYSER ENGINEERING SHALL NOT BE HELD RESPONSIBLE FOR ANY ERRORS OR OMISSIONS THAT MAY ARISE AS A RESULT OF ERRONEOUS OR INCOMPLETE INFORMATION PROVIDED BY OTHERS. CONTRACTOR TO CONFIRM ALL ELEVATIONS, GENERAL DRAINAGE AND EARTHWORK REQUIREMENTS PRIOR TO CONSTRUCTION.
- THE BENCHMARK LOCATIONS ARE SHOWN FOR REFERENCE ONLY ON THIS PLAN. THE BENCHMARKS SHALL BE VALIDATED BY LICENSED LAND SURVEYOR PRIOR TO CONSTRUCTION. CONTRACTOR ASSUMES RISK ASSOCIATED WITH BENCHMARK ELEVATIONS UNTIL CONFIRMED.
- CONTRACTOR TO OBTAIN APPROPRIATE PERMITS FOR STREET OPENINGS & TO WORK WITHIN THE CITY'S LAND IF REQUIRED.
- WYSER ENGINEERING SHALL BE HELD HARMLESS AND DOES NOT WARRANT ANY DEVIATIONS BY THE OWNER OR CONTRACTOR FROM THE APPROVED CONSTRUCTION PLANS THAT MAY RESULT IN DISCIPLINARY ACTIONS BY REGULATORY AGENCIES.
- IF ANY ERRORS, DISCREPANCIES, OR OMISSIONS WITHIN THE PLAN BECOME APPARENT, IT SHALL BE BROUGHT TO THE ATTENTION OF THE ENGINEER PRIOR TO CONSTRUCTION SO THAT CLARIFICATION OR REDESIGN MAY OCCUR.
- ALL MUNICIPAL UTILITY CONNECTIONS, WORK IN ROW, PUBLIC OUTLOTS AND PUBLIC EASEMENTS SHALL BE IN ACCORDANCE WITH CITY OF MADISON STANDARD SPECIFICATIONS FOR PUBLIC WORKS CONSTRUCTION.

UTILITY NOTES

- DIMENSIONS TAKE PRECEDENCE OVER SCALE. CONTRACTOR TO VERIFY ALL DIMENSIONS IN FIELD.
- LENGTHS OF ALL UTILITIES ARE TO CENTER OF STRUCTURES OR FITTINGS AND MAY VARY SLIGHTLY FROM PLAN. LENGTHS SHALL BE VERIFIED IN THE FIELD DURING CONSTRUCTION.
- CONTRACTOR SHALL VERIFY ALL ELEVATIONS, LOCATIONS, AND SIZES OF SANITARY, WATER AND STORM LATERALS AND CHECK ALL UTILITY CROSSINGS FOR CONFLICTS.
- THE PROPOSED IMPROVEMENTS MUST BE CONSTRUCTED IN ACCORDANCE WITH ENGINEERING PLANS DESIGNED TO MEET ORDINANCES AND REQUIREMENTS OF THE MUNICIPALITY AND WISDOT, WISDPS, AND WDRN.
- PRIOR TO CONSTRUCTION, THE CONTRACTOR IS RESPONSIBLE FOR:
 - EXAMINING ALL SITES CONDITIONS RELATIVE TO THE CONDITIONS INDICATED ON THE ENGINEERING DRAWINGS. ANY DISCREPANCIES ARE TO BE REPORTED TO THE ENGINEER AND RESOLVED PRIOR TO THE START OF CONSTRUCTION.
 - OBTAINING ALL PERMITS INCLUDING PERMIT COSTS, TAP FEES, METER DEPOSITS, BONDS, AND ALL OTHER FEES REQUIRED FOR PROPOSED WORK TO OBTAIN OCCUPANCY.
 - VERIFYING UTILITY ELEVATIONS AND NOTIFYING ENGINEER OF ANY DISCREPANCY. NO WORK SHALL BE PERFORMED UNTIL THE DISCREPANCY IS RESOLVED.
 - NOTIFYING ALL UTILITIES PRIOR TO THE INSTALLATION OF ANY UNDERGROUND IMPROVEMENTS.
 - NOTIFYING THE DESIGN ENGINEER AND MUNICIPALITY 48 HOURS PRIOR TO THE START OF CONSTRUCTION TO ARRANGE FOR APPROPRIATE CONSTRUCTION OBSERVATION.
- THE CONTRACTOR IS RESPONSIBLE FOR PROVIDING THE ENGINEER WITH AS-BUILT CONDITIONS OF THE DESIGNATED IMPROVEMENTS IN ORDER THAT THE APPROPRIATE DRAWINGS CAN BE PREPARED, IF REQUIRED. ANY CHANGES TO THE DRAWINGS OR ADDITIONAL ITEMS MUST BE REPORTED TO THE ENGINEER AS WORK PROGRESSES.
- ANY SANITARY SEWER, SANITARY SEWER SERVICES, WATER MAIN, WATER SERVICES, STORM SEWER, OR OTHER UTILITIES, WHICH ARE DAMAGED BY THE CONTRACTORS, SHALL BE REPAIRED TO THE OWNER'S SATISFACTION AT THE CONTRACTOR'S EXPENSE. NO BLASTING IS ALLOWED WITHIN 30 FEET OF EXISTING UTILITIES.
- ALL PRIVATE INTERCEPTOR WATER MAIN AND WATER SERVICES SHALL BE INSTALLED WITH A 6" MINIMUM BURY. PROVIDE INSULATION ABOVE PIPES WITH LESS THAN 5' OF GROUND COVER.
- GRANULAR BACKFILL MATERIALS ARE REQUIRED IN ALL UTILITY TRENCHES UNDER SIDEWALKS AND PROPOSED PAVED AREAS (UNLESS OTHERWISE SPECIFIED BY A GEOTECHNICAL ENGINEER). ALL UTILITY TRENCH BACKFILL SHALL BE COMPACTED PER SPECIFICATIONS. ALL PAVEMENT PATCHING SHALL COMPLY WITH THE CITY OF MADISON STANDARD SPECIFICATIONS. ADDITIONAL PAVEMENT MILLING AND OVERLAY MAY BE REQUIRED BY PERMIT.
- CONTRACTOR SHALL NOTIFY THE MUNICIPAL PUBLIC WORKS DEPARTMENT A MINIMUM OF 48 HOURS BEFORE CONNECTING TO PUBLIC UTILITIES.
- ALL NON-METALLIC BUILDING SEWER AND WATER SERVICES MUST BE ACCOMPANIED BY MEANS OF LOCATING UNDERGROUND PIPE. TRACER WIRE VALVE BOXES SHALL BE INSTALLED ON ALL LATERALS AND AS INDICATED ON THESE PLANS.
- ALL EXTERIOR CLEANOUTS SHALL BE PROVIDED WITH A FROST SLEEVE IN ACCORDANCE WITH SPS 382.34(5)(a)(b) AND SPS 384.30(2)(c).
- ALL PRIVATE SANITARY BUILDING SEWER PIPE AND TUBING SHALL CONFORM TO SPS 384.30-3.
- ALL PRIVATE STORM BUILDING PIPE AND TUBING SHALL CONFORM TO SPS 384.30-6.
- ALL PRIVATE PIPE AND TUBING FOR WATER SERVICE SHALL CONFORM TO SPS 384.30-7.
- ALL PRIVATE PIPE SHALL BE INSTALLED PER SPS 384.40-8 INCLUDING AT LEAST 8" OF HORIZONTAL DISTANCE BETWEEN WATER PIPING AND SANITARY SEWER FROM CENTER OF PIPE TO CENTER OF PIPE AND 6" OF SEPARATION BETWEEN STORM SEWER AND WATER PIPING.
- THE CONTRACTOR SHALL ALLOW 10 WORKING DAYS FOR THE CONSTRUCTION OF GAS MAINS WHEN SCHEDULING THE WORK AND SHALL NOT RESTRICT ACCESS TO THE GAS MAIN CONTRACTOR OR OTHER UTILITY COMPANIES.
- INLET CASTINGS SHALL BE SET TO GRADE PRIOR TO AND SEPARATE FROM THE POURING OF THE CONCRETE CURB AND GUTTER. IS REQUIRED THAT THREE FEET OF CONCRETE CURB AND GUTTER ON EACH SIDE OF THE INLET SHALL BE POURED BY HAND, NOT THROUGH THE USE OF A CURB MACHINING. THE INLET CASTING SHALL BE SET TO GRADE ON A BED OF MORTAR WHICH SHALL BE A MINIMUM OF TWO INCHES THICK. THE INLET SHALL BE PLACED ON THE MORTAR BED AND SHALL BE ADJUSTED TO GRADE BY APPLYING DIRECT PRESSURE TO THE CASTING. ONCE THE CASTING ADJUSTMENT IS COMPLETE, THREE FEET OF CURB AND GUTTER ON EACH SIDE OF THE CASTING SHALL BE POURED BY HAND.
- THE CURB INLET SHALL HAVE A CATCH-ALL HR-1 OIL AND GREASE FILTER OR APPROVED EQUIVALENT INSTALLED WITHIN THEM.
- NO BLASTING SHALL OCCUR WITHIN 30 FEET OF ANY EXISTING UTILITIES
- CONTRACTOR SHALL VERIFY AND COORDINATE ALL UTILITY CONNECTIONS WITH THE BUILDING PRIOR TO CONSTRUCTION.
- THE CONTRACTOR SHALL CONDUCT HIS OPERATIONS SO AS TO BE IN CONFORMANCE WITH THE CITY OF MADISON EROSION CONTROL AND STORMWATER ORDINANCE, AND DNR ADMINISTRATIVE RULE NR 216 AT ALL TIMES.



801 WEST BADGER ROAD
MADISON, WI 53713

MADISON COLLEGE
GOODMAN SOUTH CAMPUS
CITY OF MADISON, DANE COUNTY, WI


Sheet Title:
UTILITY PLAN

Revisions:


No.	Date:	Description:

Graphic Scale	0' 15' 30' 45'
---------------	----------------

Wyser Number	17-0407
Set Type	UDC
Date Issued	12/12/2017
Sheet Number	C300



Toll Free (800) 242-8511 -or- 811
 Hearing Impaired TDD (800) 542-2289
www.DiggersHotline.com



NOT FOR CONSTRUCTION

Date: 12/13/17
 Job No: 170143-01
 Sheet No.:


LOWER LEVEL PLAN

Madison College
Goodman South Campus
 801 W Badger Road, Madison, Wisconsin 53713



prad
PLUNKETT RAYSICH
ARCHITECTS, LLP

209 south water street milwaukee, wisconsin 53204 414 359 3060
 2310 crossroads drive suite 2000 madison, wisconsin 53718 608 240 0900
 205 north orange avenue suite 202 sarasota, florida 34236 941 348 3616
 intelligent designs. inspired results. | www.prarch.com



NOT FOR CONSTRUCTION

Sheet No.:

170143-01

Job No.:

12/13/17

Date:

1st

FIRST FLOOR PLAN


Madison College
 Goodman South Campus
 801 W Badger Road, Madison, Wisconsin 53713



MADISON
 AREA TECHNICAL
 COLLEGE

pro |
 PLUNKETT RAYSICH
 ARCHITECTS, LLP

209 south water street milwaukee, wisconsin 53204 414 359 3060
 2310 crossroads drive suite 2000 madison, wisconsin 53718 608 240 0900
 205 north orange avenue suite 202 sarasota, florida 34236 941 348 3616
 intelligent designs. inspired results. | www.prch.com



NOT FOR CONSTRUCTION



Date: 12/13/17
 Job No: 170143-01
 Sheet No.:

Madison College
 Goodman South Campus
 801 W Badger Road, Madison, Wisconsin 53713



prad
 PLUNKETT RAYSICH
 ARCHITECTS, LLP

209 south water street milwaukee, wisconsin 53204 414 359 3060
 2310 crossroads drive suite 2000 madison, wisconsin 53718 608 240 0900
 205 north orange avenue suite 202 sarasota, florida 34236 941 348 3616
 intelligent designs. inspired results. | www.prarch.com



NOT FOR CONSTRUCTION

Date: 12/13/17
 Job No: 170143-01
 Sheet No.:

ROOF PLAN

Madison College
Goodman South Campus
 801 W Badger Road, Madison, Wisconsin 53713




MADISON
 AREA TECHNICAL
 COLLEGE



PLUNKETT RAYSICH
 ARCHITECTS, LLP

209 south water street milwaukee, wisconsin 53204 414 359 3060
 2310 crossroads drive suite 2000 madison, wisconsin 53718 608 240 0900
 205 north orange avenue suite 202 sarasota, florida 34236 941 348 3616

intelligent designs. inspired results. | www.prarch.com




OVERALL EAST ELEVATION
 0 3 5 11 21
 SCALE: 3/32"= 1'-0"


EXTERIOR ELEVATION NOTES	
NOTE #	EXTERIOR ELEVATION NOTE
400	METAL FASCIA
401	METAL SOFFIT
402	METAL COPING
403	STONE VENEER
404	BRICK VENEER
405	PRECAST STONE SILL
406	PRECAST STONE LINTEL
407	METAL WALL PANEL, COLOR 1
408	METAL WALL PANEL, COLOR 2
409	ALUMINUM CURTAIN WALL
410	SUN SHADE
411	STANDING SEAM METAL ROOF
412	MECHANICAL PENTHOUSE
413	AREA DEDICATED FOR BUILDING SIGNAGE, TO BE DETERMINED AT A LATER DATE.
414	GRAVEL STOP



OVERALL NORTH ELEVATION
 0 3 5 11 21
 SCALE: 3/32"= 1'-0"




OVERALL SOUTH ELEVATION
 0 3 5 11 21
 SCALE: 3/32"= 1'-0"




OVERALL WEST ELEVATION
 0 3 5 11 21
 SCALE: 3/32"= 1'-0"

DRAWN BY: Author 12/13/2017 1:40:59 PM


NOT FOR CONSTRUCTION



OVERALL EAST ELEVATION



OVERALL NORTH ELEVATION



EXTERIOR ELEVATION NOTES	
NOTE #	EXTERIOR ELEVATION NOTE
400	METAL FASCIA
401	METAL SOFFIT
402	METAL COPING
403	STONE VENEER
404	BRICK VENEER
405	PRECAST STONE SILL
406	PRECAST STONE LINTEL
407	METAL WALL PANEL, COLOR 1
408	METAL WALL PANEL, COLOR 2
409	ALUMINUM CURTAIN WALL
410	SUN SHADE
411	STANDING SEAM METAL ROOF
412	MECHANICAL PENTHOUSE
413	AREA DEDICATED FOR BUILDING SIGNAGE, TO BE DETERMINED AT A LATER DATE.
414	GRAVEL STOP


DRAWN BY: Author 12/13/2017 1:41:45 PM


NOT FOR CONSTRUCTION

Madison College
 Goodman South Campus
 801 W Badger Road, Madison, Wisconsin 53713

OVERALL ELEVATIONS - COLOR
 Date: 12/13/17
 Job No: 170143-01
 Sheet No.:


E & N


prad
 PLUNKETT RAYSICH
 ARCHITECTS, LLP
 209 south water street milwaukee, wisconsin 53204
 2310 crossroads drive suite 2000 madison, wisconsin 53718
 205 north orange avenue suite 202 sarasota, florida 34236
 414 359 3060
 608 240 9900
 941 348 3616
 intelligent designs. inspired results. | www.prarch.com



OVERALL WEST ELEVATION

SCALE: 1/8" = 1'-0"



OVERALL SOUTH ELEVATION

SCALE: 1/8" = 1'-0"

NOTE #	EXTERIOR ELEVATION NOTE
400	METAL FASCIA
401	METAL SOFFIT
402	METAL COPING
403	STONE VENEER
404	BRICK VENEER
405	PRECAST STONE SILL
406	PRECAST STONE LINTEL
407	METAL WALL PANEL, COLOR 1
408	METAL WALL PANEL, COLOR 2
409	ALUMINUM CURTAIN WALL
410	SUN SHADE
411	STANDING SEAM METAL ROOF
412	MECHANICAL PENTHOUSE
413	AREA DEDICATED FOR BUILDING SIGNAGE, TO BE DETERMINED AT A LATER DATE.
414	GRAVEL STOP

DRAWN BY: Author 12/13/2017 1:42:36 PM

NOT FOR CONSTRUCTION

Madison College
Goodman South Campus
801 W Badger Road, Madison, Wisconsin 53713

Revisions:

OVERALL ELEVATIONS - COLOR

Date: 12/13/17
Job No: 170143-01
Sheet No.:

W & S



pro

PLUNKETT RAYSICH
ARCHITECTS, LLP

209 south water street milwaukee, wisconsin 53204
2310 crossroads drive suite 2000 madison, wisconsin 53718
205 north orange avenue suite 202 sarasota, florida 34236


intelligent designs. inspired results. | www.prch.com

414 359 3060
608 240 0900
941 348 3616

View from Intersection of Badger Road and Park Street



DRAWN BY: Author 9/29/2017 3:43:36 PM



NOT FOR CONSTRUCTION

Revisions:	
Plan Commission	
Date:	17_1213
Job No.:	17_PRA_01
Sheet No.:	

Madison College
 Goodman South Campus
 801 W Badger Road, Madison, Wisconsin 53713



MADISON AREA TECHNICAL COLLEGE

pro

PLUNKETT RAYSICH ARCHITECTS, LLP



Intelligent design, inspired results. www.parch.com

etc design studio

209 south water street milwaukee, wisconsin 53204 - 414.359.3060
 2310 crossroads drive suite 2000 madison, wisconsin 53718 - 608.240.9900
 205 north orange avenue suite 202 sarasota, florida 34236 - 941.348.3618

L100

DRAWN BY: Author 9/29/2017 3:43:36 PM



NOT FOR CONSTRUCTION

Revisions:	
Plan Commission	
Date:	17_1213
Job No.:	17_PRA_01
Sheet No.:	

Madison College
 Goodman South Campus
 801 W Badger Road, Madison, Wisconsin 53713



MADISON AREA TECHNICAL COLLEGE

pro

PLUNKETT RAYSICH ARCHITECTS, LLP

209 south water street milwaukee, wisconsin 53204 - 414.359.3060
 2310 crossroads drive suite 2000 madison, wisconsin 53718 - 608.240.9900
 205 north orange avenue suite 202 sarasota, florida 34236 - 941.348.3618




L101


Landscape Plan

Intelligent design, inspired results. www.parch.com

DRAWN BY: Author 9/29/2017 3:43:36 PM



NOT FOR CONSTRUCTION



Revisions:	
Plan Commission	
Entry Engagement	
Landscape Plan	
Date:	17_1213
Job No.:	17_PRA_01
Sheet No.:	

Madison College
 Goodman South Campus
 801 W Badger Road, Madison, Wisconsin 53713




pro
 MADISON AREA TECHNICAL COLLEGE

PLUNKETT RAYSICH ARCHITECTS, LLP

209 south water street milwaukee, wisconsin 53204 - 414.359.3060
 2310 crossroads drive suite 2000 madison, wisconsin 53718 - 608.240.9900
 205 north orange avenue suite 202 sarasota, florida 34236 - 941.348.3618
 Intelligent design, inspired results. www.parch.com



DRAWN BY: Author 9/29/2017 3:43:36 PM



209 south water street milwaukee, wisconsin 53204 - 414.359.3060
 2310 crossroads drive suite 2000 madison, wisconsin 53718 - 608.240.9900
 205 north orange avenue suite 202 sarasota, florida 34236 - 941.348.3618
 intelligent design, inspired results. www.parch.com

pro
 PLUNKETT RAYSICH
 ARCHITECTS, LLP

MADISON
 AREA | TECHNICAL
COLLEGE

Madison College
Goodman South Campus
 801 W Badger Road, Madison, Wisconsin 53713

Revisions:
 Plan Commission

Rear Entry
 Enlargement
 Landscape Plan

Date: 17_1213
 Job No: 17_PRA_01
 Sheet No.:

NOT FOR CONSTRUCTION

L103



North
 SCALE
 0 4 8
SCALE: 1/8" = 1'-0"

LANDSCAPE PLANT LEGEND

Symbol	Botanical name	Common Name	Size	Root	Quantity	Remarks
SHADE TREES						
CE	Celtis occidentalis	Common Hackberry	3" Cal.	B&B		
CO	Carya ovata	Shagbark Hickory	3" Cal.	B&B		
FG	Fagus grandifolia	American Beech	3" Cal.	B&B		Multi-stem Tree 3 Trunks- Min 1 1/2" Cal.
GB	Ginkgo biloba	Ginkgo Tree	3" Cal.	B&B		
GD	Gymnocladus dioicus	Kentucky Coffeetree	3" Cal.	B&B		
PA	Platanus x acerfolia	American Sycamore	3" Cal.	B&B		
QB	Quercus bicolor	Swamp White Oak	3" Cal.	B&B		
QM	Quercus macrocarpa	Bur Oak	3" Cal.	B&B		
QR	Quercus rubra	Red Oak	3" Cal.	B&B		
TT	Tilia tomentosa	Silver Linden	3" Cal.	B&B		
UP	Ulmus x 'Pioneer'	Pioneer Elm	3" Cal.	B&B		
EVERGREEN TREES						
PG	Picea glauca	White Spruce	6' - 8' HT.	B&B		
PM	Pseudotsuga menziesii	Douglas Fir	6' - 8' HT.	B&B		
PN	Pinus nigra	Austrian Pine	6' - 8' HT.	B&B		
PS	Pinus strobus	Eastern White Pine	6' - 8' HT.	B&B		
TC	Tsuga canadensis	Canadian Hemlock	4' - 6' HT.	B&B		
ORNAMENTAL TREES						
AC	Amelanchier canadensis	Shadblow Serviceberry	5-6' HT.	B&B		
CC	Carpinus caroliniana	American Hornbeam (Musclewood)	2"-3" Cal.	B&B		
CA	Cornus alternifolia	Pagoda Dogwood	5-6' HT.	B&B		
CK	Cornus kousa	Kousa Dogwood	5-6' HT.	B&B		
CI	Crataegus crus-galli var. inermis	Thornless Cockspur Hawthorn	2" Cal.	B&B		
OV	Ostrya virginiana	American Hophornbean	2"-3" Cal.	B&B		
PV	Prunus virginiana 'Schubert'	Canada Red Chokecherry	2" Cal.	B&B		
VL	Viburnum lentago	Nannyberry Viburnum	2" Cal.	B&B		
VP	Viburnum prunifolium	Blackhaw Viburnum	6-8' HT.	B&B		Multi-stem Tree, 3 Trunks- Min 1" Cal.
SHRUBS						
Cc	Caryopteris x clandonensis Arthur Simmonds	Arthur Simmonds Caryopteris	3 gal	Pot		
Cf	Calamagrostis x acutiflora 'Karl Foerster'	Karl Foerster Feather Reed Grass	2 Gal.	CG		
Fs	Forsythia x 'Sunrise'	Sunrise Forsythia	3 gal	Pot		
Hk	Hypericum kalmianum	St. Johns Wort	3 gal	Pot		
Kj	Kerria Japonica	Japenese Kerria	2 gal.	Pot		
Pa	Pennisetum alopecuroides 'Hameln'	Dwarf Fountain Grass	2 Gal.	CG		
Pv	Panicum virgatum 'Shenandoah'	Shenandoah Swith Grass	2 Gal.	CG		
Ra	Rhus aromatica 'Grow Low'	'Gro low' Sumac	2 gal	Container		
Rg	Rhus glabara	Smooth Sumac	5 gal	Pot		
Vj	Viburnum x juddi	Judd Viburnum	5 gal	B&B		
Vt	Viburnum trilobum	American Cranberrybush Viburnum	5 gal	B&B		

EVERGREEN SHRUBS

Iv	Illex verticillata	Winterberry	5 Gal.	CG		
Jr	Juniperus ramlosa	Ramlosa juniper	5 Gal.	CG		
Tm	Taxus tauntonii	Taunton yew	5 Gal.	CG		

PERENNIALS

abs	Amsonia 'Blue Starflower'	Blue Starflower	1 Gal.	Container		30"O.C.
aaf	Astilbe x arendsii 'Fanal'	Fanal Astilbe	1 Gal.	Container		15"O.C.
apd	Aster novae-angliae 'Purple Dome'	Purple Dome	1 Gal.	Container		24"O.C.
asr	Aster novae-angliae 'September Ruby'	September Ruby Aster	1 Gal.	Container		24"O.C.
bec	Bergenia cordifolia	Heartleaf Bergenia	1 Gal.	Container		15"O.C.
cca	Catananche caerulea	Cupids Dart	1 Gal.	Container		12"O.C.
cvz	Coreopsis verticillata 'Zagreb'	Zagreb Coreopsis	1 Gal.	Container		18"O.C.
epm	Echinacea purpurea 'Magnus'	Magnus Purple Coneflower	1 Gal.	Container		36"O.C.
ise	Iberis sempervirens	Candytoft	1 Gal.	Container		15"O.C.
lpy	Liatrus pycnostachya	Prairie Blazingstar	1 Gal.	Container		18"O.C.
lla	Limonium latifolium	Sea Lavender	1 Gal.	Container		24"O.C.
mpd	Monarda 'Petite Delight'	Petite Delight Beebalm	1 Gal.	Container		24"O.C.
rfg	Rudbeckia fulgida 'Goldstrum'	Goldstrum Black-eyed Susan	1 Gal.	Container		18"O.C.

Detention Basin Seed Mix

The species in this mix designed by Prairie Nursery of Westfield, Wisconsin (or approved equal) grow naturally in medium-moist prairies, making them the perfect for temporarily flooded areas that also dry out in summer. Designed for planting in basins that are flooded for 24-48 hours, and then drain out. This mix is particularly well adapted to loamy and clay soils. For detention basins in sandy soils, we recommend planting our Tall Prairie for Dry Soils Seed Mix.

WILDFLOWERS: Nodding Pink Onion, Red Milkweed, New England Aster, White False Indigo, Pale Indian Plantain, Wild Senna, Joe Pye Weed, Boneset, Dogtooth Daisy, Ox Eye Sunflower, Wild Iris, Blue Flag Iris, Prairie Blazingstar, Dense Blazingstar, Great Blue Lobelia, Bergamot, Yellow Coneflower, Black Eyed Susan, Sweet Black Eyed Susan, Brown Eyed Susan, Rosinweed, Cupplant, Prairie Dock, Ohio Goldenrod, Stiff Goldenrod, Blue Vervain, Ironweed, Golden Alexanders

GRASSES: Big Bluestem, Bebb's Sedge, Bottlebrush Sedge, Porcupine Sedge, Awl Fruited Sedge, Fox Sedge, Canada Wild Rye, Virginia Wild Rye, Switchgrass, Dark Green Bulrush, Indiangrass, Prairie Cordgrass, Annual Rye Nurse Crop

Contains at least 20 wildflowers and 8 or more grasses, sedges & bulrushes, plus annual rye



CITY OF MADISON LANDSCAPE WORKSHEET

Section 28.142 Madison General Ordinance

Project Location / Address 801 Badger Road, Madison, WI 53713

Name of Project Madison College South Campus

Owner / Contact Mike Stark

Contact Phone _____ Contact Email MStark@madisoncollege.edu

**** Landscape plans for zoning lots greater than ten thousand (10,000) square feet in size MUST be prepared by a registered landscape architect. ****

Landscape Calculations and Distribution

Required landscaped areas shall be calculated based upon the total developed area of the property. Developed area is defined as all parts of the site that are not left in a natural state within a single contiguous boundary, including building footprints, parking and loading areas, driveways, internal sidewalks, patios, and outdoor activity areas. Developed area does not include other land within required setbacks and natural areas on the same property that are left undisturbed.

(a) One (1) landscape unit shall be provided for each three hundred (300) square feet of developed area, with the exception of the IL and the IG districts as specified in (b) below.

Total square footage of developed area 194,683

Developed area divided by three hundred (300) square feet = 649 Landscape Units

(b) Within the Industrial - Limited (IL) and Industrial - General (IG) districts, one (1) landscape unit shall be provided for every six hundred (600) square feet of developed area.

Total square footage of developed area _____

Developed area divided by six hundred (600) square feet = _____ Landscape Units

(c) One landscape unit consists of five (5) landscape points. Landscape points are calculated as shown in the following table.

Landscape units multiplied by five (5) landscape points = 3245 Total Points Required

Tabulation of Points and Credits

Use the table to indicate the quantity and points for all existing and proposed landscape elements. Calculations yielding a fraction up to one-half (1/2 or 0.5) shall be rounded down to the nearest whole number; fractions of more than one half (1/2) shall be rounded up.

Plant Type/ Element	Minimum Size at Installation	Points	Credits/ Existing Landscaping		New/ Proposed Landscaping	
			Quantity	Points Achieved	Quantity	Points Achieved
Overstory deciduous tree	2 1/2 inch caliper	35			51	1785
Ornamental tree	1 1/2 inch caliper	15			22	330
Evergreen tree	3 feet tall	15			3	45
Shrub, deciduous	18" or 3 gallon container size	2			356	1068
Shrub, evergreen	18" or 3 gallon container size	3			18	54
Ornamental grasses	18" or 3 gallon container size	2			277	554
Ornamental/ decorative fencing or wall	n/a	4 per 10 lineal ft.				
Sub Totals						3836

Total Number of Points Provided 3836

3/2013

NOT FOR CONSTRUCTION




Revisions:
Plan Commission

Plant Schedule and
Points Sheet

Date: 17_1213


Job No: 17_PRA_01

Sheet No.:




1 B&B TREE PLANTING DETAIL
L105

NTS




2 B&B EVERGREEN TREE PLANTING DETAIL
L105

NTS




3 B&B SHRUB PLANTING DETAIL
L105

NTS




4 CONTAINER PLANTING DETAIL
L105

NTS




5 GROUNDCOVER / PERENNIAL PLANTING DETAIL
L105

NTS



6 PERENNIAL/GROUNDCOVER SPACING DETAIL
L105

NTS




7 BARK MULCH/SHOVEL CUT EDGE DETAIL
L105


NTS

DRAWN BY: Author 9/29/2017 3:43:36 PM


NOT FOR CONSTRUCTION




1 PED LOAD CONCRETE PAVEMENT-SECTION
L106 NTS




2 PED LOAD UNIT PAVER BAND - SECTION
L106 NTS



3 UNIT PAVER RESTRAINING EDGE SECTION
L106 SCALE 1/2"=1'-0" NTS




4 EXPANSION/CONTROL JOINT-SECTION
L106 NTS




NOTES:
1. FOR 12' WIDE PATH CONTRACTION JOINTS @ 6'-0" O.C., FOR 10' WIDE PATH CONTRACTION JOINTS @ 5'-0" O.C., FOR 8' WIDE PATH CONTRACTION JOINTS @ 4'-0".
2. EXPANSION JOINTS FOR ALL WIDTHS TO BE AT 30' O.C. MAX. ALWAYS. (SEE LAYOUT PLANS FOR ADDITIONAL SCORING PATTERN DETAILS)
3. EXPANSION JOINTS SHALL BE CONSTRUCTED OF PREFORMED JOINT FILLER OR AS SPECIFIED. COLOR TO MATCH PAVEMENT COLOR.


5 CONCRETE PAVEMENT SCORE PATTERN-PLAN
L106 NTS




6 FREE STANDING LIMESTONE VENEER BENCH SECTION
L106 NTS



7 BIKE RACK ON CONCRETE PAD
L106 SCALE N.T.S.



8 LIMESTONE BLOCK DETENTION BASIN ACCENT TYPICAL
L106 SCALE: NTS



9 LANDSCAPE BOULDER DETAIL- SECTION
L106 SCALE: NTS



DRAWN BY: Author 9/29/2017 3:43:36 PM

NOT FOR CONSTRUCTION

209 south water street milwaukee, wisconsin 53204 - 414 359 3060
 2310 crossroads drive suite 2000 madison, wisconsin 53718 - 608 240 9900
 205 north orange avenue suite 202 sarasota, florida 34236 - 941 348 3618
 intelligent design, inspired results. www.parch.com
 PLUNKETT RAYSICH ARCHITECTS, LLP
 pro MADISON AREA TECHNICAL COLLEGE
 Madison College Goodman South Campus
 801 W Badger Road, Madison, Wisconsin 53713
 Revisions:
 Plan Commission
 Date: 17_1213
 Job No: 17_PRA_01
 Sheet No.:
 Site Details
 L106

Calculation Summary							
Label	CalcType	Units	AVG	MAX	MIN	AVG/REQ	MAX/REQ
Express North East	ILLUMINATION	FC	2.45	3.1	1.8	1.53	1.94

Luminaire Schedule							
Index	Qty	Label	Description	LEN, METRS	LEN, LUMENS	LF	
20	01	FW-E00-30-xx-02-E-0L-350-40W	FW-E00-30-xx-02-E-0L-350-40W - 800X2158-087	21.3	1179	0.000	
19	02	L04870010 E04870010A4 KL80W	4 1/2" RWB ROUND	14.3	1140	0.000	
18	02	L04870010 E04870010A4 KL80W	L04870010 E04870010A4 KL80W	28	2277	0.000	
17	02	W01-134-02-35	1/2" SQUARE BRASS ADJUSTABLE JOINT LIGHT	1.6	1164	0.000	
16	02	W01-134-02-35	1/2" X 3/8" FROST LIGHT	1	1194	0.000	
15	02	W01-134-02-35	1/2" X 3/8" FROST LIGHT	1.21	1142	0.000	
14	02	W01-134-02-35	1/2" X 3/8" FROST LIGHT	0	1164	0.000	
13	02	W01-134-02-35	1/2" X 3/8" FROST LIGHT	0	1056	0.000	
12	02	W01-134-02-35	1/2" X 3/8" FROST LIGHT	134	13209	0.000	
11	02	W01-134-02-35	1/2" X 3/8" FROST LIGHT	0	1408	0.000	
10	02	W01-134-02-35	1/2" X 3/8" FROST LIGHT	0	1408	0.000	
9	02	W01-134-02-35	1/2" X 3/8" FROST LIGHT	23.3	2005	0.000	
8	02	W01-134-02-35	1/2" X 3/8" FROST LIGHT	70.1	1593	0.000	
7	02	W01-134-02-35	1/2" X 3/8" FROST LIGHT	131.4	10343	0.000	



NOT FOR CONSTRUCTION

Date: 11/15/17
Job No: 170143-01
Sheet No:

170143-01

Madison College
South Campus Project
801 W Badger Road, Madison, Wisconsin 53713



MADISON
AREA TECHNICAL
COLLEGE



pro
PLUNKETT RAYSICH
ARCHITECTS, LLP

209 south water street milwaukee, wisconsin 53204 414 359 3060
2310 crossroads drive suite 2000 madison, wisconsin 53718 608 240 0900
205 north orange avenue suite 202 sarasota, florida 34236 941 348 3616
intelligent designs. inspired results. | www.prch.com

LIGHTING PLAN

Label	CalcType	Units	Avg	Max	Min	Avg/Min	Max/Min
Green North East	Illuminance	FC	2.40	3.11	1.46	4.23	11.94
Entrance	Illuminance	FC	12.15	16.7	0.0	20.25	31.17
Handicapped Parking	Illuminance	FC	1.23	2.28	0.7	2.76	4.00
Loading Dock Ramp	Illuminance	FC	2.26	3.8	0.8	2.83	14.75
Main Parking Lot	Illuminance	FC	1.50	4.20	0.4	2.88	11.25
North Entry Drive	Illuminance	FC	1.32	3.8	0.0	3.44	10.60
Phase South	Illuminance	FC	2.20	15.2	0.0	8.8	30.00
Property Line +10'	Illuminance	FC	0.26	2.4	0.0	0.6	3.0
Southwest Green Path	Illuminance	FC	2.26	3.7	0.4	2.90	12.25
West Bike Parking	Illuminance	FC	2.93	3.1	0.0	4.88	15.17
West Entry Drive 1	Illuminance	FC	1.30	4.20	0.0	4.16	12.25
West Entry Drive 2	Illuminance	FC	1.68	2.5	0.7	2.40	3.57

Symbol	Qty	Vol	Label	Description	Lot, Met	Lot, Lumens	Lot
19	82	10475070	SM-E-10-25	PHOTOMETRIC: 10'-24" H-100-100	121.3	1178	0.000
19	01	104815070	SM-E-10-25	PHOTOMETRIC: 10'-24" H-100-100	14.3	1165	0.000
19	02	104815070	SM-E-10-25	PHOTOMETRIC: 10'-24" H-100-100	28	2277	0.000
13	01	ACCI-355-10	ACCI-355-10	10' GEOMETRIC BEAM ADJUSTABLE SPOTLIGHT	18	1162	0.000
4	02	SM-E-10-25	SM-E-10-25	PHOTOMETRIC: 10'-24" H-100-100	18	1162	0.000
5	21	SM-E-10-25	SM-E-10-25	PHOTOMETRIC: 10'-24" H-100-100	171	1819	0.000
5	22	SM-E-10-25	SM-E-10-25	PHOTOMETRIC: 10'-24" H-100-100	0	1168	0.000
5	23	SM-E-10-25	SM-E-10-25	PHOTOMETRIC: 10'-24" H-100-100	0	1054	0.000
5	24	SM-E-10-25	SM-E-10-25	PHOTOMETRIC: 10'-24" H-100-100	134	1309	0.000
4	25	SM-E-10-25	SM-E-10-25	PHOTOMETRIC: 10'-24" H-100-100	0	1468	0.000
4	26	SM-E-10-25	SM-E-10-25	PHOTOMETRIC: 10'-24" H-100-100	23.3	2025	0.000
18	22	2016	2016	2016 Washer Quattro AC 8-2	107.7	1553	0.000
1	W1	10178173	2016	2016 Washer Quattro AC 8-2	131.4	10143	0.000



NOT FOR CONSTRUCTION

Date: 11/15/17
 Job No: 170143-01
 Sheet No:

Madison College
 South Campus Project
 801 W Badger Road, Madison, Wisconsin 53713

MADISON AREA TECHNICAL COLLEGE
 PLUNKETT RAYSICH ARCHITECTS, LLP

intelligent designs. inspired results. | www.prch.com
 209 south water street milwaukee, wisconsin 53204
 2310 crossroads drive suite 2000 madison, wisconsin 53718
 205 north orange avenue suite 202 sarasota, florida 34236
 414 359 3060
 608 240 0900
 941 348 3616

PHOTOMETRICS PLAN

MADISON COLLEGE SOUTH CAMPUS EXTERIOR LUMINAIRE SCHEDULE

QTY	TYPE	DESCRIPTION	CCT	NOMINAL DELIVERED LUMENS	NOMINAL WATTAGE	MFTR	MODEL #	NOTES
	B1	42" BOLLARD. SYMMETRICAL DISTRIBUTION. FINISH TO BE DETERMINED.	4000K	1,780	22	CREE INTRIGUE AMERLUX	PATHWAY PWY-EDG-5M-P42-02-E-UL-XX-350-40K	
	D1	4 INCH APERTURE DOWNLIGHT WITH SELF-TRIMMING MATTE CLEAR OR HAZE REFLECTOR. LENSED FOR COVERED EXTERIOR SOFFIT.	4000K	1,500	16	HALO	LD4B-15-D010/EU4B-1020-80-40/4LBM-1H	
	D2	6 INCH APERTURE DOWNLIGHT WITH SELF-TRIMMING MATTE CLEAR OR HAZE REFLECTOR. LENSED FOR COVERED EXTERIOR SOFFIT.	4000K	2,240	28	HALO	LD6B-30-D010/EU6B-3050-8040/6LBM1H	
	G1	KNUCKLE MOUNTED 10 DEGREE EXTERIOR SPOTLIGHT WITH JUNCTION BOX MOUNT, JUNCTION BOX AND GLARE SHIELD. FINISH TO BE DETERMINED.	3500K	1,300	17	AMERLUX	ACCION LARGE ACCL35-10-K-XXX-JCOV-JBOX-HGL	MOUNTED AT TOP OF COLUMNS AT NORTH ENTRANCE. MOUNTED AT BOTTOM OF COLUMNS AT SOUTH ENTRANCE.
	G2	KNUCKLE MOUNTED 30 X 60 DEGREE EXTERIOR SPOTLIGHT WITH HEAVY-DUTY POLYCARBONATE STEAK AND GLARE SHIELD. FINISH TO BE DETERMINED.	3500K	1,200	17	AMERLUX	ACCION LARGE ACCL35-V6030-K-XXX-GSO17-HGL	SIGN LIGHTING TO BE CONFIRMED WITH FINAL PLACEMENT AND SIZING OF SIGNS.
	P1	FULL CUTOFF AREA LIGHT, TYPE V DISTRIBUTION. PROVIDE WITH 22' ROUND STRAIGHT STEEL POLE. TO BE MOUNTED ON 30" RAISED CONCRETE BASE. FINISH TO BE DETERMINED.	4000K	18,400	171	CREE CYCLONE USA ARCHITECTURAL	EDGE ROUND ARE-EDR-5M-R3-10-E-UL-XX-525-40K	
	P2	FULL CUTOFF AREA LIGHT, TYPE II DISTRIBUTION WITH HOUSE SIDE SHIELD. PROVIDE WITH 22' ROUND STRAIGHT STEEL POLE. TO BE MOUNTED ON 30" RAISED CONCRETE BASE. FINISH TO BE DETERMINED.	4000K	13,200	171	CREE CYCLONE USA ARCHITECTURAL	EDGE ROUND ARE-EDR-2BLS-R3-10-E-UL-XX-525-40K	
	P3	FULL CUTOFF AREA LIGHT, TYPE III DISTRIBUTION. PROVIDE WITH 22' ROUND STRAIGHT STEEL POLE. TO BE MOUNTED ON 30" RAISED CONCRETE BASE. FINISH TO BE DETERMINED.	4000K	16,600	171	CREE CYCLONE USA ARCHITECTURAL	EDGE ROUND ARE-EDR-3M-R3-10-E-UL-XX-525-40K	
	P4	FULL CUTOFF AREA LIGHT, TYPE V DISTRIBUTION. PROVIDE WITH 16' ROUND STRAIGHT STEEL POLE. TO BE MOUNTED ON FLUSH CONCRETE BASE. FINISH TO BE DETERMINED.	4000K	13,100	134	CREE CYCLONE USA ARCHITECTURAL	EDGE ROUND ARE-EDR-5M-R3-06-E-UL-XX-700-40K	
	P5	FULL CUTOFF AREA LIGHT, TYPE V DISTRIBUTION. PROVIDE WITH 14' ROUND STRAIGHT STEEL POLE. TO BE MOUNTED ON FLUSH CONCRETE BASE. FINISH TO BE DETERMINED.	4000K	7,500	70	CREE CYCLONE USA ARCHITECTURAL	EDGE ROUND ARE-EDR-5M-R3-04-E-UL-XX-525-40K	
	W1	FULL CUTOFF EXTERIOR WALL LUMINAIRE. TYPE 3 DISTRIBUTION. FINISH TO BE DETERMINED.	4000K	2,000	25	CREE	EDGE SECURITY SEC-EDG-3M-WM-02-E-UL-XX-350-40K	MOUNTED AT APPROXIMATELY 9' AFG.
	W2	COLOR CHANGING (RGBW) EXTERIOR FLOODLIGHT FOR UPLIGHTING UNDERSIDE OF BUILDING CANOPY. DMX CONTROL REQUIRED.	N/A	MAX 3200 WHEN ALL ON	85	TRAXXON	QUATTRO WASH RGBW	MOUNTED AT APPROXIMATELY 26' AFG TO INDIRECTLY LIGHT CANOPY AT NORTH SIDE OF BUILDING. MOUNTED AT APPROXIMATELY XX' TO INDIRECTLY LIGHT CANOPY AT SOUTH SIDE OF BUILDING.
	W1	FULL CUTOFF EXTERIOR WALL LUMINAIRE. TYPE 3 DISTRIBUTION. FINISH TO BE DETERMINED.	4000K	10,300	132	CREE	EDGE SECURITY SEC-EDG-3M-WM-06-E-UL-XX-700-40K	MOUNTED AT APPROXIMATELY 18' AFG.

Cree Edge™ Series

LED Pathway Luminaire

Product Description

Durable die-cast aluminum luminaire housing mounts directly to 4" (102mm) diameter pole (included) without visible mounting hardware for clean appearance. Pole mounts to rugged die cast aluminum internal flange secured by three 3/8" - 16x6" anchor bolts with 1-1/4" hook (provided). **Note:** T45 Torx 3/8" socket required for head installation. Top mounted LEDs for superior optical performance and light control.

Applications: Landscape, walk-ways and general site lighting

Performance Summary

Patented NanoOptic® Product Technology

Made in the U.S.A. of U.S. and imported parts

CRI: Minimum 70 CRI


CCT: 4000K (+/- 300K), 5700K (+/- 500K) standard

Limited Warranty*: 10 years on luminaire/10 years on Colorfast DeltaGuard® finish

* See <http://lighting.cree.com/warranty> for warranty terms

Accessories

Field-Installed
Upgrade Kit - Used for replacement of existing bollards with a bolt hole circle of 5.75" (146mm) XA-XBP8RSV XA-XBP8RWH XA-XBP8RBK XA-XBP8RBZ



Model	Dim. "A"	Weight*
Landscape (P0)	13" (330mm)	12.7 lbs. (5.8kg)
Landscape (P1)	18" (457mm)	13.3 lbs. (6.0kg)
Pathway (P3)	36" (914mm)	17.9 lbs. (8.1kg)
Pathway (P4)	42" (1068mm)	18.6 lbs. (8.4kg)
Pedestrian (P8)	96" (2438mm)	28.4 lbs (12.9kg)

* Add 4.5 lbs. (2.0kg) for 347-480V

Ordering Information

Example: PWY-EDG-2M-P0-02-E-UL-SV-350

PWY-EDG			02	E				
Product	Optic	Mounting	LED Count (x9)	Series	Voltage	Color Options	Drive Current	Options
PWY-EDG	2M Type II Medium 3M Type III Medium 5M Type V Medium 5S Type V Short	P0 13" (330mm) landscape P1 18" (457mm) landscape P3 36" (914mm) pathway P4 42" (1067mm) pathway P8 96" (2438mm) pedestrian	02	E	UL Universal 120-277V UH* Universal 347-480V - Available with P3, P4, and P8 mounts only 12 120V 27 277V	BK Black BZ Bronze SV Silver WH White	350 350mA 525 525mA - Available with P1, P3, P4, and P8 mounts only	F Fuse - When code dictates fusing, use time delay fuse - Refer to ML spec sheet for availability with ML options HL Hi/Low (Dual Circuit Input) - Available with UL voltage and 525mA driver current only - Refer to HL spec sheet for details - Sensor not included TL Two-Level (175/525 w/integrated sensor control) - Available with 12 or 27 voltages only - Refer to TL spec sheet for details TL2 Two-Level (0/350 w/integrated sensor control) - Available with 12 or 27 voltages only - Refer to TL spec sheet for details TL3 Two-Level (0/525 w/integrated sensor control) - Available with 12 or 27 voltages only - Refer to TL spec sheet for details WB Welded Base Plate - Standard on P8 mount option, available with P3 and P4 mount - Includes welded base cover 40K 4000K Color Temperature - Minimum 70 CRI - Color temperature per luminaire

* 347-480V utilizes magnetic step-down transformer. For input power for 347-480V, refer to the Electrical Data table



Rev. Date: V5 08/11/2016



Product Specifications

CONSTRUCTION & MATERIALS

- Durable die-cast aluminum luminaire housing mounts directly to 4" (102mm) diameter pole (included) without visible mounting hardware for clean appearance
- Pole mounts to rugged die cast aluminum internal flange secured by three 3/8"-16x6" anchor bolts with 1-1/4" hook (provided).
Note: T45 Torx 3/8" socket required for head installation
- Top mounted LEDs for superior optical performance and light control
- Exclusive Colorfast DeltaGuard® finish features an E-Coat epoxy primer with an ultradurable powder topcoat, providing excellent resistance to corrosion, ultraviolet degradation and abrasion. Black, bronze, silver and white are available
- **Weight:** See Dimension and Weight Chart on pages 1 and 4

ELECTRICAL SYSTEM

- **Input Voltage:** 120-277V or 347-480V, 50/60Hz, Class 1 drivers
- **Power Factor:** > 0.9 at full load at 120V
- **Total Harmonic Distortion:** < 20% at full load at 120V
- Integral 10kV surge suppression protection standard
- When code dictates fusing, a slow blow fuse or type C/D breaker should be used to address inrush current

REGULATORY & VOLUNTARY QUALIFICATIONS

- cULus Listed
- Suitable for wet locations
- 10kV surge suppression protection tested in accordance with IEEE/ANSI C62.41.2
- Luminaire and finish endurance tested to withstand 5,000 hours of elevated ambient salt fog conditions as defined in ASTM Standard B 117
- Meets Buy American requirements within ARRA
- RoHS compliant. Consult factory for additional details

Electrical Data* (A)								
LED Count (x9)	System Watts 120-277V	System Watts 347-480V	Total Current					
			120V	208V	240V	277V	347V	480V
350mA								
02	22	28	0.18	0.12	0.10	0.10	0.09	0.13
525mA								
02	34	40	0.29	0.19	0.17	0.15	0.12	0.13

* Electrical data at 25°C (77°F). Actual wattage may differ by +/- 10% when operating between 120-480V +/- 10%

Recommended Cree Edge™ Series Lumen Maintenance Factors (LMF) ¹					
Ambient	Initial LMF	25K hr Projected ² LMF	50K hr Projected ² LMF	75K hr Calculated ³ LMF	100K hr Calculated ³ LMF
5°C (41°F)	1.04	0.99	0.97	0.95	0.93
10°C (50°F)	1.03	0.98	0.96	0.94	0.92
15°C (59°F)	1.02	0.97	0.95	0.93	0.91
20°C (68°F)	1.01	0.96	0.94	0.92	0.90
25°C (77°F)	1.00	0.95	0.93	0.91	0.89

¹ Lumen maintenance values at 25°C are calculated per TM-21 based on LM-80 data and in-situ luminaire testing


² In accordance with IESNA TM-21-11, Projected Values represent interpolated value based on time durations that are within six times (6X) the IESNA LM-80-08 total test duration (in hours) for the device under testing ((DUT) i.e. the packaged LED chip)

³ In accordance with IESNA TM-21-11, Calculated Values represent time durations that exceed six times (6X) the IESNA LM-80-08 total test duration (in hours) for the device under testing ((DUT) i.e. the packaged LED chip)


Photometry

All published luminaire photometric testing performed to IESNA LM-79-08 standards by a NVLAP accredited laboratory. To obtain an IES file specific to your project consult: <http://lighting.cree.com/products/outdoor/bollards-and-pathway/cree-edge-pathway>

2M



RESTL Test Report #: PL5758-001
 PWY-EDG-2M-**-02-E-UL-350-40K
 Initial Delivered Lumens: 1,549




PWY-EDG-2M-**-02-E-UL-350-40K
 Mounting Height: 3' [0.9m] A.F.G.
 Initial Delivered Lumens: 1,565
 Initial FC at grade


Type II Medium Distribution				
LED Count (x9)	4000K		5700K	
	Initial Delivered Lumens*	BUG Ratings** Per TM-15-11	Initial Delivered Lumens*	BUG Ratings** Per TM-15-11
350mA				
02	1,565	B1 U0 G1	1,625	B1 U0 G1
525mA				
02	2,191	B1 U0 G1	2,276	B1 U0 G1

* Initial delivered lumens at 25°C (77°F). Actual production yield may vary between -10 and +10% of initial delivered lumens
 ** For more information on the IES BUG (Backlight-Uplight-Glare) Rating visit: www.ies.org/PDF/Erratas/TM-15-11BugRatingsAddendum.pdf

3M



RESTL Test Report #: PL5698-001
 PWY-EDG-3M-**-02-E-UL-350-40K
 Initial Delivered Lumens: 1,470




PWY-EDG-3M-**-02-E-UL-350-40K
 Mounting Height: 3' [0.9m] A.F.G.
 Initial Delivered Lumens: 1,389
 Initial FC at grade


Type III Medium Distribution				
LED Count (x9)	4000K		5700K	
	Initial Delivered Lumens*	BUG Ratings** Per TM-15-11	Initial Delivered Lumens*	BUG Ratings** Per TM-15-11
350mA				
02	1,389	B1 U0 G1	1,442	B1 U0 G1
525mA				
02	1,944	B1 U0 G1	2,019	B1 U0 G1

* Initial delivered lumens at 25°C (77°F). Actual production yield may vary between -10 and +10% of initial delivered lumens
 ** For more information on the IES BUG (Backlight-Uplight-Glare) Rating visit: www.ies.org/PDF/Erratas/TM-15-11BugRatingsAddendum.pdf

5M



RESTL Test Report #: PL5798-001
 PWY-EDG-5M-**-02-E-UL-350-40K
 Initial Delivered Lumens: 1,780



PWY-EDG-5M-**-02-E-UL-350-40K
 Mounting Height: 3' [0.9m] A.F.G.
 Initial Delivered Lumens: 1,666
 Initial FC at grade

Type V Medium Distribution				
LED Count (x9)	4000K		5700K	
	Initial Delivered Lumens*	BUG Ratings** Per TM-15-11	Initial Delivered Lumens*	BUG Ratings** Per TM-15-11
350mA				
02	1,666	B1 U2 G1	1,730	B1 U2 G1
525mA				
02	2,333	B2 U2 G2	2,422	B2 U2 G2


* Initial delivered lumens at 25°C (77°F). Actual production yield may vary between -10 and +10% of initial delivered lumens
 ** For more information on the IES BUG (Backlight-Uplight-Glare) Rating visit: www.ies.org/PDF/Erratas/TM-15-11BugRatingsAddendum.pdf




Photometry

All published luminaire photometric testing performed to IESNA LM-79-08 standards by a NVLAP accredited laboratory. To obtain an IES file specific to your project consult: <http://lighting.cree.com/products/outdoor/bollards-and-pathway/cree-edge-pathway>

55



RESTL Test Report #: PL5759-001
 PWY-EDG-5S-**-02-E-UL-350-40K
 Initial Delivered Lumens: 1,897




PWY-EDG-5S-**-02-E-UL-350-40K
 Mounting Height: 3' [0.9m] A.F.G.
 Initial Delivered Lumens: 1,868
 Initial FC at grade

Type V Short Distribution				
LED Count (x9)	4000K		5700K	
	Initial Delivered Lumens*	BUG Ratings** Per TM-15-11	Initial Delivered Lumens*	BUG Ratings** Per TM-15-11
350mA				
02	1,868	B1 U2 G1	1,940	B1 U2 G1
525mA				
02	2,615	B1 U2 G1	2,716	B1 U2 G1

* Initial delivered lumens at 25°C (77°F). Actual production yield may vary between -10 and +10% of initial delivered lumens
 ** For more information on the IES BUG (Backlight-Uplight-Glare) Rating visit: www.ies.org/PDF/Erratas/TM-15-11BugRatingsAddendum.pdf

with Welded Base



Model	Dim. "A"	Weight*
Pathway (P3)	36" [914mm]	17.9 lbs. [8.1kg]
Pathway (P4)	42" [1068mm]	18.6 lbs. [8.4kg]
Pedestrian (P8)	96" [2438mm]	28.4 lbs [12.9kg]

* Add 4.5 lbs. [2.0kg] for 347-480V

DESCRIPTION

4 inch LED recessed narrow, medium, or wide beam downlight designed for glare free even illumination. Featuring a two-stage diffused reflector system producing smooth distribution with excellent light control and low aperture brightness. Lumen packages range from 1000 to 4000 with color temperatures of 2400K, 2700K, 3000K, 3500K, 4000K, and 5000K. Available with dim-to-warm technology – similar to halogen at full power, the 3000K LED warms smoothly as dimmed to 1850K creating a rich warm glow within the space.

Catalog #		Type
Project		
Comments		Date
Prepared by		

SPECIFICATION FEATURES

Lower Shielding Reflector

Painted die cast aluminum or spun aluminum lower reflector with a lensed upper optical chamber providing superior lumen output with minimal source brightness. Spun reflectors are offered in all Portfolio Alzak® finishes. Available with non-conductive polymer trim. Reflector is retained with two torsion springs holding the flange tight to the finished ceiling surface. Plaster lathing ring accessory offered for flush reflector transition.

Plaster Frame / Collar

Die cast aluminum 1-1/2" deep collar accommodates ceiling materials up to 2". Universal mounting bracket accepts 1/2" EMT, C channel and bar hangers and adjusts 5" vertically from above and below the ceiling.

Junction Box

Listed for (8) #12 AWG (four in, four out) 90°C conductors and feed thru branch wiring. (4) 1/2" and (2) 3/4" trade size pry outs positioned to allow straight conduit runs. Lever connectors for simple push in wiring.

Thermal

Aluminum heat sink conducts heat away from the LED module for optimal performance and long life.

LED

Chip on board with a multitude of highly efficient white LED's, combined with a high reflectance upper reflector and convex transitional lens produce even distribution with no pixilation. Rated for 50,000 hours at 70% lumen maintenance. Auto resetting, thermally protected, LED's are turned off when safe operating temperatures are exceeded. Color variation within 3-step MacAdam ellipses. Quick disconnect allows for tool-less replacement of LED engine from below ceiling. Available in 80, 90 or 97 CRI. D2W™ – dim-to-warm shifts CCT from 3000K to 1850K as fixture dims mimicking halogen sources.

Driver

Standard 120-277V 0-10V dimming driver provides flicker free dimming from 100% to 1%. Optional 120V leading edge, <1% 0-10V, Fifth Light, DMX or Lutron® Ecosystem. Driver can be serviced from above or through the aperture.

Connected Lighting Systems

WaveLinX tilemount daylight sensor includes control module, sensor and cable allowing use with the comprehensive lighting system.

LumaWatt Pro (powered by Enlighted) wireless tile mount sensor and relay accessory enables wireless control using a tile mount sensor accessory.

Code Compliance

Thermally protected and cULus listed for wet locations with covered ceiling. IP66 rated when used with IP66 gasket kit accessory. Optional City of Chicago environmental air (CCEA) marking for plenum applications. EMI/RFI emissions per FCC 47CFR Part 18 Class B consumer limits. 2000 lumen and above are Non-IC rated - Insulation must be kept 3" from top and sides of housing. IC rated up to 1500 lumens. RoHS Compliant. Photometric testing completed in accordance with IES LM 79 and TM-30 standards. LED life testing completed in accordance with LM 80 standards.

Warranty

5-year warranty




LD4B EU4B 4LBW 4LBM 4LBN

1000, 1500, 2000, 3000, 4000

Lumens LED

Narrow, Medium, or Wide Beam

New Construction



D2W™



Refer to ENERGY STAR® Qualified Products List. Can be used to comply with California Title 24 High Efficacy requirements.

SAMPLE NUMBER: LD4B15D010IEMBOD

Housing	Lumens ¹	Voltage	Driver	Options
LD4B =LED Downlight 4" Nominal Aperture LD4BCP =LED Downlight 4" Nominal Aperture, Chicago Plenum	10 =1000 lumens 15 =1500 lumens 20 =2000 lumens 30 =3000 lumens 40 =4000 lumens	Blank =120-277V	1000 - 4000 Lumen D010 =0-10V Dimming, 1% to 100%, 120V-277V D010TR =0-10V or Line Voltage Dimming, 5% to 100%, 120V-277V DE010 =0-10V Dimming, 0% to 100%, 120V-277V D5LT =Fifth Light® (DALI) Dimming, 0% to 100%, 120V-277V DMX =DMX Dimming, 0% to 100%, 120V-277V ¹³ DL2 =Lutron® Hi-Lume Forward Phase Dimming, 1% to 100%, 120V Only DL3 =Lutron® Hi-Lume 3 Wire Dimming, 1% to 100%, 120V-277V DLE =Lutron Ecosystem dimming 1% to 100%, 120V-277V	EMBOD =Bodine® Emergency Module with Remote Test Switch ³ EM7 =7W Emergency Module with Remote Test Switch ^{3,4} EM14 =14W Emergency Module with Remote Test Switch ^{3,4} IEMBOD =Bodine® Emergency Module with Integral Test Switch ³ IEM7 =7W Emergency Module with Integral Test Switch ^{3,4} IEM14 =14W Emergency Module with Integral Test Switch ^{3,4}

SAMPLE NUMBER: EU4B10208035

Power Module	Lumen Levels ¹	CRI	Color		
EU4B=4" Universal LED Module	1020 =1000, 1500, 2000 lumens 3040 =3000-4000 lumens 1015IC =1000, 1500 lumen IC rated	80 =80 CRI Minimum 90 =90 CRI Minimum 97 =97 CRI Minimum	80 CRI 27 =2700K 30 =3000K 35 =3500K 40 =4000K 50 =5000K	90 CRI 24 =2400K 27 =2700K 30 =3000K 35 =3500K 40 =4000K 50 =5000K	97 CRI 27 =2700K 30 =3000K
Dim 2 Warm 109030D2W =1000 lumen, 90 CRI, Dim 2 Warm 159030D2W =1500 lumen, 90 CRI, Dim 2 Warm 209030D2W =2000 lumen, 90 CRI, Dim 2 Warm					

SAMPLE NUMBER: 4LBM1LIE

Trim	Distribution ⁵	Flange	Finish	Options
4LB=4" LED	N =Narrow (30° Beam), Spun Aluminum M =Medium (50° Beam), Spun Aluminum W =Wide (75° Beam), Spun Aluminum S =Shallow (75° Beam), Spun Aluminum PS =Plastic Shallow (75° Beam), Injection Molded white ¹¹ CS =Cast Shallow (75° Beam), Die Cast Aluminum BA =Baffle, Spun Aluminum ⁷	0 =White Polymer Trim Ring 1 =Self-flanged ¹² 2 =White Painted Self-flanged	LI =Specular Clear ¹⁰ H =Semi-Specular Clear ¹⁰ WMH =Warm Haze ¹⁰ WH =Wheat ¹⁰ GPH =Graphite Haze ¹⁰ B =Specular Black ¹⁰ MW =Matte White MB =Matte Black ⁹ MMS =Matte Metallic Silver ⁸	E =Integral Emergency Test Switch Hole ⁶

Accessories

HSA4=Slope Adapter for 4" Aperture Housings, Specify Slope in 5° increments
TRM4=Metal Trim Ring, Specify Color²
TRR4=Rimless Trim Ring²
LGSKT4IP66=IP66 Gasket Kit
PRR4=Rimless Plaster Ring for Flush Mount²
Bar Hangers
HB26=C-channel Bar Hanger, 26" Long, Pair
HB50=C-channel Bar Hanger, 50" Long, Pair
RMB22=Wood Joist Bar Hanger, 22" Long, Pair
Transformers
H347=347 to 120V Step Down Transformer, 75VA
H347200=347 to 120V Step Down Transformer, 200VA
Connected Lighting Systems
PORLWTPD1=LumaWatt Pro wireless sensor kit (0-10V only)
TMSWPD1=WaveLinX tilemount daylight sensor (includes control module, sensor, cable and tile mount)

Notes:

- Nominal Lumens will vary depending on selected color, driver and reflector finish.
- Order spun trim with polymer trim ring or die cast with rimless flange (Consult specification sheet for color ordering information and options).
- Not available with Chicago Plenum.
- ULus approved only.
- Beam angles are nominal with LI finish trims.
- Only available with Narrow and Medium Spun Aluminum trims. Required for use with all IEMBOD, IEM7, and IEM14 housings.
- Only available with Matte White and Matte Black Finishes.
- Only available on CS distribution.
- Available only on BA and CS distributions.
- Not available on PS, CS or BA distributions.
- Matte white and self flanged only
- Flange is same finish as the reflector.
- DMX fixtures default to full on upon loss of DMX signal.

ENERGY

ENERGY DATA
Sound Rating: Class A standards
(Values at non-dimming line voltage)
Minimum Starting Temperature: -30°C (-22°F)
EMI/RFI: FCC Title 47 CFR, Part 15, Class B (Consumer)
Input Voltage: UNV (120V - 277V)
Power Factor: >0.90 (at nominal input 120-277 VAC & 100% of Rated Output Power)
Input Frequency: 50/60Hz

1000 Lumen D010		1500 Lumen D010	
Input Power: 11W	THD: <14%	Input Power: 15.5W	THD: <13%
120V Input Current: 0.09A	277V Input Current: 0.04A	120V Input Current: 0.13A	277V Input Current: 0.06A

2000 Lumen D010		3000 Lumen D010	
Input Power: 21.2W	THD: <9%	Input Power: 27.6W	THD: <10%
120V Input Current: 0.18A	277V Input Current: 0.08A	120V Input Current: 0.23A	277V Input Current: 0.10A

4000 Lumen D010	
Input Power: 41.6W	THD: <13%
120V Input Current: 0.35A	277V Input Current: 0.15A

Lumens	120V		277V	
	Inrush (A)	Duration (ms)	Inrush (A)	Duration (ms)
1000 Lumen D010	1.02	0.041	2.18	0.021
1500 Lumen D010	1.02	0.042	2.24	0.064
2000 Lumen D010	1.02	0.077	2.43	0.027
3000 Lumen D010	1.15	0.067	3.26	0.027
4000 Lumen D010	1.2	0.088	3.9	0.03



Eaton
 1121 Highway 74 South
 Peachtree City, GA 30269
 P: 770-486-4800
www.eaton.com/lighting

Specifications and
 dimensions subject to
 change without notice.

PHOTOMETRY

NARROW (30° BEAM)		CANDLEPOWER DISTRIBUTION		CONE OF LIGHT		CANDELA TABLE		ZONAL LUMEN SUMMARY			LUMINANCE	
Test Number	P201208					Degrees Vertical	Candela	Zone	Lumens	% Fixture	Average Candela Degrees	Average 0° Luminance
Housing	LD4B15D010					0	2790	0-30	926	82.1	45	489
Module	EU4B10208035					5	2550	0-40	1094	97	55	55
Trim	4LBN1LI					15	1421	0-60	1127	99.9	65	26
Lumens	1128					25	667	0-90	1128	100	75	0
Efficacy	78.9 Lm/W	35	266	90-180	0	0	85	0				
SC	0.5	45	32	0-180	1128	100						
		55	3									
		65	1									
		75	0									
		85	0									
		90	0									
		D	FC	L	W							
		5.5'	92	2.6	2.6							
		7'	57	3.4	3.4							
		8'	44	3.8	3.8							
		9'	34	4.4	4.4							
		10'	28	4.8	4.8							
		12'	19	5.8	5.8							

MEDIUM (50° BEAM)		CANDLEPOWER DISTRIBUTION		CONE OF LIGHT		CANDELA TABLE		ZONAL LUMEN SUMMARY			LUMINANCE	
Test Number	P201206					Degrees Vertical	Candela	Zone	Lumens	% Fixture	Average Candela Degrees	Average 0° Luminance
Housing	LD4B15D010					0	2267	0-30	1144	77.3	45	1072
Module	EU4B10208035					5	2227	0-40	1406	95	55	151
Trim	4LBM1LI					15	1690	0-60	1477	99.7	65	77
Lumens	1481					25	1027	0-90	1481	100	75	42
Efficacy	103.6 Lm/W	35	409	90-180	0	0	85	0				
SC	0.71	45	70	0-180	1481	100						
		55	8									
		65	3									
		75	1									
		85	0									
		90	0									
		D	FC	L	W							
		5.5'	75	3.8	3.8							
		7'	46	5	5							
		8'	35	5.6	5.6							
		9'	28	6.4	6.4							
		10'	23	7	7							
		12'	16	8.4	8.4							

WIDE (75° BEAM)		CANDLEPOWER DISTRIBUTION		CONE OF LIGHT		CANDELA TABLE		ZONAL LUMEN SUMMARY			LUMINANCE	
Test Number	P201204					Degrees Vertical	Candela	Zone	Lumens	% Fixture	Average Candela Degrees	Average 0° Luminance
Housing	LD4B15D010					0	914	0-30	816	53.8	45	4372
Module	EU4B10208035					5	925	0-40	1252	82.5	55	574
Trim	4LBW1LI					15	998	0-60	1513	99.7	65	100
Lumens	1518					25	977	0-90	1518	100	75	42
Efficacy	106.2 Lm/W	35	707	90-180	0	0	85	0				
SC	1.3	45	286	0-180	1518	100						
		55	30									
		65	4									
		75	1									
		85	0									
		90	0									
		D	FC	L	W							
		5.5'	30	7	7							
		7'	19	9	9							
		8'	14	10.4	10.4							
		9'	11	11.6	11.6							
		10'	9	13	13							
		12'	6	15.6	15.6							

SHALLOW (75° BEAM)		CANDLEPOWER DISTRIBUTION		CONE OF LIGHT		CANDELA TABLE		ZONAL LUMEN SUMMARY			LUMINANCE	
Test Number	P201210					Degrees Vertical	Candela	Zone	Lumens	% Fixture	Average Candela Degrees	Average 0° Luminance
Housing	LD4B15D010					0	688	0-30	512	34.2	45	5827
Module	EU4B10208035					5	682	0-40	816	54.5	55	4771
Trim	4LBCS1MMS					15	645	0-60	1333	89	65	3226
Lumens	1497					25	577	0-90	1497	100	75	1339
Efficacy	104.7 Lm/W	35	486	90-180	0	0	85	124				
SC	1.16	45	380	0-180	1497	100						
		55	253									
		65	126									
		75	32									
		85	1									
		90	0									
		D	FC	L	W							
		5.5'	23	6.2	6.2							
		7'	14	8	8							
		8'	11	9.2	9.2							
		9'	9	10.4	10.4							
		10'	7	11.6	11.6							
		12'	5	13.8	13.8							

PHOTOMETRY

NARROW (25° BEAM)		CANDLEPOWER DISTRIBUTION		CONE OF LIGHT		CANDELA TABLE		ZONAL LUMEN SUMMARY			LUMINANCE	
Test Number	PP201209					Degrees Vertical	Candela	Zone	Lumens	% Fixture	Average Candela Degrees	Average 0° Luminance
Housing	LD4B40D010					0	7625	0-30	2531	82.1	45	1337
Module	EU4B30408035					5	6969	0-40	2989	97	55	149
Trim	4LBN1LI					15	3883	0-60	3080	99.9	65	67
Lumens	3083					25	1822	0-90	3083	100	75	0
Efficacy	73.8 Lm/W	35	727	90-180	0	0	85	0				
SC	0.5	45	87	0-180	3083	100						
		55	8									
		65	3									
		75	0									
		85	0									
		90	0									
		D	FC	L	W							
		5.5'	252	2.6	2.6							
7'	156	3.4	3.4									
8'	119	3.8	3.8									
9'	94	4.4	4.4									
10'	76	4.8	4.8									
12'	53	5.8	5.8									

MEDIUM (50° BEAM)		CANDLEPOWER DISTRIBUTION		CONE OF LIGHT		CANDELA TABLE		ZONAL LUMEN SUMMARY			LUMINANCE	
Test Number	P201207					Degrees Vertical	Candela	Zone	Lumens	% Fixture	Average Candela Degrees	Average 0° Luminance
Housing	LD4B40D010					0	6015	0-30	3036	77.3	45	2844
Module	EU4B30408035					5	5909	0-40	3731	95	55	400
Trim	4LBM1LI					15	4484	0-60	3918	99.7	65	205
Lumens	3929					25	2725	0-90	3929	100	75	113
Efficacy	94 Lm/W	35	1085	90-180	0	0	85	0				
SC	0.71	45	186	0-180	3929	100						
		55	21									
		65	8									
		75	3									
		85	0									
		90	0									
		D	FC	L	W							
		5.5'	199	3.8	3.8							
7'	123	5	5									
8'	94	5.6	5.6									
9'	74	6.4	6.4									
10'	60	7	7									
12'	42	8.4	8.4									

WIDE (75° BEAM)		CANDLEPOWER DISTRIBUTION		CONE OF LIGHT		CANDELA TABLE		ZONAL LUMEN SUMMARY			LUMINANCE	
Test Number	P201205					Degrees Vertical	Candela	Zone	Lumens	% Fixture	Average Candela Degrees	Average 0° Luminance
Housing	LD4B40D010					0	2499	0-30	2230	53.8	45	11948
Module	EU4B30408035					5	2528	0-40	3421	82.5	55	1569
Trim	4LBW1LI					15	2727	0-60	4134	99.7	65	274
Lumens	4148					25	2670	0-90	4148	100	75	113
Efficacy	99.2 Lm/W	35	1933	90-180	0	0	85	0				
SC	1.3	45	780	0-180	4148	100						
		55	83									
		65	11									
		75	3									
		85	0									
		90	0									
		D	FC	L	W							
		5.5'	83	7	7							
7'	51	9	9									
8'	39	10.4	10.4									
9'	31	11.6	11.6									
10'	25	13	13									
12'	17	15.6	15.6									

SHALLOW (75° BEAM)		CANDLEPOWER DISTRIBUTION		CONE OF LIGHT		CANDELA TABLE		ZONAL LUMEN SUMMARY			LUMINANCE	
Test Number	P201211					Degrees Vertical	Candela	Zone	Lumens	% Fixture	Average Candela Degrees	Average 0° Luminance
Housing	LD4B40D010					0	1880	0-30	1400	34.2	45	15933
Module	EU4B30508035					5	1864	0-40	2230	54.5	55	13046
Trim	4LBCS1MMS					15	1763	0-60	3645	89	65	8819
Lumens	4093					25	1578	0-90	4093	100	75	3657
Efficacy	97.9 Lm/W	35	1329	90-180	0	0	85	323				
SC	1.16	45	1040	0-180	4093	100						
		55	691									
		65	344									
		75	87									
		85	3									
		90	0									
		D	FC	L	W							
		5.5'	62	6.2	6.2							
7'	38	8	8									
8'	29	9.2	9.2									
9'	23	10.4	10.4									
10'	19	11.6	11.6									
12'	13	13.8	13.8									

DESCRIPTION

6 inch LED recessed narrow, medium, or wide beam downlight designed for glare free even illumination. Featuring a two-stage diffused reflector system producing smooth distribution with excellent light control and low aperture brightness. Lumen packages range from 1000 to 7000 with color temperatures of 2400K, 2700K, 3000K, 3500K, 4000K, and 5000K. Available with dim-to-warm technology – similar to halogen at full power, the 3000K LED warms smoothly as dimmed to 1850K creating a rich warm glow within the space.

Catalog #		Type
Project		
Comments		Date
Prepared by		

SPECIFICATION FEATURES

Lower Shielding Reflector

Painted die cast aluminum or spun aluminum lower reflector with a lensed upper optical chamber providing superior lumen output with minimal source brightness. Spun reflectors are offered in all Portfolio Alzak® finishes. Available with non-conductive polymer trim. Reflector is retained with two torsion springs holding the flange tight to the finished ceiling surface.

Plaster Frame / Collar

Die cast aluminum 1-1/2" deep collar accommodates ceiling materials up to 2". Universal mounting bracket accepts 1/2" EMT, C channel and bar hangers and adjusts 5" vertically from above and below the ceiling.

Junction Box

Listed for (8) #12 AWG (four in, four out) 90°C conductors and feed thru branch wiring. (4) 1/2" and (2) 3/4" trade size pry outs positioned to allow straight conduit runs. Lever connectors for simple push in wiring.

Thermal

Aluminum heat sink conducts heat away from the LED module for optimal performance and long life.

LED

Chip on board with a multitude of highly efficient white LED's, combined with a high reflectance upper reflector and convex transitional lens produce even distribution with no pixilation. Rated for 50,000 hours at 70% lumen maintenance. Auto resetting, thermally protected, LED's are turned off when safe operating temperatures are exceeded. Color variation within 3-step MacAdam ellipses. Quick disconnect allows for tool-less replacement of LED engine from below ceiling. Available in 80, 90 or 97 CRI. D2W™ – dim-to-warm shifts CCT from 3000K to 1850K as fixture dims mimicking halogen sources.

Driver

Standard 120-277V 0-10V dimming driver provides flicker free dimming from 100% to 1% (offered up to 4000 lumens). Optional 120V leading edge, <1% 0-10V, Fifth Light, DMX or Lutron® Ecosystem. Driver can be serviced from above or through the aperture.

Connected Lighting Systems

WaveLinX tilemount daylight sensor includes control module, sensor and cable allowing use with the comprehensive lighting system.

LumaWatt Pro (powered by Enlighted) wireless tile mount sensor and relay accessory enables wireless control using a tile mount sensor accessory.

Code Compliance

Thermally protected and cULus listed for wet locations with covered ceiling. IP66 rated when used with IP66 gasket kit accessory. Optional City of Chicago environmental air (CEEA) marking for plenum applications. EMI/RFI emissions per FCC 47CFR Part 18 Class B consumer limits. Non-IC rated - Insulation must be kept 3" from top and sides of housing. IC rated up to 1500 lumens. 5000 lumen and above are marked spacing and must follow spacing requirements. RoHS Compliant. Photometric testing completed in accordance with IES LM 79 and TM-30 standards. LED life testing completed in accordance with LM 80 standards.

Warranty


5-year warranty



**LD6B EU6B
6LBW 6LBM
6LBN**

1000 - 7000 lumens LED

Narrow, Medium, or Wide Beam
New Construction



Refer to ENERGY STAR® Qualified Products List. Can be used to comply with California Title 24 High Efficacy requirements.

ORDERING INFORMATION

SAMPLE NUMBER: LD6B15D010EMBOD

Housing	Lumens ¹	Voltage	Driver	Options
LD6B =LED Downlight 6" Nominal Aperture LD6BCP =LED Downlight 6" Nominal Aperture, Chicago Plenum	10 =1000 lumens 15 =1500 lumens 20 =2000 lumens 30 =3000 lumens 40 =4000 lumens 50 =5000 lumens ¹⁰ 60 =6000 lumens ¹⁰ 70 =7000 lumens ¹⁰	Blank =120-277V	1000 - 4000 Lumen D010 =0-10V Dimming, 1% to 100%, 120V-277V D010TR =0-10V or Line Voltage Dimming, 5% to 100%, 120V-277V DE010 =0-10V Dimming, 0% to 100%, 120V-277V D5LT =Fifth Light® (DALI) Dimming, 0% to 100%, 120V-277V DMX =DMX Dimming, 0% to 100%, 120V-277V ¹⁴ DL2 =Lutron® Hi-Lume Forward Phase Dimming, 1% to 100%, 120V Only DL3 =Lutron® Hi-Lume 3 Wire Dimming, 1% to 100%, 120V-277V DLE =Lutron Ecosystem dimming 1% to 100%, 120V-277V 5000, 6000, and 7000 Lumen D010TE =0-10V 1% or Trailing Edge, 10% to 100%, 120V-277V (120V Only for Trailing Edge Dimming)	EMBOD =Bodine® Emergency Module with Remote Test Switch ³ EM7 =7W Emergency Module with Remote Test Switch ^{3,4} EM14 =14W Emergency Module with Remote Test Switch ^{3,4} IEMBOD =Bodine® Emergency Module with Integral Test Switch ³ IEM7 =7W Emergency Module with Integral Test Switch ^{3,4} IEM14 =14W Emergency Module with Integral Test Switch ^{3,4}

SAMPLE NUMBER: EU6B10208035

Power Module	Lumen Levels ¹	CRI	Color			
EU6B =6" Universal LED Module	1020 =1000, 1500, 2000 lumens 3050 =3000, 4000, 5000 lumens 6070 =6000, 7000 lumens 1015IC =1000, 1500 lumen IC rated	80 =80 CRI Minimum 90 =90 CRI Minimum 97 =97 CRI Minimum	80 CRI 27 =2700K 30 =3000K 35 =3500K 40 =4000K 50 =5000K	90 CRI 24 =2400K 27 =2700K 30 =3000K 35 =3500K 40 =4000K 50 =5000K	97 CRI 27 =2700K 30 =3000K	
	Dim 2 Warm 109030D2W =1000 lumen, 90 CRI, Dim 2 Warm 159030D2W =1500 lumen, 90 CRI, Dim 2 Warm 209030D2W =2000 lumen, 90 CRI, Dim 2 Warm					

SAMPLE NUMBER: 6LBM1LIE

Trim	Distribution ⁵	Flange	Finish	Options
6LB =6" LED	N =Narrow (30° Beam), Spun Aluminum M =Medium (50° Beam), Spun Aluminum W =Wide (75° Beam), Spun Aluminum S =Shallow (75° Beam), Spun Aluminum ¹² PS =Plastic Shallow (75° Beam), Injection Molded white ^{11, 12} CS =Cast Shallow (75° Beam), Die Cast Aluminum ¹² BA =Baffle (50° Beam), Spun Aluminum ⁷	0 =White Polymer Trim Ring 1 =Self-flanged ¹³ 2 =White Painted Self-flanged	LI =Specular Clear ⁹ H =Semi-Specular Clear ⁹ WMH =Warm Haze ⁹ WH =Wheat ⁹ GPH =Graphite Haze ⁹ B =Specular Black ⁹ MW =Matte White MB =Matte Black ⁹ MMS =Matte Metallic Silver ⁹	E =Integral Emergency Test Switch Hole ⁹

Accessories

HSA6=Slope Adapter for 6" Aperture Housings, Specify Slope**TRM6**=Metal Trim Ring, Specify Color²**PRR6**=Rimless Trim Ring for Flush Mount²**LGSKT6IP66**=IP66 Gasket Kit**DT6**=Deco Trim²

Bar Hangers

HB26=C-channel Bar Hanger, 26" Long, Pair**HB50**=C-channel Bar Hanger, 50" Long, Pair**RMB22**=Wood Joist Bar Hanger, 22" Long, Pair

Transformers

H347=347 to 120V Step Down Transformer, 75VA**H347200**=347 to 120V Step Down Transformer, 200VA

Connected Lighting Systems

PORLWTPD1=LumaWatt Pro wireless sensor kit (0-10V only)**TMSWPD1**=WaveLinX tilemount daylight sensor (includes control module, sensor, cable and tile mount)

Notes:

- Nominal Lumens will vary depending on selected color, driver and reflector finish.
- Order trim with polymer trim ring (Consult specification sheet for color ordering information and options).
- Not available with Chicago Plenum.
- ULus listed only
- Beam angles are nominal with LI finish trims.
- Only available with Narrow and Medium Spun Aluminum trims. Required for use with all IEMBOD, IEM7, and IEM14 housings. Requires above ceiling access with wide beam trim.
- Only available with Matte White and Matte Black Finishes.
- Available only on CS distributions.
- Not available on PS, CS or BA distributions.
- Product is marked spacing and must be installed with the following minimum spacing.
 - Center to center of adjacent luminaires: 36"
 - Center of luminaire to side of building member: 18"
 - Minimum overhead: 1/2"
 - Not available with CS or PS trims
- PS available in self-flanged MW finish only.
- Offered up to 2000 lumens
- Flange is the same finish as the reflector
- DMX fixtures default to full on upon loss of DMX signal.

ENERGY

ENERGY DATA
Sound Rating: Class A standards
(Values at non-dimming line voltage)
Minimum Starting Temperature: -30°C (-22°F)
EMI/RFI: FCC Title 47 CFR, Part 15, Class B (Consumer)
Input Voltage: UNV (120V - 277V)
Power Factor: >0.90 (at nominal input 120-277 VAC & 100% of Rated Output Power)
Input Frequency: 50/60Hz

1000 Lumen D010		1500 Lumen D010	
Input Power: 11W	THD: <14%	Input Power: 15.5W	THD: <13%
120V Input Current: 0.08A	277V Input Current: 0.04A	120V Input Current: 0.13A	277V Input Current: 0.06A
2000 Lumen D010		3000 Lumen D010	
Input Power: 21.2W	THD: <9%	Input Power: 27.6W	THD: <10%
120V Input Current: 0.18A	277V Input Current: 0.08A	120V Input Current: 0.23A	277V Input Current: 0.10A
4000 Lumen D010		5000 Lumen D010TE	
Input Power: 41.6W	THD: <13%	Input Power: 57.9W	THD: <14%
120V Input Current: 0.35A	277V Input Current: 0.15A	120V Input Current: 0.49A	277V Input Current: 0.22A
6000 Lumen D010TE		7000 Lumen D010TE	
Input Power: 59.7W	THD: <14%	Input Power: 75.8W	THD: <13%
120V Input Current: 0.50A	277V Input Current: 0.22A	120V Input Current: 0.64A	277V Input Current: 0.29A

Lumens	120V		277V	
	Inrush (A)	Duration (ms)	Inrush (A)	Duration (ms)
1000 Lumen D010	1.02	0.041	2.18	0.021
1500 Lumen D010	1.02	0.042	2.24	0.064
2000 Lumen D010	1.02	0.077	2.43	0.027
3000 Lumen D010	1.15	0.067	3.26	0.027
4000 Lumen D010	1.2	0.088	3.9	0.03
5000 Lumen D010TE	5.1	0.132	10.2	0.153
6000 Lumen D010TE	5.4	0.123	10.8	0.154
7000 Lumen D010TE	4.9	0.13	9.8	0.156

PHOTOMETRY

NARROW (30° BEAM)		CANDLEPOWER DISTRIBUTION		CONE OF LIGHT		CANDELA TABLE		ZONAL LUMEN SUMMARY			LUMINANCE	
Test Number	P201217					Degrees Vertical	Candela	Zone	Lumens	% Fixture	Average Candela Degrees	Average 0° Luminance
Housing	LD6B15D010					0	2709	0-30	960	80.4	45	677
Module	EU6B10208035					5	2526	0-40	1149	96.2	55	76
Trim	6LBN1LI					15	1468	0-60	1193	99.9	65	26
Lumens	1195					25	708	0-90	1195	100	75	0
Efficacy	83.6 Lm/W	35	299	90-180	0	0	85	0				
SC	0.53	45	44	0-180	1195	100						
		D	FC	L	W							
		5.5'	90	2.8	2.8							
		7'	55	3.6	3.6							
		8'	42	4.2	4.2							
		9'	33	4.6	4.6							
		10'	27	5.2	5.2							
		12'	19	6.2	6.2							

MEDIUM (50° BEAM)		CANDLEPOWER DISTRIBUTION		CONE OF LIGHT		CANDELA TABLE		ZONAL LUMEN SUMMARY			LUMINANCE	
Test Number	P201215					Degrees Vertical	Candela	Zone	Lumens	% Fixture	Average Candela Degrees	Average 0° Luminance
Housing	LD6B15D010					0	1683	0-30	990	73.6	45	1159
Module	EU6B10208035					5	1661	0-40	1265	94	55	130
Trim	6LBM1LI					15	1386	0-60	1341	99.7	65	87
Lumens	1345					25	993	0-90	1345	100	75	71
Efficacy	94.1 Lm/W	35	430	90-180	0	0	85	0				
SC	0.85	45	76	0-180	1345	100						
		D	FC	L	W							
		5.5'	56	4.6	4.6							
		7'	34	5.8	5.8							
		8'	26	6.6	6.6							
		9'	21	7.6	7.6							
		10'	17	8.4	8.4							
		12'	12	10	10							

WIDE (75° BEAM)		CANDLEPOWER DISTRIBUTION		CONE OF LIGHT		CANDELA TABLE		ZONAL LUMEN SUMMARY			LUMINANCE	
Test Number	P201213					Degrees Vertical	Candela	Zone	Lumens	% Fixture	Average Candela Degrees	Average 0° Luminance
Housing	LD6B15D010					0	963	0-30	785	51.7	45	4835
Module	EU6B10208035					5	963	0-40	1207	79.5	55	1055
Trim	6LBW1LI					15	976	0-60	1510	99.4	65	151
Lumens	1519					25	913	0-90	1519	100	75	84
Efficacy	106.2 Lm/W	35	687	90-180	0	0	85	0				
SC	1.23	45	316	0-180	1519	100						
		D	FC	L	W							
		5.5'	32	6.6	6.6							
		7'	20	8.6	8.6							
		8'	15	9.8	9.8							
		9'	12	11	11							
		10'	10	12.2	12.2							
		12'	7	14.6	14.6							

SHALLOW (75° BEAM)		CANDLEPOWER DISTRIBUTION		CONE OF LIGHT		CANDELA TABLE		ZONAL LUMEN SUMMARY			LUMINANCE	
Test Number	P201212					Degrees Vertical	Candela	Zone	Lumens	% Fixture	Average Candela Degrees	Average 0° Luminance
Housing	LD6B15D010					0	710	0-30	529	34.2	45	36260
Module	EU6B10208035					5	704	0-40	843	54.5	55	29687
Trim	6LBCS1MMS					15	666	0-60	1377	89	65	20068
Lumens	1546					25	596	0-90	1546	100	75	8318
Efficacy	110.4 Lm/W	35	502	90-180	0	0	85	749				
SC	1.16	45	393	0-180	1546	100						
		D	FC	L	W							
		5.5'	24	6.2	6.2							
		7'	15	8	8							
		8'	11	9.2	9.2							
		9'	9	10.4	10.4							
		10'	7	11.6	11.6							
		12'	5	13.8	13.8							

PHOTOMETRY

NARROW (30° BEAM)		CANDLEPOWER DISTRIBUTION		CONE OF LIGHT		CANDELA TABLE		ZONAL LUMEN SUMMARY			LUMINANCE	
Test Number	P201218					Degrees Vertical	Candela	Zone	Lumens	% Fixture	Average Candela Degrees	Average 0° Luminance
Housing	LD6B40D010					0	7716	0-30	2735	80.4	45	1928
Module	EU6B30508035					5	7196	0-40	3274	96.2	55	215
Trim	6LBN1LI					15	4183	0-60	3399	99.9	65	74
Lumens	3404					25	2017	0-90	3404	100	75	0
Efficacy	81.4 Lm/W	35	853	90-180	0	0	85	0				
SC	0.53	45	126	0-180	3404	100						
		55	11									
		65	3									
		75	0									
		85	0									
		90	0									
				D	FC	L	W					
				5.5'	255	2.8	2.8					
				7'	158	3.6	3.6					
				8'	121	4.2	4.2					
				9'	95	4.6	4.6					
				10'	77	5.2	5.2					
				12'	54	6.2	6.2					

MEDIUM (50° BEAM)		CANDLEPOWER DISTRIBUTION		CONE OF LIGHT		CANDELA TABLE		ZONAL LUMEN SUMMARY			LUMINANCE	
Test Number	P201216					Degrees Vertical	Candela	Zone	Lumens	% Fixture	Average Candela Degrees	Average 0° Luminance
Housing	LD6B40D010					0	4794	0-30	2819	73.6	45	3303
Module	EU6B30508035					5	4731	0-40	3602	94	55	370
Trim	6LBM1LI					15	3946	0-60	3819	99.7	65	251
Lumens	3831					25	2829	0-90	3831	100	75	205
Efficacy	91.7 Lm/W	35	1226	90-180	0	0	85	0				
SC	0.85	45	216	0-180	3831	100						
		55	20									
		65	10									
		75	5									
		85	0									
		90	0									
				D	FC	L	W					
				5.5'	159	4.6	4.6					
				7'	98	5.8	5.8					
				8'	75	6.6	6.6					
				9'	59	7.6	7.6					
				10'	48	8.4	8.4					
				12'	33	10	10					

WIDE (75° BEAM)		CANDLEPOWER DISTRIBUTION		CONE OF LIGHT		CANDELA TABLE		ZONAL LUMEN SUMMARY			LUMINANCE	
Test Number	P201214					Degrees Vertical	Candela	Zone	Lumens	% Fixture	Average Candela Degrees	Average 0° Luminance
Housing	LD6B40D010					0	2742	0-30	2236	51.7	45	13769
Module	EU6B30508035					5	2742	0-40	3439	79.5	55	3006
Trim	6LBW1LI					15	2778	0-60	4301	99.4	65	430
Lumens	4326					25	2600	0-90	4326	100	75	234
Efficacy	103.5 Lm/W	35	1957	90-180	0	0	85	0				
SC	1.23	45	899	0-180	4326	100						
		55	159									
		65	17									
		75	6									
		85	0									
		90	0									
				D	FC	L	W					
				5.5'	91	6.6	6.6					
				7'	56	8.6	8.6					
				8'	43	9.8	9.8					
				9'	34	11	11					
				10'	27	12.2	12.2					
				12'	19	14.6	14.6					

SHALLOW (75° BEAM)		CANDLEPOWER DISTRIBUTION		CONE OF LIGHT		CANDELA TABLE		ZONAL LUMEN SUMMARY			LUMINANCE	
Test Number	P35144					Degrees Vertical	Candela	Zone	Lumens	% Fixture	Average Candela Degrees	Average 0° Luminance
Housing	LD6B40D010					0	2022	0-30	1506	34.2	45	17139
Module	EU6B30508035					5	2005	0-40	2399	54.5	55	14033
Trim	6LBCS1MMS					15	1897	0-60	3921	89	65	9486
Lumens	4403					25	1697	0-90	4403	100	75	3933
Efficacy	105.3 Lm/W	35	1430	90-180	0	0	85	348				
SC	1.16	45	1119	0-180	4403	100						
		55	743									
		65	370									
		75	94									
		85	3									
		90	0									
				D	FC	L	W					
				5.5'	67	6.2	6.2					
				7'	41	8	8					
				8'	32	9.2	9.2					
				9'	25	10.4	10.4					
				10'	20	11.6	11.6					
				12'	14	13.8	13.8					

Acion

Large LED Accent

ACCL / BLK



Features


The Amerlux Acion accent luminaire employs solid state technology and precision engineering to provide small scale LED solutions in landscape and architecture layouts. All components are encapsulated inside a single attractive enclosure designed for superior performance in weather resistant applications. Offered in a choice of beam spreads, finishes, and color temperatures, two mounting options and glare shield are also available.

Product Overview

Wattage:	17W
Lumen Output:	1,360 lm
Color Temp:	2,700K / 3,000K / 3,500K
Dimming:	ELV at 120v only

PROJECT:

TYPE:



Construction:

- Die-cast aluminum
- IP67 sealed optical chamber and integral driver chamber
- Easy "two-screw" integral driver access, does not disturb optical chamber seal
- Flush lens prevents puddles/water deposits in upward facing applications
- Knuckle mount
- Vertical aiming lock, with tamper-resistant tooled locking after final aiming

Optics:

- Lumen maintenance: 70% @ 50,000 hours
- 10°, 15°, 30°, 40°, 60°, 60x10, 60x30, 90x60 beam spreads are available with secondary shaping lens

Electrical:

- Integral driver
- Input voltage 120v-277v auto-sensing
- 1/2" NPSM wire entry
- Drive current 700mA
- Power consumption 17W
- ELV dimmable at 120v only

ETL listed, suitable for wet locations.

Accessories:

- Ground Stake (**GSP17**)
- Ground Spike (**GSP2**)
- Junction Box (**JBOX**)
- Junction Mount (**JCOV**)

Optical Accessories:

- Hexell Louver (**HCL**)
- Half Glare Shield (**HGL**)

Finish:

Premium quality thermoset polyester powdercoat for a durable finish.


BLK -Satin Black
CLB -Classic Bronze

GRN -Green
CSTM -Custom


PROJECT:

TYPE:


Accessories:



Optical Accessories:



Optical Performance:



Data represents the use of light shaping filters
Complete photometric data (ies format) available upon request

Ordering Information

Model	OCT	Beam Spread	Approx. Lumens	Total Efficacy	Mounting	Finish	Accessories	Optical Accessories		
ACCL	27 (2,700K)	Symmetric Pattern	10 (10°)	1240-1360	72-80 lm/W	K (Knuckle)	BLK CLB GRN CSTM	GSP17 GSP2 JBOX JCOV	HCL HGL	
			15 (15°)	1190-1305	70-76 lm/W					
			30 (30°)	1140-1250	67-73 lm/W					
			40 (40°)	1130-1250	66-73 lm/W					
			60 (60°)	1110-1190	65-70 lm/W					
	30 (3,000K)	Horizontal Pattern	H6010 (60x10)	980-1180	57-69 lm/W					
			H6030 (60x30)	1070-1190	62-70 lm/W					
			H9060 (90x60)	1050-1170	61-68 lm/W					
			Vertical Pattern	V6010 (60x10)	1180-980					69-57 lm/W
				V6030 (60x30)	1190-1070					70-62 lm/W
35 (3,500K)		V9060 (90x60)	1170-1050	68-61 lm/W						

Ordering options shown as **BOLD**. Example: **ACCL/27/40/K/BLK**

Cree Edge™ Series

P1, P2, P3, P4, P5

LED Area Luminaire – Round

Product Description

The Cree Edge™ Series has a slim, low profile design. Its rugged cast aluminum housing minimizes wind load requirements and features an integral, weathertight LED driver compartment, spun vented cover, high performance aluminum heat sinks and leaf/debris guard.

Applications: Auto Dealerships, parking lots, campuses, facade lighting and general site lighting applications

Performance Summary


Patented NanoOptic® Product Technology
Made in the U.S.A. of U.S. and imported parts
CRI: Minimum 70 CRI
CCT: 4000K (+/- 300K), 5700K (+/- 500K) standard
Limited Warranty*: 10 years on luminaire/10 years on Colorfast DeltaGuard® finish

* See <http://lighting.cree.com/warranty> for warranty terms

Accessories

Field-Installed	
Bird Spikes XA-BRDSPK	Backlight Control Shields XA-20BLS-4 - Four-pack - Unpainted stainless steel

R3 Mount



LED Count (x10)	Weight
04	33.8 lbs. (15.3kg)
06	35.2 lbs. (15.9kg)
08	37.0 lbs. (16.8kg)
10	40.7 lbs. (18.5kg)
12	42.4 lbs. (19.3kg)

R4/R5 Mount - see page 14 for weight & dimensions

Ordering Information

Example: ARE-EDR-2M-R3-12-E-UL-SV-350

ARE-EDR	Product	Optic	Mounting*	LED Count (x10)	Series	Voltage	Color Options	Drive Current	Options	
	ARE-EDR	2M Type II Medium 2MB Type II Medium w/BLS 2MP Type II Medium w/Partial BLS 3M Type III Medium 3MB Type III Medium w/BLS	3MP Type III Medium w/Partial BLS 4M Type IV Medium 4MB Type IV Medium w/BLS 4MP Type IV Medium w/Partial BLS 5M Type V Medium 5S Type V Short	R3 Spider, Center Tenon, 2-3/8" to 3" OD R4 Spider, Center Direct, 4" Square R5 Spider, Center Direct, 5" Round	04** 06** 08** 10 12	E	UL Universal 120-277V UH Universal 347-480V	BK Black BZ Bronze SV Silver WH White	350 350mA 525 525mA 700 700mA - Available with 40-60 LEDs	DIM 0-10V Dimming - Control by others - Refer to Dimming spec sheet for details - Can't exceed specified drive current F Fuse - When code dictates fusing, use time delay fuse - Available with UL voltage only - Available for U.S. applications only HL Hi/Low (Dual Circuit Input) - Refer to HL spec sheet for details - Sensor not included P Photocell - Available with UL voltage only 40K 4000K Color Temperature - Minimum 70 CRI - Color temperature per luminaire

* Reference EPA and pole configuration suitability data beginning on page 14
 ** Consists of multiple 20 LED light bars. 40, 60, and 80 LED units use blanks as needed in place of populated light bars
 NOTE: Price adder may apply depending on configuration



Product Specifications

CONSTRUCTION & MATERIALS

- Slim, low profile, minimizing wind load requirements
- Luminaire sides are rugged die cast aluminum with integral, weathertight LED driver compartment, spun vented cover, and high performance aluminum heat sinks
- R3 spider mount hub slip-fits over a 2.375" (60mm) to 3" (76mm) O.D. steel or aluminum tenon or pole and secures with eight set screws
- R4 spider mount fits directly inside 4" (102mm) square pole and secures to pole with four set screws
- R5 spider mount fits directly inside of a 5" (127mm) round pole to provide a clean hardware-less outer appearance
- Includes leaf/debris guard
- Exclusive Colorfast DeltaGuard® finish features an E-Coat epoxy primer with an ultra-durable powder topcoat, providing excellent resistance to corrosion, ultraviolet degradation and abrasion. Black, bronze, silver, and white are available
- **Weight:** See Dimensions and Weight charts on pages 1 and 14

ELECTRICAL SYSTEM

- **Input Voltage:** 120-277V or 347-480V, 50/60Hz, Class 1 drivers
- **Power Factor:** > 0.9 at full load
- **Total Harmonic Distortion:** < 20% at full load
- **10V Source Current:** 40-80 LEDs: 0.15mA; 100-120 LEDs: 0.30mA
- Integral 10kV surge suppression protection standard
- When code dictates fusing, a slow blow fuse or type C/D breaker should be used to address inrush current

REGULATORY & VOLUNTARY QUALIFICATIONS

- cULus Listed
- Suitable for wet locations
- Meets FCC Part 15, Subpart B, Class A standards for conducted and radiated emissions
- Enclosure rated IP66 per IEC 60529 when ordered without P option
- Certified to ANSI C136.31-2001, 1.5G normal vibration standards when ordered with R3, R4 and R5 mounts
- 10kV surge suppression protection tested in accordance with IEEE/ANSI C62.41.2
- Luminaire and finish endurance tested to withstand 5,000 hours of elevated ambient salt fog conditions as defined in ASTM Standard B 117
- DLC qualified. Exceptions apply when ordered with full backlight control or 3MP optic. Please refer to www.designlights.org/QPL for most current information
- Meets Buy American requirements within ARRA

Electrical Data*							
LED Count (x10)	System Watts 120-480V	Total Current (A)					
		120V	208V	240V	277V	347V	480V
350mA							
04	46	0.36	0.23	0.21	0.20	0.15	0.12
06	66	0.52	0.31	0.28	0.26	0.20	0.15
08	90	0.75	0.44	0.38	0.34	0.26	0.20
10	110	0.92	0.53	0.47	0.41	0.32	0.24
12	130	1.10	0.63	0.55	0.48	0.38	0.28
525mA							
04	70	0.58	0.34	0.31	0.28	0.21	0.16
06	101	0.84	0.49	0.43	0.38	0.30	0.22
08	133	1.13	0.66	0.58	0.51	0.39	0.28
10	171	1.43	0.83	0.74	0.66	0.50	0.38
12	202	1.69	0.98	0.86	0.77	0.59	0.44
700mA							
04	93	0.78	0.46	0.40	0.36	0.27	0.20
06	134	1.14	0.65	0.57	0.50	0.39	0.29

* Electrical data at 25°C (77°F). Actual wattage may differ by +/- 10% when operating between 120-480V +/- 10%

Recommended Cree Edge™ Series Lumen Maintenance Factors (LMF) ¹					
Ambient	Initial LMF	25K hr Projected ² LMF	50K hr Projected ² LMF	75K hr Calculated ³ LMF	100K hr Calculated ³ LMF
5°C (41°F)	1.04	1.01	0.99	0.98	0.96
10°C (50°F)	1.03	1.00	0.98	0.97	0.95
15°C (59°F)	1.02	0.99	0.97	0.96	0.94
20°C (68°F)	1.01	0.98	0.96	0.95	0.93
25°C (77°F)	1.00	0.97	0.95	0.94	0.92

¹ Lumen maintenance values at 25°C are calculated per TM-21 based on LM-80 data and in-situ luminaire testing


² In accordance with IESNA TM-21-11, Projected Values represent interpolated value based on time durations that are within six times (6X) the IESNA LM-80-08 total test duration (in hours) for the device under testing (DUT) i.e. the packaged LED chip

³ In accordance with IESNA TM-21-11, Calculated Values represent time durations that exceed six times (6X) the IESNA LM-80-08 total test duration (in hours) for the device under testing (DUT) i.e. the packaged LED chip


Photometry

All published luminaire photometric testing performed to IESNA LM-79-08 standards by a NVLAP accredited laboratory. To obtain an IES file specific to your project consult: <http://lighting.cree.com/products/outdoor/area/cree-edge-series-1>

2M



CSA Test Report #: 6371
ARE-EDG-2M-**-06-E-UL-700-40K
Initial Delivered Lumens: 10,985



ARE-EDR-2M-**-10-E-UL-525-40K
Mounting Height: 25' (7.6m) A.F.G.
Initial Delivered Lumens: 17,504
Initial FC at grade

Type II Medium Distribution				
LED Count (x10)	4000K		5700K	
	Initial Delivered Lumens*	BUG Ratings** Per TM-15-11	Initial Delivered Lumens*	BUG Ratings** Per TM-15-11
350mA				
04	5,003	B1 U0 G1	5,102	B1 U0 G1
06	7,418	B2 U0 G2	7,565	B2 U0 G2
08	9,891	B2 U0 G2	10,087	B2 U0 G2
10	12,334	B2 U0 G2	12,578	B2 U0 G2
12	14,801	B3 U0 G3	15,094	B3 U0 G3
525mA				
04	7,099	B2 U0 G2	7,248	B2 U0 G2
06	10,527	B2 U0 G2	10,748	B2 U0 G2
08	14,037	B3 U0 G3	14,331	B3 U0 G3
10	17,504	B3 U0 G3	17,870	B3 U0 G3
12	21,004	B3 U0 G3	21,444	B3 U0 G3
700mA				
04	8,379	B2 U0 G2	8,549	B2 U0 G2
06	12,425	B2 U0 G2	12,678	B2 U0 G2

* Initial delivered lumens at 25°C (77°F). Actual production yield may vary between -10 and +10% of initial delivered lumens

** For more information on the IES BUG (Backlight-Uplight-Glare) Rating visit: www.ies.org/PDF/Erratas/TM-15-11BugRatingsAddendum.pdf




Cree Edge™ LED Area Luminaire – Round


Photometry

All published luminaire photometric testing performed to IESNA LM-79-08 standards by a NVLAP accredited laboratory. To obtain an IES file specific to your project consult: <http://lighting.cree.com/products/outdoor/area/cree-edge-series-1>

2MB



CSA Test Report #: 6447
 ARE-EDG-2MB-**-06-E-UL-700-40K
 Initial Delivered Lumens: 7,953



ARE-EDR-2MB-**-10-E-UL-525-40K
 Mounting Height: 25' (7.6m) A.F.G.
 Initial Delivered Lumens: 13,185
 Initial FC at grade

Type II Medium Distribution w/BLS				
LED Count (x10)	4000K		5700K	
	Initial Delivered Lumens*	BUG Ratings** Per TM-15-11	Initial Delivered Lumens*	BUG Ratings** Per TM-15-11
350mA				
04	3,768	B1 U0 G1	3,843	B1 U0 G1
06	5,588	B1 U0 G1	5,698	B1 U0 G1
08	7,450	B1 U0 G2	7,598	B1 U0 G2
10	9,291	B1 U0 G2	9,475	B1 U0 G2
12	11,149	B1 U0 G2	11,370	B1 U0 G2
525mA				
04	5,348	B1 U0 G1	5,460	B1 U0 G1
06	7,930	B1 U0 G2	8,096	B1 U0 G2
08	10,573	B1 U0 G2	10,794	B1 U0 G2
10	13,185	B1 U0 G2	13,461	B1 U0 G2
12	15,821	B2 U0 G2	16,153	B2 U0 G3
700mA				
04	6,311	B1 U0 G1	6,440	B1 U0 G1
06	9,359	B1 U0 G2	9,549	B1 U0 G2

* Initial delivered lumens at 25°C (77°F). Actual production yield may vary between -10 and +10% of initial delivered lumens


** For more information on the IES BUG (Backlight-Uplight-Glare) Rating visit: www.ies.org/PDF/Erratas/TM-15-11BugRatingsAddendum.pdf

Cree Edge™ LED Area Luminaire – Round


Photometry

All published luminaire photometric testing performed to IESNA LM-79-08 standards by a NVLAP accredited laboratory. To obtain an IES file specific to your project consult: <http://lighting.cree.com/products/outdoor/area/cree-edge-series-1>

2MP



CSA Test Report #: 6361
 ARE-EDG-2MP-**-06-E-UL-700-40K
 Initial Delivered Lumens: 9,912



ARE-EDR-2MP-**-10-E-UL-525-40K
 Mounting Height: 25' (7.6m) A.F.G.
 Initial Delivered Lumens: 15,458
 Initial FC at grade

Type II Medium Distribution w/Partial BLS				
LED Count (x10)	4000K		5700K	
	Initial Delivered Lumens*	BUG Ratings** Per TM-15-11	Initial Delivered Lumens*	BUG Ratings** Per TM-15-11
350mA				
04	4,418	B1 U0 G1	4,505	B1 U0 G1
06	6,551	B2 U0 G1	6,681	B2 U0 G1
08	8,735	B2 U0 G2	8,908	B2 U0 G2
10	10,892	B2 U0 G2	11,108	B2 U0 G2
12	13,071	B2 U0 G2	13,330	B2 U0 G2
525mA				
04	6,270	B1 U0 G1	6,401	B2 U0 G1
06	9,297	B2 U0 G2	9,492	B2 U0 G2
08	12,396	B2 U0 G2	12,656	B2 U0 G2
10	15,458	B2 U0 G3	15,782	B2 U0 G3
12	18,549	B3 U0 G3	18,938	B3 U0 G3
700mA				
04	7,400	B2 U0 G2	7,550	B2 U0 G2
06	10,973	B2 U0 G2	11,196	B2 U0 G2

* Initial delivered lumens at 25°C (77°F). Actual production yield may vary between -10 and +10% of initial delivered lumens


** For more information on the IES BUG (Backlight-Uplight-Glare) Rating visit: www.ies.org/PDF/Erratas/TM-15-11BugRatingsAddendum.pdf




Photometry

All published luminaire photometric testing performed to IESNA LM-79-08 standards by a NVLAP accredited laboratory. To obtain an IES file specific to your project consult: <http://lighting.cree.com/products/outdoor/area/cree-edge-series-1>

3M



RESTL Test Report #: PL09276-001A
 ARE-EDG-3M-**-06-E-UL-700-40K
 Initial Delivered Lumens: 11,333



ARE-EDR-3M-**-06-E-UL-700-40K
 Mounting Height: 25' (7.6m) A.F.G.
 Initial Delivered Lumens: 11,779
 Initial FC at grade

Type III Medium Distribution				
LED Count (x10)	4000K		5700K	
	Initial Delivered Lumens*	BUG Ratings** Per TM-15-11	Initial Delivered Lumens*	BUG Ratings** Per TM-15-11
350mA				
04	4,743	B1 U0 G1	4,837	B1 U0 G1
06	7,033	B2 U0 G2	7,172	B2 U0 G2
08	9,377	B2 U0 G2	9,563	B2 U0 G2
10	11,693	B3 U0 G3	11,925	B3 U0 G3
12	14,032	B3 U0 G3	14,310	B3 U0 G3
525mA				
04	6,731	B2 U0 G2	6,872	B2 U0 G2
06	9,981	B3 U0 G3	10,190	B3 U0 G3
08	13,307	B3 U0 G3	13,586	B3 U0 G3
10	16,594	B3 U0 G3	16,942	B3 U0 G3
12	19,913	B3 U0 G3	20,330	B3 U0 G3
700mA				
04	7,944	B2 U0 G2	8,105	B2 U0 G2
06	11,779	B3 U0 G3	12,019	B3 U0 G3


* Initial delivered lumens at 25°C (77°F). Actual production yield may vary between -10 and +10% of initial delivered lumens

** For more information on the IES BUG (Backlight-Uplight-Glare) Rating visit: www.ies.org/PDF/Erratas/TM-15-11BugRatingsAddendum.pdf


Photometry

All published luminaire photometric testing performed to IESNA LM-79-08 standards by a NVLAP accredited laboratory. To obtain an IES file specific to your project consult: <http://lighting.cree.com/products/outdoor/area/cree-edge-series-1>

3MB



CSA Test Report #: 6648
 ARE-EDG-3MB-**-06-E-UL-700
 Initial Delivered Lumens: 7,740



ARE-EDR-3MB-**-10-E-UL-525-40K
 Mounting Height: 25' (7.6m) A.F.G.
 Initial Delivered Lumens: 12,275
 Initial FC at grade

Type III Medium Distribution w/BLS				
LED Count (x10)	4000K		5700K	
	Initial Delivered Lumens*	BUG Ratings** Per TM-15-11	Initial Delivered Lumens*	BUG Ratings** Per TM-15-11
350mA				
04	3,508	B1 U0 G1	3,578	B1 U0 G1
06	5,202	B1 U0 G2	5,305	B1 U0 G2
08	6,936	B1 U0 G2	7,074	B1 U0 G2
10	8,650	B1 U0 G2	8,821	B1 U0 G2
12	10,380	B1 U0 G3	10,585	B1 U0 G3
525mA				
04	4,979	B1 U0 G2	5,083	B1 U0 G2
06	7,383	B1 U0 G2	7,538	B1 U0 G2
08	9,844	B1 U0 G2	10,050	B1 U0 G3
10	12,275	B1 U0 G3	12,532	B1 U0 G3
12	14,730	B2 U0 G3	15,039	B2 U0 G3
700mA				
04	5,876	B1 U0 G2	5,996	B1 U0 G2
06	8,714	B1 U0 G2	8,891	B1 U0 G2

* Initial delivered lumens at 25°C (77°F). Actual production yield may vary between -10 and +10% of initial delivered lumens

** For more information on the IES BUG (Backlight-Uplight-Glare) Rating visit: www.ies.org/PDF/Erratas/TM-15-11BugRatingsAddendum.pdf




Cree Edge™ LED Area Luminaire – Round


Photometry

All published luminaire photometric testing performed to IESNA LM-79-08 standards by a NVLAP accredited laboratory. To obtain an IES file specific to your project consult: <http://lighting.cree.com/products/outdoor/area/cree-edge-series-1>

3MP



CSA Test Report #: 6385
 ARE-EDG-3MP-**-06-E-UL-700-40K
 Initial Delivered Lumens: 9,619



ARE-EDR-3MP-**-10-E-UL-525-40K
 Mounting Height: 25' (7.6m) A.F.G.
 Initial Delivered Lumens: 14,548
 Initial FC at grade

Type III Medium Distribution w/Partial BLS				
LED Count (x10)	4000K		5700K	
	Initial Delivered Lumens*	BUG Ratings** Per TM-15-11	Initial Delivered Lumens*	BUG Ratings** Per TM-15-11
350mA				
04	4,158	B1 U0 G1	4,240	B1 U0 G1
06	6,166	B1 U0 G2	6,288	B1 U0 G2
08	8,221	B2 U0 G2	8,384	B2 U0 G2
10	10,252	B2 U0 G2	10,455	B2 U0 G3
12	12,302	B2 U0 G3	12,546	B2 U0 G3
525mA				
04	5,901	B1 U0 G2	6,024	B1 U0 G2
06	8,750	B2 U0 G2	8,933	B2 U0 G2
08	11,667	B2 U0 G3	11,911	B2 U0 G3
10	14,548	B3 U0 G3	14,853	B3 U0 G3
12	17,458	B3 U0 G3	17,824	B3 U0 G3
700mA				
04	6,964	B2 U0 G2	7,106	B2 U0 G2
06	10,327	B2 U0 G2	10,537	B2 U0 G3


* Initial delivered lumens at 25°C (77°F). Actual production yield may vary between -10 and +10% of initial delivered lumens

** For more information on the IES BUG (Backlight-Uplight-Glare) Rating visit: www.ies.org/PDF/Erratas/TM-15-11BugRatingsAddendum.pdf


Photometry

All published luminaire photometric testing performed to IESNA LM-79-08 standards by a NVLAP accredited laboratory. To obtain an IES file specific to your project consult: <http://lighting.cree.com/products/outdoor/area/cree-edge-series-1>

4M



CSA Test Report #: 6438
 ARE-EDG-4M-**-06-E-UL-700-40K
 Initial Delivered Lumens: 11,367



ARE-EDR-4M-**-10-E-UL-525-40K
 Mounting Height: 25' (7.6m) A.F.G.
 Initial Delivered Lumens: 17,504
 Initial FC at grade

Type IV Medium Distribution				
LED Count (x10)	4000K		5700K	
	Initial Delivered Lumens*	BUG Ratings** Per TM-15-11	Initial Delivered Lumens*	BUG Ratings** Per TM-15-11
350mA				
04	5,003	B2 U0 G1	5,102	B2 U0 G1
06	7,418	B2 U0 G2	7,565	B2 U0 G2
08	9,891	B2 U0 G2	10,087	B2 U0 G2
10	12,334	B3 U0 G3	12,578	B3 U0 G3
12	14,801	B3 U0 G3	15,094	B3 U0 G3
525mA				
04	7,099	B2 U0 G2	7,248	B2 U0 G2
06	10,527	B2 U0 G2	10,748	B2 U0 G2
08	14,037	B3 U0 G3	14,331	B3 U0 G3
10	17,504	B3 U0 G3	17,870	B3 U0 G3
12	21,004	B3 U0 G3	21,444	B3 U0 G3
700mA				
04	8,379	B2 U0 G2	8,549	B2 U0 G2
06	12,425	B3 U0 G3	12,678	B3 U0 G3

* Initial delivered lumens at 25°C (77°F). Actual production yield may vary between -10 and +10% of initial delivered lumens

** For more information on the IES BUG (Backlight-Uplight-Glare) Rating visit: www.ies.org/PDF/Erratas/TM-15-11BugRatingsAddendum.pdf




Cree Edge™ LED Area Luminaire – Round


Photometry

All published luminaire photometric testing performed to IESNA LM-79-08 standards by a NVLAP accredited laboratory. To obtain an IES file specific to your project consult: <http://lighting.cree.com/products/outdoor/area/cree-edge-series-1>

4MB



CSA Test Report #: 6449
 ARE-EDG-4MB-**-12-E-UL-525-40K
 Initial Delivered Lumens: 13,155



ARE-EDR-4MB-**-10-E-UL-525-40K
 Mounting Height: 25' (7.6m) A.F.G.
 Initial Delivered Lumens: 13,185
 Initial FC at grade

Type IV Medium Distribution w/BLS				
LED Count (x10)	4000K		5700K	
	Initial Delivered Lumens*	BUG Ratings** Per TM-15-11	Initial Delivered Lumens*	BUG Ratings** Per TM-15-11
350mA				
04	3,768	B1 U0 G1	3,843	B1 U0 G1
06	5,588	B1 U0 G1	5,698	B1 U0 G2
08	7,450	B1 U0 G2	7,598	B1 U0 G2
10	9,291	B1 U0 G2	9,475	B1 U0 G2
12	11,149	B1 U0 G2	11,370	B1 U0 G2
525mA				
04	5,348	B1 U0 G1	5,460	B1 U0 G1
06	7,930	B1 U0 G2	8,096	B1 U0 G2
08	10,573	B1 U0 G2	10,794	B1 U0 G2
10	13,185	B1 U0 G2	13,461	B1 U0 G2
12	15,821	B2 U0 G3	16,153	B2 U0 G3
700mA				
04	6,311	B1 U0 G2	6,440	B1 U0 G2
06	9,359	B1 U0 G2	9,549	B1 U0 G2


* Initial delivered lumens at 25°C (77°F). Actual production yield may vary between -10 and +10% of initial delivered lumens

** For more information on the IES BUG (Backlight-Uplight-Glare) Rating visit: www.ies.org/PDF/Erratas/TM-15-11BugRatingsAddendum.pdf


Photometry

All published luminaire photometric testing performed to IESNA LM-79-08 standards by a NVLAP accredited laboratory. To obtain an IES file specific to your project consult: <http://lighting.cree.com/products/outdoor/area/cree-edge-series-1>

4MP



CSA Test Report #: 6417
 ARE-EDG-4MP-**-06-E-UL-700-40K
 Initial Delivered Lumens: 9,989



ARE-EDR-4MP-**-10-E-UL-525-40K
 Mounting Height: 25' (7.6m) A.F.G.
 Initial Delivered Lumens: 15,458
 Initial FC at grade

Type IV Medium Distribution w/Partial BLS				
LED Count (x10)	4000K		5700K	
	Initial Delivered Lumens*	BUG Ratings** Per TM-15-11	Initial Delivered Lumens*	BUG Ratings** Per TM-15-11
350mA				
04	4,418	B1 U0 G1	4,505	B1 U0 G1
06	6,551	B2 U0 G1	6,681	B2 U0 G1
08	8,735	B2 U0 G2	8,908	B2 U0 G2
10	10,892	B2 U0 G2	11,108	B2 U0 G2
12	13,071	B2 U0 G2	13,330	B2 U0 G2
525mA				
04	6,270	B2 U0 G1	6,401	B2 U0 G1
06	9,297	B2 U0 G2	9,492	B2 U0 G2
08	12,396	B2 U0 G2	12,656	B2 U0 G2
10	15,458	B3 U0 G2	15,782	B3 U0 G2
12	18,549	B3 U0 G2	18,938	B3 U0 G3
700mA				
04	7,400	B2 U0 G2	7,550	B2 U0 G2
06	10,973	B2 U0 G2	11,196	B2 U0 G2

* Initial delivered lumens at 25°C (77°F). Actual production yield may vary between -10 and +10% of initial delivered lumens


** For more information on the IES BUG (Backlight-Uplight-Glare) Rating visit: www.ies.org/PDF/Erratas/TM-15-11BugRatingsAddendum.pdf. Valid with no tilt




Photometry

All published luminaire photometric testing performed to IESNA LM-79-08 standards by a NVLAP accredited laboratory. To obtain an IES file specific to your project consult: <http://lighting.cree.com/products/outdoor/area/cree-edge-series-1>

5M



RESTTest Report #: PL09285-001
 ARE-EDG-5M-**-06-E-UL-700-40K
 Initial Delivered Lumens: 13,136



ARE-EDR-5M-**-06-E-UL-700-40K
 Mounting Height: 25' (7.6m) A.F.G.
 Initial Delivered Lumens: 13,070
 Initial FC at grade

Type V Medium Distribution				
LED Count (x10)	4000K		5700K	
	Initial Delivered Lumens*	BUG Ratings** Per TM-15-11	Initial Delivered Lumens*	BUG Ratings** Per TM-15-11
350mA				
04	5,262	B3 U0 G1	5,367	B3 U0 G1
06	7,804	B3 U0 G2	7,958	B3 U0 G2
08	10,405	B4 U0 G2	10,611	B4 U0 G2
10	12,975	B4 U0 G2	13,232	B4 U0 G2
12	15,570	B4 U0 G3	15,878	B4 U0 G3
525mA				
04	7,468	B3 U0 G2	7,625	B3 U0 G2
06	11,074	B4 U0 G2	11,306	B4 U0 G2
08	14,766	B4 U0 G2	15,075	B4 U0 G3
10	18,413	B4 U0 G3	18,799	B4 U0 G3
12	22,096	B5 U0 G3	22,558	B5 U0 G3
700mA				
04	8,814	B3 U0 G2	8,993	B3 U0 G2
06	13,070	B4 U0 G2	13,336	B4 U0 G2


* Initial delivered lumens at 25°C (77°F). Actual production yield may vary between -10 and +10% of initial delivered lumens

** For more information on the IES BUG (Backlight-Uplight-Glare) Rating visit: www.ies.org/PDF/Erratas/TM-15-11BugRatingsAddendum.pdf. Valid with no tilt


Photometry

All published luminaire photometric testing performed to IESNA LM-79-08 standards by a NVLAP accredited laboratory. To obtain an IES file specific to your project consult: <http://lighting.cree.com/products/outdoor/area/cree-edge-series-1>

55



Restl Test Report #: PL09286-001A
 ARE-EDG-5S-**-06-E-UL-700-40K
 Initial Delivered Lumens: 14,123



ARE-EDR-5S-**-06-E-UL-700-40K
 Mounting Height: 25' (7.6m) A.F.G.
 Initial Delivered Lumens: 14,523
 Initial FC at grade

Type V Short Distribution				
LED Count (x10)	4000K		5700K	
	Initial Delivered Lumens*	BUG Ratings** Per TM-15-11	Initial Delivered Lumens*	BUG Ratings** Per TM-15-11
350mA				
04	5,847	B3 U0 G1	5,963	B3 U0 G1
06	8,671	B3 U0 G1	8,842	B3 U0 G1
08	11,561	B3 U0 G2	11,790	B3 U0 G2
10	14,416	B4 U0 G2	14,702	B4 U0 G2
12	17,300	B4 U0 G2	17,642	B4 U0 G2
525mA				
04	8,298	B3 U0 G1	8,472	B3 U0 G1
06	12,305	B3 U0 G2	12,563	B3 U0 G2
08	16,406	B4 U0 G2	16,750	B4 U0 G2
10	20,459	B4 U0 G2	20,887	B4 U0 G2
12	24,551	B4 U0 G2	25,065	B4 U0 G2
700mA				
04	9,793	B3 U0 G1	9,993	B3 U0 G2
06	14,523	B4 U0 G2	14,818	B4 U0 G2

* Initial delivered lumens at 25°C (77°F). Actual production yield may vary between -10 and +10% of initial delivered lumens


** For more information on the IES BUG (Backlight-Uplight-Glare) Rating visit: www.ies.org/PDF/Erratas/TM-15-11BugRatingsAddendum.pdf. Valid with no tilt



Luminaire EPA


Post Top Mount – ARE-EDR-R3/R4/R5		
LED Count (x10)	Single R3	Single R4/R5
04	1.81	1.67
06	1.81	1.67
08	1.81	1.67
10	1.81	1.67
12	1.81	1.67

R4 Mount



LED Count (x10)	Weight
04	36.2 lbs. (16.4kg)
06	37.6 lbs. (17.0kg)
08	39.3 lbs. (17.8kg)
10	43.0 lbs. (19.5kg)
12	44.8 lbs. (20.3kg)

R5 Mount



LED Count (x10)	Weight
04	33.3 lbs. (15.1kg)
06	34.6 lbs. (15.7kg)
08	36.4 lbs. (16.5kg)
10	40.1 lbs. (18.2kg)
12	41.9 lbs. (19.0kg)

Cree Edge™ Series

LED Security Wall Pack Luminaire

W1

Product Description

The Cree Edge™ wall mount luminaire has a slim, low profile design. The luminaire end caps are made from rugged die cast aluminum with integral, weathertight LED driver compartments and high performance aluminum heat sinks specifically designed for LED applications. Housing is rugged aluminum. Includes a lightweight mounting box for installation over standard and mud ring single gang J-Boxes. Secures to wall with four 3/16" (5mm) screws (by others). Conduit entry from top, bottom, sides and rear. Allows mounting for uplight or downlight. Designed and approved for easy through-wiring. Includes leaf/debris guard.

Applications: General area and security lighting

Performance Summary

Patented NanoOptic® Product Technology

Made in the U.S.A. of U.S. and imported parts

CRI: Minimum 70 CRI


CCT: 4000K (+/- 300K), 5700K (+/- 500K) standard

Limited Warranty*: 10 years on luminaire/10 years on Colorfast DeltaGuard® finish

*See <http://lighting.cree.com/warranty> for warranty terms

Accessories

Field-Installed	
Bird Spikes XA-BRDSPK	Hand-Held Remote XA-SENSREM - For successful implementation of the programmable multi-level option, a minimum of one hand-held remote is required



LED Count (x10)	Dim. "A"	Weight
02	9.9" (251mm)	20 lbs. (9.1kg)
04	11.9" (303mm)	22 lbs. (10.0kg)
06	13.9" (353mm)	25 lbs. (11.3kg)
08	15.9" (404mm)	27 lbs. (12.2kg)
10	17.9" (455mm)	31 lbs. (14.1kg)
12	19.9" (505mm)	32 lbs. (14.5kg)

Ordering Information

Example: SEC-EDG-2M-WM-06-E-UL-SV-700

SEC-EDG	Optic	WM	LED Count (x10)	E	Voltage	Color Options	Drive Current	Options
SEC-EDG	2M Type II Medium 2MB Type II Medium w/BLS 2S Type II Short 2SB Type II Short w/BLS 3M Type III Medium 3MB Type III Medium w/BLS 4M Type IV Medium 4MB Type IV Medium w/BLS	WM Wall Mount	02 04 06 08 10 12	E	UL Universal 120-277V UH Universal 347-480V 34 347V	BK Black BZ Bronze SV Silver WH White	350 350mA 525 525mA 700 700mA -Available with 20-80 LEDs -Available with 20-60 LEDs	DIM 0-10V Dimming - Control by others - Refer to Dimming spec sheet for details - Can't exceed specified drive current F Fuse - Refer to ML spec sheet for availability with ML options - Available with UL voltage only - Available for U.S. applications only - When code dictates fusing, use time delay fuse ML Multi-Level - Refer to ML spec sheet for details - Intended for downlight applications with 0° tilt P Photocell - Refer to ML spec sheet for availability with ML options - Must specify UL or 34 voltage PML Programmable Multi-Level - Refer to PML spec sheet for details - Intended for downlight applications with 0° tilt 40K 4000K Color Temperature - Minimum 70 CRI - Color temperature per luminaire



US: lighting.cree.com

T (800) 236-6800 F (262) 504-5415

Rev. Date: V3 09/06/2017

Canada: www.cree.com/canada



T (800) 473-1234 F (800) 890-7507

Product Specifications

CONSTRUCTION & MATERIALS

- Slim, low profile design
- Luminaire sides are rugged die cast aluminum with integral, weathertight LED driver compartment and high performance aluminum heat sinks specifically designed for LED applications
- Housing is rugged aluminum
- Furnished with low copper, light weight mounting box designed for installation over standard and mud ring single gang J-Boxes
- Luminaire can also be direct mounted to a wall and surface wired
- Secures to wall with four 3/16" (5mm) screws (by others)
- Conduit entry from top, bottom, sides, and rear
- Allows mounting for uplight or downlight
- Designed and approved for easy through-wiring
- Includes leaf/debris guard
- Exclusive Colorfast DeltaGuard® finish features an E-Coat epoxy primer with an ultradurable powder topcoat, providing excellent resistance to corrosion, ultraviolet degradation and abrasion. Black, bronze, silver and white are available
- **Weight:** See Dimensions and Weight Chart on page 1

ELECTRICAL SYSTEM

- **Input Voltage:** 120–277V or 347–480V, 50/60Hz, Class 1 drivers
- **Power Factor:** > 0.9 at full load
- **Total Harmonic Distortion:** < 20% at full load
- Integral weathertight J-Box with leads (wire nuts) for easy power hook up
- Integral 10kV surge suppression protection standard
- When code dictates fusing, a slow blow fuse or type C/D breaker should be used to address inrush current
- **Maximum 10V Source Current:** 20 LED (350mA): 10mA; 20LED (525 & 700 mA) and 40-120 LED: 0.15mA

REGULATORY & VOLUNTARY QUALIFICATIONS

- cULus Listed
- Suitable for wet locations
- Meets FCC Part 15, Subpart B, Class A standards for conducted and radiated emissions
- Enclosure rated IP66 per IEC 60529 when ordered without P, PML or ML options
- 10kV surge suppression protection tested in accordance with IEEE/ANSI C62.41.2
- Luminaire and finish endurance tested to withstand 5,000 hours of elevated ambient salt fog conditions as defined in ASTM Standard B 117
- DLC qualified with select SKUs. Refer to <https://www.designlights.org/search/> for most current information
- Meets Buy American requirements within ARRA

Electrical Data*							
LED Count (x10)	System Watts 120-480V	Total Current (A)					
		120V	208V	240V	277V	347V	480V
350mA							
02	25	0.21	0.13	0.11	0.10	0.08	0.07
04	46	0.36	0.23	0.21	0.20	0.15	0.12
06	66	0.52	0.31	0.28	0.26	0.20	0.15
08	90	0.75	0.44	0.38	0.34	0.26	0.20
10	110	0.92	0.53	0.47	0.41	0.32	0.24
12	130	1.10	0.63	0.55	0.48	0.38	0.28
525mA							
02	37	0.30	0.19	0.17	0.16	0.12	0.10
04	70	0.58	0.34	0.31	0.28	0.21	0.16
06	101	0.84	0.49	0.43	0.38	0.30	0.22
08	133	1.13	0.66	0.58	0.51	0.39	0.28
700mA							
02	50	0.41	0.25	0.22	0.20	0.15	0.12
04	93	0.78	0.46	0.40	0.36	0.27	0.20
06	134	1.14	0.65	0.57	0.50	0.39	0.29

* Electrical data at 25°C (77°F). Actual wattage may differ by +/- 10% when operating between 120-480V +/- 10%

Recommended Cree Edge™ Series Lumen Maintenance Factors (LMF) ¹					
Ambient	Initial LMF	25K hr Projected ² LMF	50K hr Projected ² LMF	75K hr Calculated ³ LMF	100K hr Calculated ³ LMF
5°C (41°F)	1.04	1.01	0.99	0.98	0.96
10°C (50°F)	1.03	1.00	0.98	0.97	0.95
15°C (59°F)	1.02	0.99	0.97	0.96	0.94
20°C (68°F)	1.01	0.98	0.96	0.95	0.93
25°C (77°F)	1.00	0.97	0.95	0.94	0.92

¹ Lumen maintenance values at 25°C are calculated per TM-21 based on LM-80 data and in-situ luminaire testing

² In accordance with IESNA TM-21-11, Projected Values represent interpolated value based on time durations that are within six times


(6X) the IESNA LM-80-08 total test duration (in hours) for the device under testing ((DUT) i.e. the packaged LED chip)

³ In accordance with IESNA TM-21-11, Calculated Values represent time durations that exceed six times (6X) the IESNA LM-80-08 total test duration (in hours) for the device under testing ((DUT) i.e. the packaged LED chip)


Photometry

All published luminaire photometric testing performed to IESNA LM-79-08 standards by a NVLAP accredited laboratory. To obtain an IES file specific to your project consult: <http://lighting.cree.com/products/outdoor/wall-mount/cree-edge-series-5>

2M



ITL Test Report #: 79174
SEC-EDG-2M-**-06-E-UL-700-40K
Initial Delivered Lumens: 11,128




SEC-EDG-2M-**-08-E-UL-525-40K
Mounting Height: 10' (3.0m) A.F.G.
Initial Delivered Lumens: 11,835
Initial FC at grade


Type II Medium Distribution				
LED Count (x10)	4000K		5700K	
	Initial Delivered Lumens*	BUG Ratings** Per TM-15-11	Initial Delivered Lumens*	BUG Ratings** Per TM-15-11
350mA				
02	2,138	B1 U0 G1	2,220	B1 U0 G1
04	4,276	B1 U0 G1	4,440	B1 U0 G1
06	6,340	B2 U0 G2	6,584	B2 U0 G2
08	8,454	B2 U0 G2	8,779	B2 U0 G2
10	10,542	B3 U0 G3	10,947	B3 U0 G3
12	12,650	B3 U0 G3	13,137	B3 U0 G3
525mA				
02	2,993	B1 U0 G1	3,108	B1 U0 G1
04	5,986	B2 U0 G2	6,216	B2 U0 G2
06	8,876	B2 U0 G2	9,218	B2 U0 G2
08	11,835	B3 U0 G3	12,290	B3 U0 G3
700mA				
02	3,656	B1 U0 G1	3,796	B1 U0 G1
04	7,311	B2 U0 G2	7,593	B2 U0 G2
06	10,842	B3 U0 G3	11,259	B3 U0 G3

* Initial delivered lumens at 25°C (77°F). Actual production yield may vary between -10 and +10% of initial delivered lumens
 ** For more information on the IES BUG (Backlight-Uplight-Glare) Rating visit: <https://www.ies.org/wp-content/uploads/2017/03/TM-15-11BUGRatingsAddendum.pdf>

2MB



CSA Test Report #: 6447
ARE-EDG-2MB-**-06-E-UL-700-40K
Initial Delivered Lumens: 7,953



SEC-EDG-2MB-**-08-E-UL-525-40K
Mounting Height: 10' (3.0m) A.F.G.
Initial Delivered Lumens: 8,915
Initial FC at grade

Type II Medium Distribution w/BLS				
LED Count (x10)	4000K		5700K	
	Initial Delivered Lumens*	BUG Ratings** Per TM-15-11	Initial Delivered Lumens*	BUG Ratings** Per TM-15-11
350mA				
02	1,610	B0 U0 G1	1,672	B0 U0 G1
04	3,221	B0 U0 G1	3,345	B0 U0 G1
06	4,776	B1 U0 G1	4,959	B1 U0 G1
08	6,368	B1 U0 G1	6,613	B1 U0 G2
10	7,941	B1 U0 G2	8,246	B1 U0 G2
12	9,529	B1 U0 G2	9,895	B1 U0 G2
525mA				
02	2,254	B0 U0 G1	2,341	B0 U0 G1
04	4,509	B1 U0 G1	4,682	B1 U0 G1
06	6,686	B1 U0 G2	6,943	B1 U0 G2
08	8,915	B1 U0 G2	9,258	B1 U0 G2
700mA				
02	2,754	B0 U0 G1	2,860	B0 U0 G1
04	5,507	B1 U0 G1	5,719	B1 U0 G1
06	8,167	B1 U0 G2	8,481	B1 U0 G2


* Initial delivered lumens at 25°C (77°F). Actual production yield may vary between -10 and +10% of initial delivered lumens
 ** For more information on the IES BUG (Backlight-Uplight-Glare) Rating visit: <https://www.ies.org/wp-content/uploads/2017/03/TM-15-11BUGRatingsAddendum.pdf>




Photometry

All published luminaire photometric testing performed to IESNA LM-79-08 standards by a NVLAP accredited laboratory. To obtain an IES file specific to your project consult: <http://lighting.cree.com/products/outdoor/wall-mount/cree-edge-series-5>

25



ITL Test Report #: 79175
SEC-EDG-2S-**-06-E-UL-700-40K
Initial Delivered Lumens: 11,704




SEC-EDG-2S-**-08-E-UL-525-40K
Mounting Height: 10' [3.0m] A.F.G.
Initial Delivered Lumens: 12,604
Initial FC at grade

Type II Short Distribution				
LED Count (x10)	4000K		5700K	
	Initial Delivered Lumens*	BUG Ratings** Per TM-15-11	Initial Delivered Lumens*	BUG Ratings** Per TM-15-11
350mA				
02	2,277	B1 U0 G1	2,364	B1 U0 G1
04	4,553	B1 U0 G1	4,728	B1 U0 G1
06	6,752	B2 U0 G2	7,012	B2 U0 G2
08	9,003	B2 U0 G2	9,349	B2 U0 G2
10	11,226	B3 U0 G3	11,658	B3 U0 G3
12	13,472	B3 U0 G3	13,990	B3 U0 G3
525mA				
02	3,187	B1 U0 G1	3,310	B1 U0 G1
04	6,375	B2 U0 G2	6,620	B2 U0 G2
06	9,453	B2 U0 G2	9,816	B3 U0 G3
08	12,604	B3 U0 G3	13,088	B3 U0 G3
700mA				
02	3,893	B1 U0 G1	4,043	B1 U0 G1
04	7,786	B2 U0 G2	8,086	B2 U0 G2
06	11,546	B3 U0 G3	11,990	B3 U0 G3


* Initial delivered lumens at 25°C (77°F). Actual production yield may vary between -10 and +10% of initial delivered lumens

** For more information on the IES BUG (Backlight-Uplight-Glare) Rating visit: <https://www.ies.org/wp-content/uploads/2017/03/TM-15-11BUGRatingsAddendum.pdf>

25B



CSA Test Report #: 6454
ARE-EDG-2SB-**-06-E-UL-700-40K
Initial Delivered Lumens: 9,202



SEC-EDG-2SB-**-08-E-UL-525-40K
Mounting Height: 10' [3.0m] A.F.G.
Initial Delivered Lumens: 9,683
Initial FC at grade

Type II Short Distribution w/BLS				
LED Count (x10)	4000K		5700K	
	Initial Delivered Lumens*	BUG Ratings** Per TM-15-11	Initial Delivered Lumens*	BUG Ratings** Per TM-15-11
350mA				
02	1,749	B0 U0 G1	1,816	B0 U0 G1
04	3,498	B1 U0 G1	3,633	B1 U0 G1
06	5,188	B1 U0 G1	5,387	B1 U0 G1
08	6,917	B1 U0 G1	7,183	B1 U0 G1
10	8,625	B2 U0 G1	8,957	B2 U0 G1
12	10,350	B2 U0 G2	10,748	B2 U0 G2
525mA				
02	2,449	B1 U0 G1	2,543	B1 U0 G1
04	4,898	B1 U0 G1	5,086	B1 U0 G1
06	7,263	B1 U0 G1	7,542	B1 U0 G1
08	9,683	B2 U0 G2	10,056	B2 U0 G2
700mA				
02	2,991	B1 U0 G1	3,106	B1 U0 G1
04	5,982	B1 U0 G1	6,212	B1 U0 G1
06	8,871	B2 U0 G1	9,212	B2 U0 G2

* Initial delivered lumens at 25°C (77°F). Actual production yield may vary between -10 and +10% of initial delivered lumens


** For more information on the IES BUG (Backlight-Uplight-Glare) Rating visit: <https://www.ies.org/wp-content/uploads/2017/03/TM-15-11BUGRatingsAddendum.pdf>




Photometry

All published luminaire photometric testing performed to IESNA LM-79-08 standards by a NVLAP accredited laboratory. To obtain an IES file specific to your project consult: <http://lighting.cree.com/products/outdoor/wall-mount/cree-edge-series-5>

3M




ITLTest Report #: 79173
SEC-EDG-3M-**-06-E-UL-700-40K
Initial Delivered Lumens: 10,343




SEC-EDG-3M-**-08-E-UL-525-40K
Mounting Height: 10' (3.0m) A.F.G.
Initial Delivered Lumens: 11,220
Initial FC at grade

3MB



CSA Test Report #: 6448
ARE-EDG-3MB-**-06-E-UL-700
Initial Delivered Lumens: 7,740



SEC-EDG-3MB-**-08-E-UL-525-40K
Mounting Height: 10' (3.0m) A.F.G.
Initial Delivered Lumens: 8,300
Initial FC at grade

Type III Medium Distribution				
LED Count (x10)	4000K		5700K	
	Initial Delivered Lumens*	BUG Ratings** Per TM-15-11	Initial Delivered Lumens*	BUG Ratings** Per TM-15-11
350mA				
02	2,027	B1 U0 G1	2,105	B1 U0 G1
04	4,054	B1 U0 G1	4,209	B1 U0 G1
06	6,011	B2 U0 G2	6,242	B2 U0 G2
08	8,015	B2 U0 G2	8,323	B2 U0 G2
10	9,994	B3 U0 G3	10,379	B3 U0 G3
12	11,993	B3 U0 G3	12,454	B3 U0 G3
525mA				
02	2,837	B1 U0 G1	2,947	B1 U0 G1
04	5,675	B2 U0 G2	5,893	B2 U0 G2
06	8,415	B2 U0 G2	8,739	B2 U0 G2
08	11,220	B3 U0 G3	11,652	B3 U0 G3
700mA				
02	3,466	B1 U0 G1	3,599	B1 U0 G1
04	6,932	B2 U0 G2	7,198	B2 U0 G2
06	10,279	B3 U0 G3	10,674	B3 U0 G3

* Initial delivered lumens at 25°C (77°F). Actual production yield may vary between -10 and +10% of initial delivered lumens

** For more information on the IES BUG (Backlight-Uplight-Glare) Rating visit: <https://www.ies.org/wp-content/uploads/2017/03/TM-15-11BUGRatingsAddendum.pdf>

Type III Medium Distribution w/BLS				
LED Count (x10)	4000K		5700K	
	Initial Delivered Lumens*	BUG Ratings** Per TM-15-11	Initial Delivered Lumens*	BUG Ratings** Per TM-15-11
350mA				
02	1,499	B1 U0 G1	1,557	B1 U0 G1
04	2,999	B1 U0 G1	3,114	B1 U0 G1
06	4,446	B1 U0 G1	4,617	B1 U0 G1
08	5,929	B1 U0 G2	6,157	B1 U0 G2
10	7,393	B1 U0 G2	7,677	B1 U0 G2
12	8,872	B1 U0 G2	9,213	B1 U0 G2
525mA				
02	2,099	B1 U0 G1	2,180	B1 U0 G1
04	4,198	B1 U0 G1	4,359	B1 U0 G1
06	6,225	B1 U0 G2	6,464	B1 U0 G2
08	8,300	B1 U0 G2	8,619	B1 U0 G2
700mA				
02	2,564	B1 U0 G1	2,662	B1 U0 G1
04	5,127	B1 U0 G2	5,325	B1 U0 G2
06	7,603	B1 U0 G2	7,896	B1 U0 G2

* Initial delivered lumens at 25°C (77°F). Actual production yield may vary between -10 and +10% of initial delivered lumens


** For more information on the IES BUG (Backlight-Uplight-Glare) Rating visit: <https://www.ies.org/wp-content/uploads/2017/03/TM-15-11BUGRatingsAddendum.pdf>




Photometry

All published luminaire photometric testing performed to IESNA LM-79-08 standards by a NVLAP accredited laboratory. To obtain an IES file specific to your project consult: <http://lighting.cree.com/products/outdoor/wall-mount/cree-edge-series-5>

4M



ITL Test Report #: 78793
SEC-EDG-4M-**-08-E-UL-525-40K
Initial Delivered Lumens: 11,607




SEC-EDG-4M-**-08-E-UL-525-40K
Mounting Height: 10' (3.0m) A.F.G.
Initial Delivered Lumens: 11,835
Initial FC at grade


Type IV Medium Distribution				
LED Count (x10)	4000K		5700K	
	Initial Delivered Lumens*	BUG Ratings** Per TM-15-11	Initial Delivered Lumens*	BUG Ratings** Per TM-15-11
350mA				
02	2,138	B1 U0 G1	2,220	B1 U0 G1
04	4,276	B1 U0 G1	4,440	B1 U0 G1
06	6,340	B2 U0 G2	6,584	B2 U0 G2
08	8,454	B2 U0 G2	8,779	B2 U0 G2
10	10,542	B2 U0 G2	10,947	B3 U0 G3
12	12,650	B3 U0 G3	13,137	B3 U0 G3
525mA				
02	2,993	B1 U0 G1	3,108	B1 U0 G1
04	5,986	B2 U0 G2	6,216	B2 U0 G2
06	8,876	B2 U0 G2	9,218	B2 U0 G2
08	11,835	B3 U0 G3	12,290	B3 U0 G3
700mA				
02	3,656	B1 U0 G1	3,796	B1 U0 G1
04	7,311	B2 U0 G2	7,593	B2 U0 G2
06	10,842	B3 U0 G3	11,259	B3 U0 G3

* Initial delivered lumens at 25°C (77°F). Actual production yield may vary between -10 and +10% of initial delivered lumens
 ** For more information on the IES BUG (Backlight-Uplight-Glare) Rating visit: <https://www.ies.org/wp-content/uploads/2017/03/TM-15-11BUGRatingsAddendum.pdf>

4MB



CSA Test Report #: 6449
ARE-EDG-4MB-**-12-E-UL-525-40K
Initial Delivered Lumens: 13,155



SEC-EDG-4MB-**-08-E-UL-525-40K
Mounting Height: 10' (3.0m) A.F.G.
Initial Delivered Lumens: 8,915
Initial FC at grade

Type IV Medium Distribution w/BLS				
LED Count (x10)	4000K		5700K	
	Initial Delivered Lumens*	BUG Ratings** Per TM-15-11	Initial Delivered Lumens*	BUG Ratings** Per TM-15-11
350mA				
02	1,610	B0 U0 G1	1,672	B0 U0 G1
04	3,221	B1 U0 G1	3,345	B1 U0 G1
06	4,776	B1 U0 G1	4,959	B1 U0 G1
08	6,368	B1 U0 G2	6,613	B1 U0 G2
10	7,941	B1 U0 G2	8,246	B1 U0 G2
12	9,529	B1 U0 G2	9,895	B1 U0 G2
525mA				
02	2,254	B0 U0 G1	2,341	B0 U0 G1
04	4,509	B1 U0 G1	4,682	B1 U0 G1
06	6,686	B1 U0 G2	6,943	B1 U0 G2
08	8,915	B1 U0 G2	9,258	B1 U0 G2
700mA				
02	2,754	B0 U0 G1	2,860	B0 U0 G1
04	5,507	B1 U0 G1	5,719	B1 U0 G2
06	8,167	B1 U0 G2	8,481	B1 U0 G2

* Initial delivered lumens at 25°C (77°F). Actual production yield may vary between -10 and +10% of initial delivered lumens
 ** For more information on the IES BUG (Backlight-Uplight-Glare) Rating visit: <https://www.ies.org/wp-content/uploads/2017/03/TM-15-11BUGRatingsAddendum.pdf>





Washer Quattro AC XB RGBW

The Washer Quattro AC XB RGBW is an AC line powered, high brightness luminaire. The luminaire is controllable via DMX512 with auto-addressing for easy configuration. The system is connected using a daisy chain topology, allowing easy installation to form long run lengths. Remote Device Management (RDM) circuits are built into each luminaire that enables extensive control and monitoring of the entire lighting installation.



Product Specifications

Light Source	4-in-1 LED cluster x 18
Color Range	RGBW (White CCT 4000K)
Beam Angle	13°, 30°, 40°, 60°
Luminous Flux	3212 lm (13°)
Efficacy	44 lm/W
Lumen Maintenance	L70 @25°C - 80,000hrs
Cover Lens	Tempered glass cover
Housing	Aluminium
Adjustment Options	360° horizontal, 220° vertical
Size (W x H x D)	291mm x 291mm x 218mm 11.5" x 11.5" x 8.6"
Weight	8.3kg / 18.3lbs
Regulatory Listing & Safety Approval	CE, cETLus
Operating Temperature	-30°C to +50°C / -22°F to +122°F (-20°C / -4°F starting)
Storage Temperature	-40°C to +70°C / -40°F to +158°F
Environment	Outdoor (IP66)
Humidity	85%, non-condensing

Electrical Specifications

Input Voltage ¹	100-277V AC 50/60Hz
Power Consumption	85W
Power Factor	≥ 0.9

System Specifications

Power	AC line
Control	DMX512 with auto-addressing, Remote Device Management (RDM)
Power Supply	Built-in

1. Auto-switching. Single phase (line, neutral, and ground).

LED CHARACTERISTICS Because LEDs are semiconductor devices, their performances are subject to inherent variability commonly found in semiconductor industry. To improve consistency in performance across the same product, LED manufacturers "sort" LEDs into bins according to different preset parameters, such as forward driving voltage, illumination, etc. Whereas binning is a sorting function, it is not a correction process. Inherent variability in the manufacturing process results always in different binning distributions according to different production lots. Traxon uses automatically binned LEDs on its products, thereby minimizing output variations within the model range.

As with all electronic devices, LED output degrades over time – a term called lumen depreciation. This also explains why it is nearly impossible to expect photometric performances of two LED products with different service life spans to be the same. The rate of LED degrade is a complicate function of many factors such as operating efficiency, duration of continuous operation, and more significantly, environmental conditions (ambient temperature for example). If allowed working under optimal operating temperature range and with good ventilation, LED devices enjoy long service lives over conventional light sources. When using/installing LED devices, care should be taken to ensure that the devices will operate within the operating conditions specified in respective product literature.

Lumen measurement complies with LM-79-08 standard.
 Lumen maintenance is calculated based on LM-80 compliant measurement.


Washer Quattro AC XB RGBW

Photometrics

Source Specifications

LED Source	4-in-1 LED clusters
Beam Angle	13°

Candela Distribution



Light Output

Color	Luminous Flux (lm)	Candela Distribution @100%	Efficacy (lm/W)
White (full on)	3212.32	35479.21	43.50
White (RGB off)	1791.46	20068.63	58.22
RGB	1502.16	16221.28	30.59
Red	369.01	3871.815	29.47
Green	1066.45	11719.53	37.33
Blue	92.98	989.538	5.25

Illuminance at a Distance

	Center Beam LUX	Beam Width	
		V	H
2m	8869.80	0.5m	0.5m
4m	2217.45	0.9m	0.9m
6m	985.53	1.4m	1.4m
8m	554.36	1.9m	1.9m
10m	354.79	2.4m	2.3m
12m	246.38	2.8m	2.8m

● Vert.Spread: 13.5°

● Horiz.Spread: 13.3°


For fc divide by 10.7

For feet multiply by 3.28

Source Specifications

LED Source	4-in-1 LED clusters
Beam Angle	30°

Candela Distribution



Light Output

Color	Luminous Flux (lm)	Candela Distribution @100%	Efficacy (lm/W)
White (full on)	2931.38	8112.26	39.7
White (RGB off)	1633.76	4543.98	53.1
RGB	1354.69	3723.67	27.58
Red	346.23	947.72	27.65
Green	970.62	2662.60	33.97
Blue	84.59	222.96	4.78

Illuminance at a Distance

	Center Beam LUX	Beam Width	
		V	H
2m	2028.07	1.1m	1.0m
4m	507.02	2.2m	2.1m
6m	225.34	3.3m	3.1m
8m	126.75	4.4m	4.2m
10m	81.12	5.5m	5.2m
12m	56.34	6.6m	6.2m


- Vert. Spread: 30.6°
 - Horiz. Spread: 29.2°
- For fc divide by 10.7

For feet multiply by 3.28

Source Specifications

LED Source	4-in-1 LED clusters
Beam Angle	40°


Candela Distribution



Light Output

Color	Luminous Flux (lm)	Candela Distribution @100%	Efficacy (lm/W)
White (full on)	2895.92	5488.632	39.22
White (RGB off)	1610.9	3217.009	52.35
RGB	1351.95	2660.115	27.53
Red	337.75	670.243	26.98
Green	960.79	1885.462	33.63
Blue	83.49	156.96	4.71

Illuminance at a Distance



● Vert.Spread: 37.9°

● Horiz.Spread: 36.3°


For feet multiply by 3.28

For fc divide by 10.7

Source Specifications

LED Source	4-in-1 LED clusters
Beam Angle	60°


Candela Distribution



Light Output

Color	Luminous Flux (lm)	Candela Distribution @100%	Efficacy (lm/W)
White (full on)	2845.25	2788.23	38.53
White (RGB off)	1592.87	1582.855	51.77
RGB	1332.38	1310.367	27.13
Red	332.48	330.717	26.56
Green	947.08	929.712	33.15
Blue	82.51	78.437	4.66

Illuminance at a Distance




● Vert. Spread: 57.2°

● Horiz. Spread: 55.4°

For feet multiply by 3.28

For fc divide by 10.7




www.traxontechnologies.com

©2016 TRAXON TECHNOLOGIES - AN OSRAM BUSINESS. ALL RIGHTS RESERVED. TRAXON™, TX CONNECT®, ARE TRADEMARKS OF TRAXON TECHNOLOGIES. U.S. PATENTS, E.U. PATENTS, JAPAN PATENTS, OTHER PATENTS PENDING. SPECIFICATIONS ARE SUBJECT TO CHANGE WITHOUT NOTICE.


Washer Quattro AC XB RGBW


Mounting

Mounting without base



Mounting with base







Washer Quattro AC XB RGBW

Ordering

Model Number

XB	.	W5	.	9	.	3	.	1	.	N	.	1	.	0	.	0
				Ingress Protection		Color		Beam Angle		Cover Lens						
				3: IP66		1: RGBW		1: 13°		1: Clear						
								3: 30°								
								6: 40°								
								8: 60°								

Fixtures

Model No.	Description	Item Code
XB.W5.9311100	Washer Quattro AC XB4.18 RGBW 13°	AB486980055
XB.W5.9313100	Washer Quattro AC XB4.18 RGBW 30°	AB487130055
XB.W5.9316100	Washer Quattro AC XB4.18 RGBW 40°	AB487100055
XB.W5.9318100	Washer Quattro AC XB4.18 RGBW 60°	AB487080055

Accessories


Model No.	Description	Item Code
XB.AC.4000000	Quattro AC XB Data Injector (ETL Lighting / CE IT)	AB389160055
XB.AC.4000100	Quattro AC XB Data Injector (CE Lighting)	AB444880055
XB.AC.2302000	5-pin Field Installable AC Male Connector IP66	AA438580235
XB.AC.2303000	5-pin Field Installable AC Female Connector IP66	AA438570235
XB.AC.4006000	3-pin Field Installable AC Female Connector IP66	AB389040035
XE.ID.0204000	AC XB Interconnection Cable, 5-wire, CE (2m)	AB389130055
XE.ID.0204001	AC XB Interconnection Cable, 5-wire, UL (6.5ft)	AB389120055
XE.ID.0074000	AC XB Interconnection Cable, 5-wire, CE (0.7m)	AB389100055
XE.ID.0074001	AC XB Interconnection Cable, 5-wire, UL (2.33ft)	AB389070055
XE.IF.0104000	AC XB Power Cable, 3-wire, CE (1m)	AB389060055
XE.IF.0104001	AC XB Power Cable, 3-wire, UL (3.25ft)	AB389050055
DE.AC.0100000	RJ45 Male Connector Housing IP67	AA556100155
XB.AC.2304000	5-pin Connector Socket End Cap IP66	AA508870335



AN OSRAM BUSINESS

©2016 TRAXON TECHNOLOGIES - AN OSRAM BUSINESS. ALL RIGHTS RESERVED. TRAXON™, TX CONNECT®, ARE TRADEMARKS OF TRAXON TECHNOLOGIES. U.S. PATENTS, E.U. PATENTS, JAPAN PATENTS, OTHER PATENTS PENDING. SPECIFICATIONS ARE SUBJECT TO CHANGE WITHOUT NOTICE.

DRAWN BY: Author 12/20/2017 1:15:48 PM



NOT FOR CONSTRUCTION

Date: 12/18/17
 Job No: 170143-01
 Sheet No:

Madison College
Goodman South Campus
 801 W Batiger Road, Madison, Wisconsin 53713



MADISON
 AREA TECHNICAL
COLLEGE

pro

PLUNKETT RAYSICH
 ARCHITECTS, LLP

intelligent designs. inspired results. | www.prarch.com

414.359.3060
 608.240.9900
 941.348.3618

LOWER LEVEL PLAN



TRUE NORTH PLAN NORTH
SECOND FLOOR PLAN
 1/16" = 1'-0"
 0 4 8 16 32
 SCALE: 1/16" = 1'-0"

NOT FOR CONSTRUCTION

Date: 12/18/17
 Job No: 170143-01
 Sheet No:

Madison College
Goodman South Campus
 801 W Batiger Road, Madison, Wisconsin 53713



MADISON
 AREA TECHNICAL
COLLEGE

pro

PLUNKETT RAYSICH
 ARCHITECTS, LLP

209 south water street milwaukee, wisconsin 53204
 2310 crossroads drive, suite 2000 madison, wisconsin 53718
 205 north orange avenue suite 202 sarasota, florida 34236

414.359.3060
 608.240.9900
 941.348.3618

2nd

SECOND FLOOR PLAN

intelligent designs. inspired results. | www.prarch.com