




BRIEF OVERVIEW OF WATERSHED STUDY PROGRAM



- ▶ WHY IS THE CITY CONDUCTING STUDIES?
 - ▶ SCOPE OF STUDIES
 - ▶ OTHER INITIATIVES
 - ▶ USING RESULTS
 - ▶ MORE INFORMATION
- 

WHY ARE WE DOING THE STUDIES?


- ▶ 2018 FLOODING HAD SIGNIFICANT IMPACTS
- ▶ BUILDING RESILIENCE IN OUR SYSTEM
- ▶ UNDERSTANDING THE STORM WATER CONVEYANCE SYSTEM HOLISTICALLY




SCOPE OF STUDIES

- ▶ HYDROLOGICAL AND HYDRAULIC MODELING USING SWMM SOFTWARE
 - ▶ SURFACE WATER AND CONVEYANCE SYSTEM ANALYSIS

 - ▶ NOT INCLUDED:
 - ▶ GROUNDWATER ANALYSIS
 - ▶ STORMWATER QUALITY ANALYSIS
 - ▶ FULL ENVIRONMENTAL REVIEWS

 - ▶ **IN ORDER TO ADDRESS ALL OF THESE ITEMS IN ONE REPORT WOULD BE TOO TIME CONSUMING AND VERY EXPENSIVE...HOWEVER....**
- 

OTHER RELATED STORMWATER INITIATIVES


- ▶ DISTRIBUTED GREEN INFRASTRUCTURE (DGI) PILOT STUDY IN WESTMOORLAND NEIGHBORHOOD
 - ▶ DGI “WHITE PAPER” ON IMPACTS OF GREEN INFRASTRUCTURE ON FLOOD MITIGATION
 - ▶ REVISIONS TO MGO CH 37 TO ADD MORE REQUIREMENTS TO BOLSTER RESILIENCY
- 
- A decorative graphic consisting of several parallel white lines of varying lengths, slanted upwards from left to right, located in the bottom right corner of the slide.

HOW RESULTS PLAY A PART IN FUTURE PROJECTS

- ▶ INFORM DESIGNS ON WHAT IS REQUIRED TO CORRECT HISTORICAL FLOODING
- ▶ DEMONSTRATES ORDER OF IMPLEMENTATION OF PROJECTS
- ▶ INFORMS PUBLIC AND POLICY MAKERS ON REALISTIC EXPECTATIONS FOR THE SYSTEM
- ▶ ALLOWS FOR MORE THOUGHTFUL DECISION MAKING

- ▶ **WHEN DESIGNING IMPROVEMENTS THIS IS ONE PIECE OF THE COMPLEX PUZZLE, ALONG WITH STORMWATER QUALITY AND ENVIRONMENTAL REVIEWS THAT WOULD BE COMPLETED TO COME UP WITH THOUGHTFUL SOLUTIONS.**

MORE INFORMATION

- ▶ [HTTPS://WWW.CITYOFMADISON.COM/FLOODING](https://www.cityofmadison.com/flooding)
 - ▶ [HTTPS://WWW.CITYOFMADISON.COM/FLOODING/CITY-INITIATIVES/WATERSHED-STUDIES](https://www.cityofmadison.com/flooding/city-initiatives/watershed-studies)
 - ▶ [HTTPS://WWW.CITYOFMADISON.COM/FLOODING/CITY-INITIATIVES/WATERSHED-STUDIES/WATERSHED-STUDY-LEARNING-HUB](https://www.cityofmadison.com/flooding/city-initiatives/watershed-studies/watershed-study-learning-hub)
 - ▶ [HTTPS://WWW.CITYOFMADISON.COM/ENGINEERING/STORMWATER](https://www.cityofmadison.com/engineering/stormwater)
- 
- A decorative graphic consisting of several parallel white lines of varying lengths, slanted upwards from left to right, located in the bottom right corner of the blue background.





East Badger Mill Creek Watershed Study Solutions and Report

City of Madison Engineering Division
Board of Public Works Meeting
May 17, 2023


CITY OF **MADISON**



Watershed Study Phasing



Schedule



*Presentations from PIM1 (Fall 2019) and PIM 2 can be found on the Watershed Study Website

CITY OF **MADISON**



Watershed Study Milestones


- PIM 1: 10/29/19
- PIM 2: 1/14/21
- Public Works Improvements: 12/8/22
- PIM 3: 12/13/22
- Report Final Draft Finished: 3/13/23
- Report Public Comment Period: 3/17/23 – 4/15/23
- BPC: 4/19/23
- BPW: 5/17/23
- FINAL REPORT:

https://www.cityofmadison.com/engineering/documents/projects/East_Badger_Mill_Creek_Watershed_Study_Draft_Final_Report.pdf

CITY OF **MADISON**



Existing Conditions 1% Chance Event Inundation Mapping



CITY OF MADISON



Proposed Solutions


1. McKenna Blvd. and Raymond Rd. Reconstruction
2. Riva Rd. Reconstruction
3. Raymond Rd., Cameron Dr., Barton Rd., and Whitney Way Reconstruction
4. East Pass Relief Box Culvert
5. McKee Road Relief Box Culvert
6. Carnwood Road Box Culvert Replacement
7. Lancaster Lane Box Culvert Replacement
8. Canterbury Road Box Culvert Replacement
9. McKenna Boulevard-Pilgrim Road Box Culvert Replacement
10. Westbrook Lane Box Culvert Replacement
11. Lucy Lincoln Hiestand Park Box Culvert and Frisch Road Storm Sewer
12. Prairie Road Box Culvert and Theresa Terrace Storm Sewer
13. Local Sewer Improvements

Results

- **10% Chance Storm Event – Target: Eliminate storm sewer surcharge**
 - Existing: 6.6 out of 35.9 street miles do not meet the target
 - Proposed: 0.7 out of 35.9 street miles do not meet the target
- **4% Chance Storm Event – Target: Maintain drivability of city streets**
 - Existing: 2.5 out of 35.9 street miles do not meet the target
 - Proposed: 0.6 out of 35.9 street miles do not meet the target
- **1% Chance Storm Event – Target: No structure flooding**
 - Existing: 70 out of 3,089 buildings do not meet the target
 - Proposed: 29 out of 3,089 buildings do not meet the target
- **1% Chance Storm Event – Target: Pass flow through greenway crossings**
 - Existing: 3 out of 10 greenway crossings do not meet the target
 - Proposed: all greenway crossings DO meet the target



Recommended Solutions




McKenna Blvd. and Raymond Rd. Reconstruction

Target:

- Reduce flooding during 10%, 4%, and 1% chance events

Conveyance improvements:

- Increase size of storm sewer and outfall to greenway
- Removes 7 structures from flooding
- Reduction in water leaving R/W during 1% chance event
- Reduction in street inundation for 10% and 4% chance events
- Cost estimate = \$3.5 million




Riva Rd. Reconstruction

Target:

- Reduce flooding during 10%, 4%, and 1% chance events

Conveyance improvements:

- Install box sections and increase size of outfall to greenway
- Removes 2 structures from flooding
- Facilitates upstream sewer improvements
- Meets 10% chance event target
- Cost estimate = \$910,000




Raymond, Cameron, Barton, and Whitney Reconstruction

Target:


- Reduce flooding during 10%, 4%, and 1% chance events

Conveyance improvements:

- Increase size of storm sewer
- Removes 5 structures from flooding
- Prevents UG parking inundation, 1% chance event
- Meets 10% and 4% chance event targets
- Cost estimate = \$2.5 million




Greenway Crossing Box Culvert Improvements



SON



Public Outreach for East Badger Mill Creek Report



- *Report posted for 30-day public comment period: none received*

CITY OF **MADISON**

