

219 North Fair Oaks

219 N Fair Oaks, LLC
Madison, WI 53714

2021.08.00

City of Madison Land Use Submittal - 09/12/2022

Potter Lawson

Architect:
749 University Row Suite 300
Madison, WI 53705
608-274-2741

DWG #	DRAWING TITLE
GENERAL	
CD01	COVER DRAWING
CIVIL	
C001	DEMOLITION PLAN
C100	SITE PLAN
C200	GRADING & EROSION CONTROL PLAN
C300	UTILITY PLAN
EXHIBIT	FIRE APPARATUS PLAN
LANDSCAPE	
L100	LANDSCAPE PLAN
ARCHITECTURAL	
A090	LOWER LEVEL AND FIRST FLOOR PLANS - OVERALL
A091	SECOND AND THIRD FLOOR PLANS - OVERALL
A093	FOURTH FLOOR AND ROOF PLANS - OVERALL
A200	BUILDING ELEVATIONS
A201	BUILDING ELEVATIONS
A202	BUILDING ELEVATIONS

PRELIMINARY

NOT FOR CONSTRUCTION


219 North Fair Oaks
219 N Fair Oaks, LLC
Madison, WI 53714


2021.08.00

COVER DRAWING

CD01

Notes:





Notes:

WYSER ENGINEERING

PRELIMINARY
NOT FOR CONSTRUCTION

219 North Fair Oaks
219 N Fair Oaks, LLC


219 North Fair Oaks Avenue
Madison, WI

2021.08.00

DATE ISSUANCE/REVISIONS #
09/12/22 CITY OF MADISON LAND USE SUBMITTAL

GRADING & EROSION CONTROL PLAN

C200




WASTEWATER

GRADING, SEEDING & RESTORATION NOTES

1. ALL GRADES SHOWN ARE FINAL FINISHED SURFACE GRADES.
 2. AREAS TO BE SEEDED SHALL HAVE A MINIMUM 6 INCHES TOPSOIL UNLESS OTHERWISE NOTED.
 3. AREAS NOT RESTORED WITH EROSION MATTING OR OTHER STABILIZATION MEASURES SHALL BE STABILIZED WITH MULCH.
 4. APPLY ANIONIC POLYMER TO DISTURBED AREAS IF EROSION BECOMES PROBLEMATIC.
 5. MULCH SHALL BE WEED-FREE STRAW AND SHALL BE INSTALLED AT THE RATE OF 2 TONS PER ACRE PER SECTION 627 OF "STANDARD SPECIFICATIONS FOR HIGHWAY AND STRUCTURE CONSTRUCTION" (WISDOT 2014)
 6. PERMANENT SEEDING SHALL NOT OCCUR BETWEEN SEPTEMBER 15TH AND APRIL 15TH. ALTERNATE SEEDING/PLANTING METHODS AND/OR EROSION PROTECTION MAY BE NECESSARY FOR SEEDING/PLANTING THAT OCCURS DURING THAT TIME. COORDINATE WITH THE OWNER AS NECESSARY.
 7. TEMPORARY STABILIZATION SHALL CONSIST OF ONE OR MORE OF THE FOLLOWING OPTIONS:
 - a. TEMPORARY SEEDING CONSISTING OF ANNUAL RYE GRASS APPLIED AT A RATE OF 1.5 LBS PER 1000 SQUARE FEET.

**Toll Free (800) 242-8511 -or- 8
Hearing Impaired TDD (800) 542-2289**



Potter Lawson

WYSER
ENGINEERING

Notes:

PRELIMINARY

NOT FOR CONSTRUCTION



Fair Oaks
219 North Fair Oaks
219 N Fair Oaks, LLC

219 North Fair Oaks Avenue
Madison, WI

2021.08.00

UTILITY PLAN

C300



Notes:

PRELIMINARY
NOT FOR CONSTRUCTION

219 North Fair Oaks
219 N Fair Oaks, LLC

219 North Fair Oaks Avenue
Madison, WI

2021.08.00

FIRE APPARATUS PLAN

EXHIBIT

Fair Oaks Development

219 North Fair Oaks Avenue

Madison, Wisconsin

Date: September 12, 2022
Scale: 1" = 30'-0"
Designer: kms


Seal:
To protect against legal liability,
the plans presented herein are
"schematic" and should not be
outsourced as "bidable" or
"construction documents" unless
approved by the Landscape
Designer. This is not an original
document unless stamped in
red, as ORIGINAL.

Revisions:


LANDSCAPE PLAN



L100

Reference Name:
McGann



KEYNOTES
1.17 2x10' WOOD FRAMED BALCONY
WITH STEEL GUARDRAIL, PTD, TYP







**FOURTH FLOOR
AND ROOF PLANS
- OVERALL**

A093


KEYNOTES	
1.17	2' x 10' WOOD FRAMED BALCONY WITH STEEL GUARDRAIL, PTD, TYP
1.18	WOOD FRAMED BALCONY WITH STEEL GUARDRAIL, PTD




2 NORTHWEST ELEVATION 2
A201 3/32" = 1'-0"



1 NORTHWEST ELEVATION
A201 3/32" = 1'-0"



4 NORTHWEST ELEVATION 3
A201 3/32" = 1'-0"



3 NORTH ENTRY ELEVATION
A201 3/32" = 1'-0"

PRELIMINARY
NOT FOR CONSTRUCTION

219 North Fair Oaks
219 N Fair Oaks, LLC
Madison, WI 53714

2021.08.00

DATE 09/12/2022 ISSUANCE/REVISIONS
CITY OF MADISON LAND USE SUBMITTAL



5 NORTH ELEVATION
A201 3/32" = 1'-0"

**BUILDING
ELEVATIONS**

A201

**PRELIMINARY
NOT FOR CONSTRUCTION**

219 North Fair Oaks
219 N Fair Oaks, LLC
Madison, WI 53714

2021.08.00

BUILDING ELEVATIONS

A202

2 EAST ELEVATION 2
A202
3/32" = 1'-0"

1 EAST ELEVATION
A202
3/32" = 1'-0"

5 NORTH COURTYARD ELEVATION
A202
3/32" = 1'-0"

4 SOUTHEAST COURTYARD ELEVATION
A202
3/32" = 1'-0"

3 SOUTHWEST COURTYARD ELEVATION
A202
3/32" = 1'-0"

7 WEST ELEVATION
A202
3/32" = 1'-0"

6 SOUTHWEST ELEVATION
A202
3/32" = 1'-0"



CITY OF MADISON LANDSCAPE WORKSHEET

Section 28.142 Madison General Ordinance

Project Location / Address 219 Fair Oaks Avenue, Madison, WI
Name of Project Fair Oaks Development
Owner / Contact William Butcher
Contact Phone 608-301-5008 Contact Email wjbutcher@gmail.com

**** Landscape plans for zoning lots greater than ten thousand (10,000) square feet in size
MUST be prepared by a registered landscape architect. ****

Applicability

The following standards apply to all exterior construction and development activity, including the expansion of existing buildings, structures and parking lots, except the construction of detached single-family and two-family dwellings and their accessory structures. The entire development site must be brought up to compliance with this section unless **all** of the following conditions apply, in which case only the affected areas need to be brought up to compliance:

- (a) The area of site disturbance is less than ten percent (10%) of the entire development site during any ten-(10) year period.
- (b) Gross floor area is only increased by ten percent (10%) during any ten-(10) year period.
- (c) No demolition of a principal building is involved.
- (d) Any displaced landscaping elements must be replaced on the site and shown on a revised landscaping plan.

Landscape Calculations and Distribution

Required landscaped areas shall be calculated based upon the total developed area of the property. Developed area is defined as that area within a single contiguous boundary which is made up of structures, parking, driveways and docking/loading facilities, but excluding the area of any building footprint at grade, land designated for open space uses such as athletic fields, and undeveloped land area on the same zoning lot. There are three methods for calculating landscape points depending on the size of the lot and Zoning District.

- (a) For all lots except those described in (b) and (c) below, five (5) landscape points shall be provided for each three hundred (300) square feet of developed area.

Total square footage of developed area 153,133

Total landscape points required 2,552

- (b) **For lots larger than five (5) acres**, points shall be provided at five (5) points per three hundred (300) square feet for the first five (5) developed acres, and one (1) point per one hundred (100) square feet for all additional acres.

Total square footage of developed area _____

Five (5) acres = 217,800 square feet

First five (5) developed acres = 3,630 points

Remainder of developed area _____

Total landscape points required _____

- (c) **For the Industrial – Limited (IL) and Industrial – General (IG) districts**, one (1) point shall be provided per one hundred (100) square feet of developed area.

Total square footage of developed area _____

Total landscape points required _____

Landscaping shall be distributed throughout the property along street frontages, within parking lot interiors, as foundation plantings, or as general site landscaping. The total number of landscape points provided shall be distributed on the property as follows.

Total Developed Area

Required landscaped areas shall be calculated based upon the total developed area of the property. Developed area is defined as that area within a single contiguous boundary which is made up of structures, parking, driveways and docking/loading facilities, but excluding the area of any building footprint at grade, land designated for open space uses such as athletic fields, and undeveloped land area on the same zoning lot.

Development Frontage Landscaping

Landscaping and/or ornamental fencing shall be provided between buildings or parking areas and the adjacent street(s), except where buildings are placed at the sidewalk. Landscape material shall include a mix of plant materials.

Interior Parking Lot Landscaping

The purpose of interior parking lot landscaping is to improve the appearance of parking lots, provide shade, and improve stormwater infiltration. **All parking lots with twenty (20) or more parking spaces** shall be landscaped in accordance with the interior parking lot standards.

Foundation Plantings

Foundation plantings shall be installed along building facades, except where building facades directly abut the sidewalk, plaza, or other hardscape features. Foundation plantings shall consist primarily of shrubs, perennials, and native grasses.


Screening Along District Boundaries

Screening shall be provided along side and rear property boundaries between commercial, mixed use or industrial districts and residential districts.

Screening of Other Site Elements

The following site elements shall be screened in compatibility with the design elements, materials and colors used elsewhere on the site: refuse disposal areas, outdoor storage areas, loading areas, and mechanical equipment.

Example Landscape Plan



Plant Name	Size	Qty.	Pnts.
Emerald Queen Maple	2-2.5"	9	-
Marshall Seedless Ash	2-2.5"	4	450
Clavey's Dwarf Honeysuckle	1 Gal	8	24
Princess Spirea	1 Gal	7	21
Potentilla	1 Gal	10	30
Taxus Cuspidata	2 Gal	12	60
			TOTAL 585

Call City Zoning, 266-4551, with your questions about this type of plan

LANDSCAPE PLAN AND LANDSCAPE WORKSHEET INSTRUCTIONS

Refer to Zoning Code Section 28.142 LANDSCAPING AND SCREENING REQUIREMENTS for the complete requirements for preparing and submitting a Landscape Plan and Landscape Worksheet.

Applicability.

The following standards apply to all exterior construction and development activity, including the expansion of existing buildings, structures and parking lots, except the construction of detached single-family and two-family dwellings and their accessory structures. The entire development site must be brought up to compliance with this section unless all of the following conditions apply, in which case only the affected areas need to be brought up to compliance:

- (a) The area of site disturbance is less than ten percent (10%) of the entire development site during any ten-(10) year period.
- (b) Gross floor area is only increased by ten percent (10%) during any ten-(10) year period.
- (c) No demolition of a principal building is involved.
- (d) Any displaced landscaping elements must be replaced on the site and shown on a revised landscaping plan.

Landscape Plan and Design Standards.

Landscape plans shall be submitted as a component of a site plan, where required, or as a component of applications for other actions, including zoning permits, where applicable. Landscape plans for zoning lots greater than ten thousand (10,000) square feet in size must be prepared by a registered landscape architect.

- (a) Elements of the landscape plan shall include the following:
 1. Plant list including common and Latin names, size and root condition (i.e. container or ball & burlap).
 2. Site amenities, including bike racks, benches, trash receptacles, etc.
 3. Storage areas including trash and loading.
 4. Lighting (landscape, pedestrian or parking area).
 5. Irrigation.
 6. Hard surface materials.
 7. Labeling of mulching, edging and curbing.
 8. Areas of seeding or sodding.
 9. Areas to remain undisturbed and limits of land disturbance.
 10. Plants shall be depicted at their size at sixty percent (60%) of growth.
 11. Existing trees eight (8) inches or more in diameter.
 12. Site grading plan, including stormwater management, if applicable.
- (b) Plant Selection. Plant materials provided in conformance with the provisions of this section shall be nursery quality and tolerant of individual site microclimates.
- (c) Mulch shall consist of shredded bark, chipped wood or other organic material installed at a minimum depth of two (2) inches.

Landscape Calculations and Distribution.

Required landscaped areas shall be calculated based upon the total developed area of the property. Developed area, for the purpose of this requirement, is defined as that area within a single contiguous boundary which is made up of structures, parking driveways and docking/loading facilities, but **excluding** the area of any building footprint at grade, land designated for open space uses such as athletic fields, and undeveloped land area on the same zoning lot.

- (a) Landscaping shall be distributed throughout the property along street frontages, within parking lot interiors, and as foundation plantings, or as general site landscaping.
- (b) Planting beds or planted areas must have at least seventy-five percent (75%) vegetative cover.
- (c) Canopy tree diversity requirements for new trees:
 1. If the development site has fewer than 5 canopy trees, no tree diversity is required.
 2. If the development site has between 5 and 50 canopy trees, no single species may comprise more than 33% of trees.
 3. If the development site has more than 50 canopy trees, no single species may comprise more than 20% of trees.

Development Frontage Landscaping.

Landscaping and/or ornamental fencing shall be provided between buildings or parking areas and the adjacent street(s), except where buildings are placed at the sidewalk. Landscape material shall include a mix of plant material meeting the following minimum requirements:

- (a) One (1) overstory deciduous tree and five (5) shrubs shall be planted for each thirty (30) lineal feet of lot frontage. Two (2) ornamental trees or two (2) evergreen trees may be used in place of one (1) overstory deciduous tree.
- (b) In cases where building facades directly abut the sidewalk, required frontage landscaping shall be deducted from the required point total.
- (c) In cases where development frontage landscaping cannot be provided due to site constraints, the zoning administrator may waive the requirement or substitute alternative screening methods for the required landscaping.
- (d) Fencing shall be a minimum of three (3) feet in height, and shall be constructed of metal, masonry, stone or equivalent material. Chain link or temporary fencing is prohibited.

Interior Parking Lot Landscaping.

The purpose of interior parking lot landscaping is to improve the appearance of parking lots, provide shade, and improve stormwater infiltration. **All parking lots with twenty (20) or more parking spaces** shall be landscaped in accordance with the following interior parking lot standards.

- (a) For new development on sites previously undeveloped or where all improvements have been removed, a minimum of eight percent (8%) of the asphalt or concrete area of the parking lot shall be devoted to interior planting islands, peninsulas, or landscaped strips. For changes to a developed site, a minimum of five percent (5%) of the asphalt or concrete area shall be interior planting islands, peninsulas, or landscaped strips. A planting island shall be located at least every twelve (12) contiguous stalls with no break or alternatively, landscaped strips at least seven (7) feet wide between parking bays.
- (b) The primary plant materials shall be shade trees with at least one (1) deciduous canopy tree for every one hundred sixty (160) square feet of required landscaped area. Two (2) ornamental deciduous trees may be substituted for one (1) canopy tree, but ornamental trees shall constitute no more than twenty-five percent (25%) of the required trees. No light poles shall be located within the area of sixty percent (60%) of mature growth from the center of any tree.
- (c) Islands may be curbed or may be designed as uncurbed bio-retention areas as part of an approved low impact stormwater management design approved by the Director of Public Works. The ability to maintain these areas over time must be demonstrated. (See Chapter 37, Madison General Ordinances, Erosion and Stormwater Runoff Control.)

Foundation Plantings.

Foundation plantings shall be installed along building facades, except where building facades directly abut the sidewalk, plaza, or other hardscape features. Foundation plantings shall consist primarily of shrubs, perennials, and native grasses. The Zoning Administrator may modify this requirement for development existing prior to the effective date of this ordinance, as long as improvements achieve an equivalent or greater level of landscaping for the site.

Screening Along District Boundaries.

Screening shall be provided along side and rear property boundaries between commercial, mixed use or industrial districts and residential districts. Screening shall consist of a solid wall, solid fence, or hedge with year-round foliage, between six (6) and eight (8) feet in height, except that within the front yard setback area, screening shall not exceed four (4) feet in height. Height of screening shall be measured from natural or approved grade. Berms and retaining walls shall not be used to increase grade relative to screening height.

Screening of Other Site Elements.

The following site elements shall be screened in compatibility with the design elements, materials and colors used elsewhere on the site, as follows:

- (a) Refuse Disposal Areas. All developments, except single family and two family developments, shall provide a refuse disposal area. Such area shall be screened on four (4) sides (including a gate for access) by a solid, commercial-grade wood fence, wall, or equivalent material with a minimum height of six (6) feet and not greater than seven (7) feet.
- (b) Outdoor Storage Areas. Outdoor storage areas shall be screened from abutting residential uses with a by a building wall or solid, commercial-grade wood fence, wall, year-round hedge, or equivalent material, with a minimum height of six (6) feet and not greater than seven (7) feet. Screening along district boundaries, where present, may provide all or part of the required screening.
- (c) Loading Areas. Loading areas shall be screened from abutting residential uses and from street view to the extent feasible by a building wall or solid, commercial-grade wood fence, or equivalent material, with a minimum height of six (6) feet and not greater than seven (7) feet. Screening along district boundaries, where present, may provide all or part of the required screening.
- (d) Mechanical Equipment. All rooftop and ground level mechanical equipment and utilities shall be fully screened from view from any street or residential district, as viewed from six (6) feet above ground level. Screening may consist of a building wall or fence and/or landscaping as approved by the Zoning Administrator.

Maintenance.

The owner of the premises is responsible for the watering, maintenance, repair and replacement of all landscaping, fences, and other landscape architectural features on the site. All planting beds shall be kept weed free. Plant material that has died shall be replaced no later than the upcoming June 1.