



**Official Project Name** Oakridge Ave, Ohio Ave and Miller Ave Resurfacing Assm't District-2013

**Project Engineer** LeAnne Hannan 266-4057

**Project Limits** Division to Atwood, Willard to Oakridge, Willard to Lakeland  
Ald. Marsha Rummel

<b>Street</b>	<b>Existing</b>	<b>Proposed</b>
Project Type		Resurfacing Oakridge, Reconstruct Ohio & Miller
Last Surfaced	1980 (Oakridge) 1989 (Ohio) 1982 (Miller)	
Pavement Rating	4 (Oakridge) 5 (Ohio) 5 (Miller)	
Curb Rating	8 (Oakridge) 5(Ohio) 3(Miller)	
Width	28	same
Surface Type	Asphaltic. Asphalt over Conc (Ohio)	Asphaltic
Traffic (Average Vehicles per Day)	800-1500 Oakridge,	Same

<b>Sidewalk</b>	<b>Existing</b>	<b>Proposed</b>
Work Required		Replace As Necessary

<b>Storm Sewer</b>	<b>Existing</b>	<b>Proposed</b>
Work Required		relocate from Oakridge terrace to street, line Miller Ave storm
Design Storm		10 Year
Size	12" , 15" , 3'x2.5' box (Miller)	TBD
Material	VP	Concrete
Year	1916, 1914 (box)	2014

<b>Sanitary Sewer</b>	<b>Existing</b>	<b>Proposed</b>
Work Required		Complete Replacement
Size	6 Inch (Substandard), 10"(Miller)	8 Inch
Material	VP	PVC
Year	1914-1918	2014

<b>Water Main</b>	<b>Existing</b>	<b>Proposed</b>
Work Required		Complete Replacement
Size	6", 8", 10"	8", 12"
Material	SACI UL	ductile iron
Year	1916-1917	2014

<b>Parking</b>	<b>Existing</b>	<b>Proposed</b>
Parking Conditions	Parking one side	Same

<b>Street Lighting</b>	<b>Existing</b>	<b>Proposed</b>
Street Lighting	On MG&E wood poles	Same

<b>Cost</b>		
Total Cost	\$3,984,200	\$640,000 street, \$2200 Metro,
Adjacent Property Assessments	\$239,500	\$92,000 storm from street acct
City Share	\$3,744,700	\$410,000 storm, \$1,600,000 sanitary \$1,240,000 water

**Assessment Policy**  
 Street Concrete Items Owner 50% / City 50%  
 Sanitary Sewer Lateral Replacements Owner 25% / City 75%  
 Assessments payable in one lump sum or over a period of 8 years, with 3.5% interest charged on unpaid balance  
 All remaining contract items to be paid for by the City of Madison

<b>Schedule</b>	
Start Date	5-May-14
Length of Project	3-4 months

**Traffic Calming** replace 2 existing speed humps, add 3 more-if approved by PBMV, BPW and CC

**Traffic Detours** none, Metro buses will use Atwood Ave.

**Real Estate Requirements** Not Required

**Tree Information**

trimming prior to construction

**Correspondence**

---

2147 Oakridge has problems getting in drive, Type X curb may be used

2326 Oakridge has steep drive on Ohio, new curb will be higher making drive less steep.