

SECTION B: SPECIAL PROVISIONS

STREETS DIVISION SOUTH POINT YARD WASTE SITE AND DRIVEWAY REPAVING CONTRACT NO. XXXX

SECTION 104: SCOPE OF WORK

This contract is for the pavement removal, shaping and replacement of existing asphalt pavement for the yard waste site (area A) located at 424 South Point Road and driveway (area B) located at 424 South Point Road. Pavement marking is not required.

The Contractor is given the option for pavement removal. This could include milling, pulverizing or both.

The scope of work includes the furnishing of all labor, materials, equipment, tools, and services; and any other costs whatsoever which may be required for the installation of all components as specified in these special provisions.

SECTION 104.1 LANDS FOR WORK

All lands for work are located at 424 South Point Road. Existing vegetation, trees, bollards, fencing, and other landscape items shall not be trimmed or removed during the execution of this contract.

SECTION 105.12 COOPERATION BY CONTRACTOR

The yard waste drop-off site shall remain open to the public. The Contractor shall coordinate with Streets Department staff as needed for daily access requirements of employees, deliveries, and traffic required in normal daily operations. Contractor shall expect to complete the work in multiple phases. Please coordinate all work with John Marshall 267-1174 to assure access is maintained during the project.

SECTION 107.2 PROTECTION AND RESTORATION OF PROPERTY

The Contractor shall not grade, excavate, store materials or equipment, or otherwise disturb any areas beyond project limits. The Contractor shall ensure that adjacent pavement, buildings, grass, trees, bollards, fences and other landscape features are not

damaged during the execution of this contract. Any damage beyond project limits shall be repaired as directed by the Engineer at the Contractor's own expense.

SECTION 107.6 DUST PROOFING

The Contractor shall take all necessary steps to control dust arising from operations connected with this contract. When ordered by the Engineer, the Contractor shall dust proof the construction area by using power sweepers and water. Dust proofing shall be incidental with operations connected with this contract.

SECTION 107.7 BARRICADES, WARNING SIGNS, AND FLAGGING

The Contractor shall provide, install, and maintain orange traffic barrels, cones, construction warning tape or other approved devices as needed to control access to the property during the execution of this contract. Driveway access shall be maintained at all times. Such warning devices shall be incidental to Bid Item 10911 – Mobilization.

SECTION 109.7 TIME OF COMPLETION

The Contractor shall begin work on or before **JULY 18, 2016**. The time of completion for the entire project shall be **TWENTY (20) CALENDAR DAYS**.

Bid Item 90001 REMOVE EXISTING ASPHALT PAVEMENT, SHAPE, TEST ROLL AND PAVE

DESCRIPTION

This special provision describes the removal (milling and/or pulverizing), shaping, test rolling and paving of the yard waste site and driveway located at 424 South Point Road. The Contractor shall expect that multiple phases may be necessary to maintain public access to the yard waste drop-off site.

The Contractor shall remove the existing asphalt pavement either by milling or pulverizing. Any excess material that cannot be used shall be removed by the Contractor at their expense and shall be considered incidental to this bid item. No additional compensation will be provided.

The Contractor is responsible for establishing all grades to assure proper drainage. Shape existing base course and/or pulverized asphalt as needed to drain away from buildings and match existing drainage patterns.

The existing base course shall be roll tested in multiple passes as designated by the Field Engineer. The method of testing shall be as per section 201.4(c) of the Standard Specifications.

All asphalt pavements shall be 3" of 12.5 mm E-1.

METHOD OF MEASUREMENT

The removal of existing asphalt pavement, shaping, test rolling and paving of the yard waste site and driveway shall be measured by the square yard.

BASIS OF PAYMENT

Payment for remove existing asphalt pavement, shape, test roll and pave shall be full compensation for the work as described above. The work includes all labor, equipment, materials, and incidentals required to complete the work per these specifications and detail.

PROPOSAL

**STREETS DIVISION
SOUTH POINT YARD WASTE SITE AND DRIVEWAY REPAVING
CONTRACT NO: XXXX**

ACCOUNT NUMBER: 10876 -44 -131-

BID ITEM	TYPE OF WORK	ESTIMATED QUANTITIES	UNIT
10701	TRAFFIC CONTROL	1	LS
10901	MOBILIZATION	1	LS
20219	BREAKER RUN	600	TON
40321	UNDERCUT (UNDISTRIBUTED)	1000	SY
90001	REMOVE EXISTING ASPHALT PAVEMENT, SHAPE, TEST ROLL AND PAVE	7225	SY