



**Project Limits** Lumbermans Trail to I-39/90  
Ald. Amanda Hall & Ald. Denis DeMarb

<b>Street</b>	<b>Existing</b>	<b>Proposed</b>
---------------	-----------------	-----------------

Project Type		Resurfacing w/utility replacement
Last Surfaced	1999	
Pavement Rating	5	
Curb Rating	7	
Width	36' each side of median	same
Surface Type	asphalt	Asphaltic
Traffic (Average Vehicles per Day)	13,850 - 20,800	Same

<b>Sidewalk</b>	<b>Existing</b>	<b>Proposed</b>
-----------------	-----------------	-----------------

Work Required		Replace As Necessary
---------------	--	----------------------

<b>Storm Sewer</b>	<b>Existing</b>	<b>Proposed</b>
--------------------	-----------------	-----------------

Work Required		inlet adjustments, special waterway @ Meadowlark
Design Storm Size	21", 54", 10'x5' box	same
Material	RCP	RCP
Year	1962-1963	same

<b>Sanitary Sewer</b>	<b>Existing</b>	<b>Proposed</b>
-----------------------	-----------------	-----------------

Work Required		Replace between S. Stoughton Rd & Flora Ln, relocate from terrace to street from Acewood to Flora
Size	8 Inch (Substandard)	TBD, will be upisized.
Material	VP	PVC
Year	1958-1971	2017

<b>Water Main</b>	<b>Existing</b>	<b>Proposed</b>
-------------------	-----------------	-----------------

Work Required		Complete Replacement
Size	8"-12"	12"
Material	cast iron	ductile iron
Year	1968	2017

<b>Parking</b>	<b>Existing</b>	<b>Proposed</b>
----------------	-----------------	-----------------

Parking Conditions	Parking both sides	Same
--------------------	--------------------	------

<b>Street Lighting</b>	<b>Existing</b>	<b>Proposed</b>
------------------------	-----------------	-----------------

Street Lighting	in median	Same conduit in median for future use
-----------------	-----------	--

<b>Information Technology</b>	<b>Existing</b>	<b>Proposed</b>
-------------------------------	-----------------	-----------------

	none	conduit installed along length of project to provide fiber to City facilities.
--	------	--

**Cost**

Total Cost	\$3,583,000	street \$915K, Signals \$150K
Adjacent Property Assessments	\$52,460	sanitary \$1,108,000K, water \$1,300,000
City Share	\$3,530,540	IT \$100K, Lights \$10K

**Assessment Policy**

Street Concrete Items Owner 50% / City 50%

Sanitary Sewer Lateral Replacements Owner 25% / City 75%

Assessments payable in one lump sum or over a period of 8 years, with 3.0% interest charged on unpaid balance

All remaining contract items to be paid for by the City of Madison

**Schedule**

Start Date mid-May 2016

Length of Project 4-5 months

**Traffic**

one lane, in each direction, will be maintained during construction.  
pavement markings will include dedicated bike lanes and continental crosswalks  
pedestrian flashers will be installed at Thompson & Flora Ln.  
conduit will be installed for possible future signals at Thompson & Meadowlark  
future signals would be evaluated by PBMV

**Real Estate Requirements**

Not Required

**Tree Information**

no removals scheduled at this time

**Public Informational Meeting**

Jan. 6, 2016

15 attendees

**Correspondence**

---