



PROJECT SUMMARY AND FACT SHEET:

N Livingston St Utilities with Resurfacing Assessment District - 2013

Project Engineer: Eric Dundee 266-4913
Alder: Bridget Maniaci, District 2
Project Limits: North Livingston Street from East Washington Avenue to East Johnson Street
 Rutledge Street from Ingersoll St to Few St

Project Summary: The proposed project includes utility and pavement replacement on N Livingston Street from E Washington Avenue to East Johnson Street. All pavement, curb and gutter and drive aprons will be replaced along with sanitary sewer and water main. Storm sewer will be upgraded as needed to serve the reconstructed streets along with E Johnson St. Sidewalk will be replaced as needed to repair any damaged sections and as required for the installation of sanitary sewer laterals. Street widths proposed to remain. The corner radii are proposed to remain the same as existing.

Street: Rutledge Street	Existing	Proposed
Project Type		Reconstruction
Last Surfaced	1998 Asphalt Overlay	
Pavement Rating	8	
Curb Rating	7	
Width	40 feet - face to face	Remain same.
Surface Type	Asphalt	Asphalt
Sidewalk	Existing	Proposed
	Existing sidewalk to remain.	Replace Damaged Sections/Ensure Ramps ADA Compliant and replace as required for installation of sewer laterals.
Storm Sewer	Existing	Proposed
Work Required		Installing large storm sewer main from E Washington to E Johnson St
Design Storm Size	12 - 15 Inches	54 Inch main with 12"-18" leads
Material	Varies Clay & RCP	RCP
Year	Varies 1908 - 1951	
Sanitary Sewer	Existing	Proposed
Work Required		Replace Sanitary Sewer Mains & Laterals from E Mifflin to E Johnson
Size	8"-24" inches	12 Inches
Material	VP	PVC
Year	Varies 1904, 1908, 2007	
Water Main	Existing	Proposed
Work Required		Replace water main from E Mifflin to E Johnson
Size	6 Inch & 10 Inch	10 Inches
Material	Cast Iron & Ductile Iron	Ductile Iron
Year	Varies 1937-1950, 2007	
Parking	Existing	Proposed
Parking Conditions	Parking Allowed - Restrictions Vary	No Proposed Changes
Street Lighting	Existing	Proposed
Street Lighting	wood poles	none

Cost

Total Cost	\$1,202,000
Street Assessments	\$36,500
Storm Assessments	\$7,500
Sanitary Assessments	\$14,500
Street Light Assessments	\$21,000
City of Madison	\$1,148,500

Assessment Policy

The cost of concrete items (curb & gutter, sidewalk and drive aprons) is assessed 50% to property owners with remaining 50% paid by the City.

The cost for sanitary laterals is assessed 25% to property owner with remaining 75% paid by City.

Costs for private storm sewer connections are assessed 100% to the property owner requiring the connection.

Assessments are payable in one lump sum or over a period of 8 years, with 3% interest charged on unpaid balance.

Schedule

Start Date	4-Mar-13
Project Duration	3 1/2 Months

Traffic Calming: None Proposed

Traffic Detours: None

Real Estate Requirements: None

Tree Information: (1) 5" at 710 E Mifflin St (N Livingston frontage)

Rain Garden Information: Not eligible street.

Correspondence: City Engineering held a public informational meeting regarding the project on Oct. 24, 2012.

Project Location: