



North Thornton Avenue Reconstruction

Project Engineer Lisa Coleman 266-4093

Project Limits

Alder: Maniaci North Thornton Ave from Sherman Ave to new Tenney Park Shelter

Street	Existing	Proposed
Project Type		Curb, Pavement & Storm Sewer replacement
Last Surfaced	1965	
Pavement Rating	5	
Curb Rating	3	
Width	~31	24' F-F
Surface Type	Asphalt	Asphalt

Sidewalk	Existing	Proposed
Work Required	none	8'-wide asphalt path

Storm Sewer	Existing	Proposed
Work Required		Inlet, pipe & outfall replacement as necessary
Size	12"	
Material	varies	
Year	1915 & unknown	

Sanitary Sewer	Existing	Proposed
No Work Required	none	

Water Main	Existing	Proposed
No Work Required	none	

Parking	Existing	Proposed
Parking Conditions	in gravel alongside street	alongside street in designated parking spots

Street Lighting	Existing	Proposed
No Work Required	none	

Cost

Total Cost \$566,800
 Adjacent Property Assessments no assessments
 City Share 100% (50% Parks Division, 50% Engineering Division)

Schedule

Start Date 1-Apr-12
 Length of Project 24-May-12

Correspondence	None
----------------	------



Location Map



Source: GT Viewer