



City of Madison Fire Department

314 W Dayton Street, Madison, WI 53703-2506
Phone: 608-266-4420 • Fax: 608-267-1100 • E-mail: fire@cityofmadison.com

Project Address: 4846 Eastpark Blvd - Lot 49-50



Contact Name & Phone #: Greg Held - 608-836-3690

FIRE APPARATUS ACCESS AND FIRE HYDRANT WORKSHEET

1. Is the building completely protected by an NFPA 13 or 13R automatic fire sprinkler system? If non-sprinklered , fire lanes extend to within 150-feet of all portions of the exterior wall? If sprinklered , fire lanes are within 250-feet of all portions of the exterior wall?	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> Yes <input checked="" type="checkbox"/> Yes	<input type="checkbox"/> No <input type="checkbox"/> No <input type="checkbox"/> No	<input type="checkbox"/> N/A <input checked="" type="checkbox"/> N/A <input type="checkbox"/> N/A
2. Is the fire lane constructed of concrete or asphalt, designed to support a minimum load of 85,000 lbs? a) Is the fire lane a minimum unobstructed width of at least 20-feet? b) Is the fire lane unobstructed with a vertical clearance of at least 13½-feet? c) Is the minimum inside turning radius of the fire lane at least 28-feet? d) Is the grade of the fire lane not more than a slope of 8%? e) Is the fire lane posted as fire lane? (Provide detail of signage.) f) Is a roll-able curb used as part of the fire lane? (Provide detail of curb.) g) Is part of a sidewalk used as part of the required fire lane? (Must support +85,000 lbs.)	<input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> Yes <input type="checkbox"/> Yes <input type="checkbox"/> Yes <input type="checkbox"/> Yes	<input type="checkbox"/> No <input type="checkbox"/> No <input type="checkbox"/> No <input type="checkbox"/> No <input checked="" type="checkbox"/> No <input checked="" type="checkbox"/> No <input checked="" type="checkbox"/> No	<input type="checkbox"/> N/A <input type="checkbox"/> N/A <input type="checkbox"/> N/A <input type="checkbox"/> N/A <input type="checkbox"/> N/A <input type="checkbox"/> N/A <input type="checkbox"/> N/A
3. Is the fire lane obstructed by security gates or barricades? If yes: a) Is the gate a minimum of 20-feet clear opening? b) Is an approved means of emergency operations installed, key vault, padlock or key switch?	<input type="checkbox"/> Yes <input type="checkbox"/> Yes <input type="checkbox"/> Yes	<input checked="" type="checkbox"/> No <input type="checkbox"/> No <input type="checkbox"/> No	<input type="checkbox"/> N/A <input checked="" type="checkbox"/> N/A <input checked="" type="checkbox"/> N/A
4. Is the Fire lane dead-ended with a length greater than 150-feet? If yes, does the area for turning around fire apparatus comply with IFC D103?	<input type="checkbox"/> Yes <input type="checkbox"/> Yes	<input checked="" type="checkbox"/> No <input type="checkbox"/> No	<input type="checkbox"/> N/A <input checked="" type="checkbox"/> N/A
5. Is any portion of the building to be used for high-piled storage in accordance with IFC Chapter 3206.6 If yes, see IFC 3206.6 for further requirements.	<input type="checkbox"/> Yes	<input checked="" type="checkbox"/> No	<input type="checkbox"/> N/A
6. Is any part of the building <u>greater than 30-feet</u> above the grade plane? If yes, answer the following questions: a) Is the aerial apparatus fire lane parallel to one entire side of the building and covering at least 25% of the perimeter? b) Is the near edge of the aerial apparatus fire lane between 15' and 30' from the building? c) Are there any overhead power or utility lines located across the aerial apparatus fire lane? d) Are there any tree canopies expected to grow across the aerial fire lane? (Based on mature canopy width of tree species) e) Does the aerial apparatus fire lane have a minimum unobstructed width of 26-feet? f) Is the space between the aerial lane and the building free of trees exceeding 20' in heights?	<input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> Yes <input type="checkbox"/> Yes <input type="checkbox"/> Yes <input type="checkbox"/> Yes <input checked="" type="checkbox"/> Yes <input type="checkbox"/> Yes	<input type="checkbox"/> No <input type="checkbox"/> No <input checked="" type="checkbox"/> No <input checked="" type="checkbox"/> No <input checked="" type="checkbox"/> No <input type="checkbox"/> No <input checked="" type="checkbox"/> No	<input type="checkbox"/> N/A <input type="checkbox"/> N/A <input type="checkbox"/> N/A <input type="checkbox"/> N/A <input type="checkbox"/> N/A <input type="checkbox"/> N/A <input type="checkbox"/> N/A
7. Are all portions of the required fire lanes within 500-feet of at least (2) hydrants? <i>Note: Distances shall be measured along the path of the hose lay as it comes off the fire apparatus.</i> a) Is the fire lane at least 26' wide for at least 20-feet on each side of the hydrants? b) Is there at least 40' between a hydrant and the building? c) Are the hydrant(s) setback no less than 5-feet nor more than 10-feet from the curb or edge of the street or fire lane? d) Are hydrants located in parking lot islands a minimum of 3½-feet from the hydrant to the curb? e) Are there no obstructions, including but not limited to: power poles, trees, bushes, fences, posts located, or grade changes exceeding 1½-feet, within 5-feet of a fire hydrant? <i>Note: Hydrants shall be installed and in-service prior to combustible construction on the project site.</i>	<input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> Yes	<input type="checkbox"/> No <input type="checkbox"/> No <input type="checkbox"/> No <input type="checkbox"/> No <input type="checkbox"/> No <input type="checkbox"/> No	<input type="checkbox"/> N/A <input type="checkbox"/> N/A <input type="checkbox"/> N/A <input type="checkbox"/> N/A <input type="checkbox"/> N/A <input type="checkbox"/> N/A

Attach an additional sheet if further explanation is required for any answers.

This worksheet is based on **MGO 34.503** and **IFC 2015 Edition Chapter 5 and Appendix D**; please see the codes for further information.



SHEET INDEX	
SITE	
C-1.0	OVERALL SITE PLAN
C-1.1	ENLARGED SITE PLAN LOT 49
C-1.2	ENLARGED SITE PLAN LOT 50 NORTH
C-1.3	ENLARGED SITE PLAN LOT 50 SOUTH
C-2.1	SITE LIGHTING LOT 49
C-2.2	SITE LIGHTING LOT 50 NORTH
C-2.3	SITE LIGHTING LOT 50 SOUTH
C-3.1	LOT COVERAGE LOT 49
C-3.2	LOT COVERAGE LOT 50 NORTH
C-3.3	LOT COVERAGE LOT 50 SOUTH
C1	CIVIL TITLE SHEET
C2	NOTES & LEGENDS
C3	EXISTING CONDITIONS
C4	EROSION CONTROL PLAN
C5	PHASE I OVERALL SITE & UTILITY PLAN
C6	LOT 49 SITE & UTILITY PLAN
C7	LOT 50 NORTH SITE & UTILITY PLAN
C8	LOT 50 SOUTH SITE & UTILITY PLAN
C9	PHASE I OVERALL GRADING PLAN
C10	LOT 49 GRADING PLAN
C11	LOT 50 NORTH GRADING PLAN
C12	LOT 50 SOUTH GRADING PLAN
C13	FIRE ACCESS PLAN
L100	OVERALL LANDSCAPE PLAN
L103	ENLARGED LANDSCAPE LOT 49
L104	ENLARGED LANDSCAPE LOT 50 NORTH
L105	ENLARGED LANDSCAPE LOT 50 SOUTH
ARCHITECTURAL LOT 49	
A-1.0	BASEMENT PLAN
A-1.1	FIRST FLOOR PLAN
A-1.2	SECOND FLOOR PLAN
A-1.3	THIRD FLOOR PLAN
A-1.4	FOURTH FLOOR PLAN
A-2.1	EXTERIOR ELEVATIONS
A-2.2	EXTERIOR ELEVATIONS
A-2.3	ELEVATIONS COLORED
A-2.4	ELEVATIONS COLORED
ARCHITECTURAL LOT 50	
A-1.0	BASEMENT PLAN
A-1.1	FIRST FLOOR PLAN
A-1.2	SECOND FLOOR PLAN
A-1.3	THIRD FLOOR PLAN
A-1.4	FOURTH FLOOR PLAN
A-2.1	EXTERIOR ELEVATIONS
A-2.2	EXTERIOR ELEVATIONS
A-2.3	EXTERIOR ELEVATIONS
A-2.4	EXTERIOR ELEVATIONS
A-2.5	ELEVATIONS COLORED
A-2.6	ELEVATIONS COLORED
A-2.7	ELEVATIONS COLORED
A-2.8	ELEVATIONS COLORED
EXTERIOR RENDERINGS	
R1	LOT 49 LOOKING EAST
R2	LOT 49 LOOKING SOUTH
R3	LOT 49-50 LOOKING SOUTH
R4	LOT 50 LOOKING WEST
R5	LOT 50 LOOKING NORTHWEST
R6	LOT 50 LOOKING SOUTHEAST
R7	LOT 50 LOOKING NORTHEAST


ISSUED
Issued for LUA & UDC Submittals - February 27, 2023


PROJECT TITLE
**CASCADE -
THE AMERICAN
CENTER EASTPARK
FIFTH ADDITION**

4846 Eastpark Blvd.
Madison, WI
SHEET TITLE
**Phase I - Overall
Site Plan**

Lot 49-50
SHEET NUMBER


C-1.0
PROJECT NO. **2155**
© Knothe & Bruce Architects, LLC






Site Development Data:			
Zoning	TR-U2		
Densities:			
Lot Area	74,337 S.F./1.71 ACRES		
Dwelling Units	67 units		
Lot Area / D.U.	1,110 S.F./D.U.		
Density	39 units/Acre		
Lot Coverage	40,600 S.F. (53%)	PROVIDED	ZONING REQUIREMENTS
Building Height	4 stories/54'-0"		75% Max.
Gross Building Area	95,002 S.F.		4 Stories/52' Max.
Dwelling Unit Mix:			
Studio	9		
One Bedroom	30		
Two Bedroom	28		
Total Dwelling Units	67		
Vehicle Parking Stalls:			
Underground Garage	56		
Surface	43		
Total	99		
Electric Vehicle Parking Stalls:			
EV Installed	2		2 - Min. 2% of Residential Stalls
EV Ready	6		6 - Min. 10% of Residential Stalls
Total	8		8 - Min. EV Required
Bicycle Parking:			
Long-Term Covered Garage	67		67 - Min. 100% of Req'd
(49 F.M. & 18 W.M.)			
Short-Term Guest - Surface	8		7 - Min. 10% of Units
Total	75		74 - Min. Bike Stalls Required

- GENERAL NOTES:
- THE APPLICANT SHALL REPLACE ALL SIDEWALK AND CURB AND GUTTER THAT ABUTS THE PROPERTY THAT IS DAMAGED BY THE CONSTRUCTION, OR ANY SIDEWALK AND CURB AND GUTTER WHICH THE CITY ENGINEER DETERMINES NEEDS TO BE REPLACED BECAUSE IT IS NOT AT A DESIRABLE GRADE, REGARDLESS OF WHETHER THE CONDITION EXISTED PRIOR TO BEGINNING CONSTRUCTION.
 - ALL WORK IN THE PUBLIC RIGHT OF WAY SHALL BE PERFORMED BY A CITY-LICENSED CONTRACTOR.
 - ALL DAMAGE TO THE PAVEMENT ON CITY STREETS, AND ADJACENT TO THIS DEVELOPMENT SHALL BE RESTORED IN ACCORDANCE WITH THE CITY OF MADISON'S PAVEMENT PATCHING CRITERIA.
 - ALL PROPOSED STREET TREE REMOVALS WITHIN THE RIGHT OF WAY SHALL BE REVIEWED BY CITY FORESTRY BEFORE THE PLAN COMMISSION MEETING. STREET TREE REMOVALS REQUIRE APPROVAL AND A TREE REMOVAL PERMIT ISSUED BY CITY FORESTRY. ANY STREET TREE REMOVALS REQUESTED AFTER THE DEVELOPMENT PLAN IS APPROVED BY THE PLAN COMMISSION OR THE BOARD OF PUBLIC WORKS AND CITY FORESTRY WILL REQUIRE A MINIMUM OF A 72-HOUR REVIEW PERIOD WHICH SHALL INCLUDE THE NOTIFICATION OF THE ALDERPERSON WITHIN WHO'S DISTRICT IS AFFECTED BY THE STREET TREE REMOVAL(S) PRIOR TO A TREE REMOVAL PERMIT BEING ISSUED.
 - AS DEFINED BY THE SECTION 107.13 OF CITY OF MADISON STANDARD SPECIFICATIONS FOR PUBLIC WORKS CONSTRUCTION: NO EXCAVATION IS PERMITTED WITHIN 5 FEET OF THE TRUNK OF THE STREET TREE OR WHEN CUTTING ROOTS OVER 3 INCHES IN DIAMETER. IF EXCAVATION IS NECESSARY, THE CONTRACTOR SHALL CONTACT MADISON CITY FORESTRY (266-4816) PRIOR TO EXCAVATION. CITY OF MADISON FORESTRY PERSONNEL SHALL ASSESS THE IMPACT TO THE TREE AND TO ITS ROOT SYSTEM PRIOR TO WORK COMMENCING. TREE PROTECTION SPECIFICATIONS CAN BE FOUND ON THE FOLLOWING WEBSITE: CITYOFMADISON.COM/BUSINESS/PW/SPECS.CFM
 - CONTRACTOR SHALL TAKE PRECAUTIONS DURING CONSTRUCTION TO NOT DISFIGURE, SCAR, OR IMPAIR THE HEALTH OF ANY STREET TREE. CONTRACTOR SHALL OPERATE EQUIPMENT IN A MANNER AS TO NOT DAMAGE THE BRANCHES OF THE STREET TREE. THIS REQUIRE USING SMALLER EQUIPMENT AND LOADING AND UNLOADING MATERIALS IN A DESIGNATED SPACE AWAY FROM TREES ON THE CONSTRUCTION SITE. ANY DAMAGE OR INJURY TO EXISTING STREET TREES (EITHER ABOVE OR BELOW GROUND) SHALL BE REPORTED IMMEDIATELY TO CITY FORESTRY AT 266-4816. PENALTIES AND REMEDIATION SHALL BE REQUIRED.
 - SECTION 107.13(G) OF CITY OF MADISON STANDARD SPECIFICATIONS FOR PUBLIC WORKS CONSTRUCTION ADDRESSES SOIL COMPACTION NEAR STREET TREES AND SHALL BE FOLLOWED BY CONTRACTOR. THE STORAGE OF PARKED VEHICLES, CONSTRUCTION EQUIPMENT, BUILDING MATERIALS, REFUSE, EXCAVATED SPOILS OR DUMPING OF POISONOUS MATERIALS ON OR AROUND TREES AND ROOTS WITHIN FIVE (5) FEET OF THE TREE OR WITHIN THE PROTECTION ZONE IS PROHIBITED.
 - ON THIS PROJECT, STREET TREE PROTECTION ZONE FENCING IS REQUIRED. THE FENCING SHALL BE ERECTED BEFORE THE DEMOLITION, GRADING OR CONSTRUCTION BEGINS. THE FENCE SHALL INCLUDE THE ENTIRE WIDTH OF TERRACE AND, EXTEND AT LEAST 5 FEET ON BOTH SIDES OF THE OUTSIDE EDGE OF THE TREE TRUNK. DO NOT REMOVE THE FENCING TO ALLOW FOR DELIVERIES OR EQUIPMENT ACCESS THROUGH THE TREE PROTECTION ZONE.
 - STREET TREE PRUNING SHALL BE COORDINATED WITH MADISON FORESTRY AT A MINIMUM OF TWO WEEKS PRIOR TO THE START OF CONSTRUCTION FOR THIS PROJECT. ALL PRUNING SHALL FOLLOW THE AMERICAN NATIONAL STANDARDS INSTITUTE (ANSI) A300 - PART 1 STANDARDS FOR PRUNING.
 - AT LEAST ONE WEEK PRIOR TO STREET TREE PLANTING, CONTRACTOR SHALL CONTACT CITY FORESTRY AT (608) 266-4816 TO SCHEDULE INSPECTION AND APPROVAL OF NURSERY TREE STOCK AND REVIEW PLANTING SPECIFICATIONS WITH THE LANDSCAPER.
 - APPROVAL OF PLANS FOR THIS PROJECT DOES NOT INCLUDE ANY APPROVAL TO PRUNE, REMOVE, OR PLANT TREES IN THE PUBLIC RIGHT-OF-WAY. PERMISSION FOR SUCH ACTIVITIES MUST BE OBTAINED FROM THE CITY FORESTER (266-4816).
 - THE PUBLIC RIGHT-OF-WAY IS THE SOLE JURISDICTION OF THE CITY OF MADISON AND IS SUBJECT TO CHANGE AT ANY TIME. NO ITEMS SHOWN ON THIS SITE PLAN IN THE RIGHT-OF-WAY ARE PERMANENT AND MAY NEED TO BE REMOVED AT THE APPLICANTS EXPENSE UPON NOTIFICATION BY THE CITY.





BIKE RACKS

INTERIOR & EXTERIOR FLOOR MOUNTED: "INVERTED U" TYPE. MADRAX UX OR SARIS BIKE DOCK



INTERIOR WALL MOUNTED: MADRAX VERTICAL RACK OR SARIS BIKE TRACK






Site Development Data:		
Zoning	TR-U2	
Densities:		
Lot Area	134,349 S.F./3.08 ACRES	
Dwelling Units	134 units	
Lot Area / D.U.	1,003 S.F./D.U.	
Density	43.5 units/Acre	
Lot Coverage	79,200 S.F. (59%)	75% Max.
Building Height	4 stories/54'-0"	4 Stories/52' Max.
Gross Building Area	199,967 S.F.	
Dwelling Unit Mix:		
Studio	24	
One Bedroom	54	
One Bedroom + Den	8	
Two Bedroom	48	
Total Dwelling Units	134	
Vehicle Parking Stalls:		
Underground Garage	135	
Surface	78	
Total	213	
Electric Vehicle Parking Stalls:		
EV Installed	3	3 - Min. 2% of Residential Stalls
EV Ready	14	14 - Min. 10% of Residential Stalls
Total	17	17 - Min. EV Required
Bicycle Parking:		
Long-Term Covered Garage	134	134 - Min. 100% of Req'd
(98 F.M. & 36 W.M.)		
Short-Term Guest - Surface	16	14 - Min. 10% of Units
Total	150	148 - Min. Bike Stalls Required

- GENERAL NOTES:
- THE APPLICANT SHALL REPLACE ALL SIDEWALK AND CURB AND GUTTER THAT ABUTS THE PROPERTY THAT IS DAMAGED BY THE CONSTRUCTION, OR ANY SIDEWALK AND CURB AND GUTTER WHICH THE CITY ENGINEER DETERMINES NEEDS TO BE REPLACED BECAUSE IT IS NOT AT A DESIRABLE GRADE, REGARDLESS OF WHETHER THE CONDITION EXISTED PRIOR TO BEGINNING CONSTRUCTION.
 - ALL WORK IN THE PUBLIC RIGHT OF WAY SHALL BE PERFORMED BY A CITY-LICENSED CONTRACTOR.
 - ALL DAMAGE TO THE PAVEMENT ON CITY STREETS, AND ADJACENT TO THIS DEVELOPMENT SHALL BE RESTORED IN ACCORDANCE WITH THE CITY OF MADISON'S PAVEMENT PATCHING CRITERIA.
 - ALL PROPOSED STREET TREE REMOVALS WITHIN THE RIGHT OF WAY SHALL BE REVIEWED BY CITY FORESTRY BEFORE THE PLAN COMMISSION MEETING. STREET TREE REMOVALS REQUIRE APPROVAL AND A TREE REMOVAL PERMIT ISSUED BY CITY FORESTRY. ANY STREET TREE REMOVALS REQUESTED AFTER THE DEVELOPMENT PLAN IS APPROVED BY THE PLAN COMMISSION OR THE BOARD OF PUBLIC WORKS AND CITY FORESTRY WILL REQUIRE A MINIMUM OF A 72-HOUR REVIEW PERIOD WHICH SHALL INCLUDE THE NOTIFICATION OF THE ALDERPERSON WITHIN WHO'S DISTRICT IS AFFECTED BY THE STREET TREE REMOVAL(S) PRIOR TO A TREE REMOVAL PERMIT BEING ISSUED.
 - AS DEFINED BY THE SECTION 107.13 OF CITY OF MADISON STANDARD SPECIFICATIONS FOR PUBLIC WORKS CONSTRUCTION: NO EXCAVATION IS PERMITTED WITHIN 5 FEET OF THE TRUNK OF THE STREET TREE OR WHEN CUTTING ROOTS OVER 3 INCHES IN DIAMETER. IF EXCAVATION IS NECESSARY, THE CONTRACTOR SHALL CONTACT MADISON CITY FORESTRY (266-4816) PRIOR TO EXCAVATION. CITY OF MADISON FORESTRY PERSONNEL SHALL ASSESS THE IMPACT TO THE TREE AND TO ITS ROOT SYSTEM PRIOR TO WORK COMMENCING. TREE PROTECTION SPECIFICATIONS CAN BE FOUND ON THE FOLLOWING WEBSITE: CITYOFMADISON.COM/BUSINESS/PW/SPECS.CFM
 - CONTRACTOR SHALL TAKE PRECAUTIONS DURING CONSTRUCTION TO NOT DISFIGURE, SCAR, OR IMPAIR THE HEALTH OF ANY STREET TREE. CONTRACTOR SHALL OPERATE EQUIPMENT IN A MANNER AS TO NOT DAMAGE THE BRANCHES OF THE STREET TREE(S). THIS MAY REQUIRE USING SMALLER EQUIPMENT AND LOADING AND UNLOADING MATERIALS IN A DESIGNATED SPACE AWAY FROM TREES ON THE CONSTRUCTION SITE. ANY DAMAGE OR INJURY TO EXISTING STREET TREES (EITHER ABOVE OR BELOW GROUND) SHALL BE REPORTED IMMEDIATELY TO CITY FORESTRY AT 266-4816. PENALTIES AND REMEDIATION SHALL BE REQUIRED.
 - SECTION 107.13(G) OF CITY OF MADISON STANDARD SPECIFICATIONS FOR PUBLIC WORKS CONSTRUCTION ADDRESSES SOIL COMPACTION NEAR STREET TREES AND SHALL BE FOLLOWED BY CONTRACTOR. THE STORAGE OF PARKED VEHICLES, CONSTRUCTION EQUIPMENT, BUILDING MATERIALS, REFUSE, EXCAVATED SPOILS OR DUMPING OF POISONOUS MATERIALS ON OR AROUND TREES AND ROOTS WITHIN FIVE (5) FEET OF THE TREE OR WITHIN THE PROTECTION ZONE IS PROHIBITED.
 - ON THIS PROJECT, STREET TREE PROTECTION ZONE FENCING IS REQUIRED. THE FENCING SHALL BE ERECTED BEFORE THE DEMOLITION, GRADING OR CONSTRUCTION BEGINS. THE FENCE SHALL INCLUDE THE ENTIRE WIDTH OF TERRACE AND, EXTEND AT LEAST 5 FEET ON BOTH SIDES OF THE OUTSIDE EDGE OF THE TREE TRUNK. DO NOT REMOVE THE FENCING TO ALLOW FOR DELIVERIES OR EQUIPMENT ACCESS THROUGH THE TREE PROTECTION ZONE.
 - STREET TREE PRUNING SHALL BE COORDINATED WITH MADISON FORESTRY AT A MINIMUM OF TWO WEEKS PRIOR TO THE START OF CONSTRUCTION FOR THIS PROJECT. ALL PRUNING SHALL FOLLOW THE AMERICAN NATIONAL STANDARDS INSTITUTE (ANSI) A300 - PART I STANDARDS FOR PRUNING.
 - AT LEAST ONE WEEK PRIOR TO STREET TREE PLANTING, CONTRACTOR SHALL CONTACT CITY FORESTRY AT (608) 266-4816 TO SCHEDULE INSPECTION AND APPROVAL OF NURSERY TREE STOCK AND REVIEW PLANTING SPECIFICATIONS WITH THE LANDSCAPER.
 - APPROVAL OF PLANS FOR THIS PROJECT DOES NOT INCLUDE ANY APPROVAL TO PRUNE, REMOVE, OR PLANT TREES IN THE PUBLIC RIGHT-OF-WAY. PERMISSION FOR SUCH ACTIVITIES MUST BE OBTAINED FROM THE CITY FORESTER (266-4816).
 - THE PUBLIC RIGHT-OF-WAY IS THE SOLE JURISDICTION OF THE CITY OF MADISON AND IS SUBJECT TO CHANGE AT ANY TIME. NO ITEMS SHOWN ON THIS SITE PLAN IN THE RIGHT-OF-WAY ARE PERMANENT AND MAY NEED TO BE REMOVED AT THE APPLICANTS EXPENSE UPON NOTIFICATION BY THE CITY.

BIKE RACKS
INTERIOR & EXTERIOR FLOOR MOUNTED: "INVERTED U" TYPE. MADRAX UX OR SARIS BIKE DOCK

INTERIOR WALL MOUNTED: MADRAX VERTICAL RACK OR SARIS BIKE TRACK





knothe • bruce
ARCHITECTS

Phone: 7601 University Ave., Ste 201
608.836.3690 Middleton, WI 53562

ISSUED
Issued for LUA & UDC Submittals - February 27, 2023


PROJECT TITLE
CASCADE -
THE AMERICAN
CENTER EASTPARK
FIFTH ADDITION

4846 Eastpark Blvd.
Madison, WI
SHEET TITLE
Partial Site Plan -
South

Lot 50
SHEET NUMBER


C-1.3


PROJECT NO. 2155
© Knothe & Bruce Architects, LLC






GENERAL NOTES:

1. THE APPLICANT SHALL REPLACE ALL SIDEWALK AND CURB AND GUTTER THAT ABUTS THE PROPERTY THAT IS DAMAGED BY THE CONSTRUCTION, OR ANY SIDEWALK AND CURB AND GUTTER WHICH THE CITY ENGINEER DETERMINES NEEDS TO BE REPLACED BECAUSE IT IS NOT AT A DESIRABLE GRADE, REGARDLESS OF WHETHER THE CONDITION EXISTED PRIOR TO BEGINNING CONSTRUCTION.
2. ALL WORK IN THE PUBLIC RIGHT OF WAY SHALL BE PERFORMED BY A CITY-LICENSED CONTRACTOR.
3. ALL DAMAGE TO THE PAVEMENT ON CITY STREETS, AND ADJACENT TO THIS DEVELOPMENT SHALL BE RESTORED IN ACCORDANCE WITH THE CITY OF MADISON'S PAVEMENT PATCHING CRITERIA.
4. ALL PROPOSED STREET TREE REMOVALS WITHIN THE RIGHT OF WAY SHALL BE REVIEWED BY CITY FORESTRY BEFORE THE PLAN COMMISSION MEETING. STREET TREE REMOVALS REQUIRE APPROVAL AND A TREE REMOVAL PERMIT ISSUED BY CITY FORESTRY. ANY STREET TREE REMOVALS REQUESTED AFTER THE DEVELOPMENT PLAN IS APPROVED BY THE PLAN COMMISSION OR THE BOARD OF PUBLIC WORKS AND CITY FORESTRY WILL REQUIRE A MINIMUM OF A 72-HOUR REVIEW PERIOD WHICH SHALL INCLUDE THE NOTIFICATION OF THE ALDERPERSON WITHIN WHO'S DISTRICT IS AFFECTED BY THE STREET TREE REMOVAL(S) PRIOR TO A TREE REMOVAL PERMIT BEING ISSUED.
5. AS DEFINED BY THE SECTION 107.13 OF CITY OF MADISON STANDARD SPECIFICATIONS FOR PUBLIC WORKS CONSTRUCTION: NO EXCAVATION IS PERMITTED WITHIN 5 FEET OF THE TRUNK OF THE STREET TREE OR WHEN CUTTING ROOTS OVER 3 INCHES IN DIAMETER. IF EXCAVATION IS NECESSARY, THE CONTRACTOR SHALL CONTACT MADISON CITY FORESTRY (266-4816) PRIOR TO EXCAVATION. CITY OF MADISON FORESTRY PERSONNEL SHALL ASSESS THE IMPACT TO THE TREE AND TO ITS ROOT SYSTEM PRIOR TO WORK COMMENCING. TREE PROTECTION SPECIFICATIONS CAN BE FOUND ON THE FOLLOWING WEBSITE: CITYOFMADISON.COM/BUSINESS/PW/SPECS.CFM
6. CONTRACTOR SHALL TAKE PRECAUTIONS DURING CONSTRUCTION TO NOT DISFIGURE, SCAR, OR IMPAIR THE HEALTH OF ANY STREET TREE. CONTRACTOR SHALL OPERATE EQUIPMENT IN A MANNER AS TO NOT DAMAGE THE BRANCHES OF THE STREET TREES; THIS MAY REQUIRE USING SMALLER EQUIPMENT AND LOADING AND UNLOADING MATERIALS IN A DESIGNATED SPACE AWAY FROM TREES ON THE CONSTRUCTION SITE. ANY DAMAGE OR INJURY TO EXISTING STREET TREES (EITHER ABOVE OR BELOW GROUND) SHALL BE REPORTED IMMEDIATELY TO CITY FORESTRY AT 266-4816. PENALTIES AND REMEDIATION SHALL BE REQUIRED.
7. SECTION 107.13(G) OF CITY OF MADISON STANDARD SPECIFICATIONS FOR PUBLIC WORKS CONSTRUCTION ADDRESSES SOIL COMPACTION NEAR STREET TREES AND SHALL BE FOLLOWED BY CONTRACTOR. THE STORAGE OF PARKED VEHICLES, CONSTRUCTION EQUIPMENT, BUILDING MATERIALS, REFUSE, EXCAVATED SPOILS OR DUMPING OF POISONOUS MATERIALS ON OR AROUND TREES AND ROOTS WITHIN FIVE (5) FEET OF THE TREE OR WITHIN THE PROTECTION ZONE IS PROHIBITED.
8. ON THIS PROJECT, STREET TREE PROTECTION ZONE FENCING IS REQUIRED. THE FENCING SHALL BE ERECTED BEFORE THE DEMOLITION, GRADING OR CONSTRUCTION BEGINS. THE FENCE SHALL INCLUDE THE ENTIRE WIDTH OF TERRACE AND, EXTEND AT LEAST 5 FEET ON BOTH SIDES OF THE OUTSIDE EDGE OF THE TREE TRUNK. DO NOT REMOVE THE FENCING TO ALLOW FOR DELIVERIES OR EQUIPMENT ACCESS THROUGH THE TREE PROTECTION ZONE.
9. STREET TREE PRUNING SHALL BE COORDINATED WITH MADISON FORESTRY AT A MINIMUM OF TWO WEEKS PRIOR TO THE START OF CONSTRUCTION FOR THIS PROJECT. ALL PRUNING SHALL FOLLOW THE AMERICAN NATIONAL STANDARDS INSTITUTE (ANSI) A300 - PART I STANDARDS FOR PRUNING.
10. AT LEAST ONE WEEK PRIOR TO STREET TREE PLANTING, CONTRACTOR SHALL CONTACT CITY FORESTRY AT (608) 266-4816 TO SCHEDULE INSPECTION AND APPROVAL OF NURSERY TREE STOCK AND REVIEW PLANTING SPECIFICATIONS WITH THE LANDSCAPER.
11. APPROVAL OF PLANS FOR THIS PROJECT DOES NOT INCLUDE ANY APPROVAL TO PRUNE, REMOVE, OR PLANT TREES IN THE PUBLIC RIGHT-OF-WAY. PERMISSION FOR SUCH ACTIVITIES MUST BE OBTAINED FROM THE CITY FORESTER (266-4816).
12. THE PUBLIC RIGHT-OF-WAY IS THE SOLE JURISDICTION OF THE CITY OF MADISON AND IS SUBJECT TO CHANGE AT ANY TIME. NO ITEMS SHOWN ON THIS SITE PLAN IN THE RIGHT-OF-WAY ARE PERMANENT AND MAY NEED TO BE REMOVED AT THE APPLICANTS EXPENSE UPON NOTIFICATION BY THE CITY.









**BIKE RACKS**
INTERIOR & EXTERIOR FLOOR MOUNTED: "INVERTED U" TYPE. MADRAX UX OR SARIS BIKE DOCK

**INTERIOR WALL MOUNTED: MADRAX VERTICAL RACK OR SARIS BIKE TRACK**






LIGHT LEVEL STATISTICS						
DESCRIPTION	SYMBOL	AVG.	MAX.	MIN.	MAX. / MIN.	AVG. / MIN.
South-West Parking Lot and Drive Aisle Lighting	+	0.7 fc	6.4 fc	0.2 fc	32.0:1	3.5:1
North-East Parking Lot and Drive Aisle Lighting	+	0.6 fc	6.3 fc	0.2 fc	31.5:1	3.0:1
Parking Garage Entry Security Lighting	+	2.4 fc	5.7 fc	0.5 fc	11.4:1	4.8:1

LUMINAIRE SCHEDULE							
SYMBOL	LABEL	QTY.	MANUF.	CATALOG	DESCRIPTION	FILE	MOUNTING
	A	4	LITHONIA LIGHTING	WPXI LED PI 30K MVOLT	WPXI LED WALLPACK, 1500lm, 3000K COLOR TEMPERATURE, 120-277 VOLTS	WPXI_LED_PI _30K_MVOLT.ies	8'-0" ABOVE GRADE ON BUILDING
	B	1	LITHONIA LIGHTING	DSXWPM LED 10C 350 30K T2S MVOLT HS	DSXWPM LED WITH (1) 10 LED LIGHT ENGINE, TYPE T2S OPTIC, 3000K AT 350mA, WITH HOUSE SIDE SHIELD	DSXWPM_LED_10C _350_30K_T2S _MVOLT_HS.ies	16'-0" POLE ON 2'-0" TALL CONC. BASE
	C	7	LITHONIA LIGHTING	DSXWPM LED 10C 530 30K T2M MVOLT HS	DSXWPM LED WITH (1) 10 LED LIGHT ENGINE, TYPE T2M OPTIC, 3000K AT 530mA, WITH HOUSE SIDE SHIELD	DSXWPM_LED_10C _530_30K_T2M _MVOLT_HS.ies	16'-0" POLE ON 2'-0" TALL CONC. BASE
	D	4	LITHONIA LIGHTING	DSXWPM LED 10C 530 30K T2S MVOLT HS	DSXWPM LED WITH (1) 10 LED LIGHT ENGINE, TYPE T2S OPTIC, 3000K AT 530mA, WITH HOUSE SIDE SHIELD	DSXWPM_LED_10C _530_30K_T2S _MVOLT_HS.ies	16'-0" POLE ON 2'-0" TALL CONC. BASE
	E	8	LITHONIA LIGHTING	DSXWPM LED 10C 530 30K T3S MVOLT HS	DSXWPM LED WITH (1) 10 LED LIGHT ENGINE, TYPE T3S OPTIC, 3000K AT 530mA, WITH HOUSE SIDE SHIELD	DSXWPM_LED_10C _530_30K_T3S _MVOLT_HS.ies	16'-0" POLE ON 2'-0" TALL CONC. BASE
	F	10	LITHONIA LIGHTING	DSXWPM LED 10C 530 30K T3S MVOLT HS	DSXWPM LED WITH (1) 10 LED LIGHT ENGINE, TYPE T3S OPTIC, 3000K AT 530mA, WITH HOUSE SIDE SHIELD	DSXWPM_LED_10C _530_30K_T3S _MVOLT_HS.ies	18'-0" POLE ON FLUSH CONC. BASE
	G	4	LITHONIA LIGHTING	DSXWPM LED 10C 530 30K T4M MVOLT HS	DSXWPM LED WITH (1) 10 LED LIGHT ENGINE, TYPE T4M OPTIC, 3000K AT 530mA, WITH HOUSE SIDE SHIELD	DSXWPM_LED_10C _530_30K_T4M _MVOLT_HS.ies	16'-0" POLE ON 2'-0" TALL CONC. BASE
	H	1	LITHONIA LIGHTING	DSXWPM LED 10C 700 30K T5M MVOLT HS	DSXWPM LED WITH (1) 10 LED LIGHT ENGINE, TYPE T5M OPTIC, 3000K AT 700mA, WITH HOUSE SIDE SHIELD	DSXWPM_LED_10C _700_30K_T5M _MVOLT_HS.ies	16'-0" POLE ON 2'-0" TALL CONC. BASE

EXAMPLE LIGHT FIXTURE DISTRIBUTION



knothe + bruce
ARCHITECTS

Phone: 7601 University Ave, Ste 201
608.836.3690 Middleton, WI 53562

ISSUED
Issued for LUA & UDC Submittals - February 27, 2023

PROJECT TITLE
CASCADE -
THE AMERICAN
CENTER EASTPARK
FIFTH ADDITION


4846 Eastpark Blvd.
Madison, WI
SHEET TITLE
Site Lighting Plan -
South


Lot 50
SHEET NUMBER

C-2.3


PROJECT NO. 2155

© Knothe & Bruce Architects, LLC





LOT COVERAGE		
ZONING	TR-U2	
MAXIMUM LOT COVERAGE	80%	
LOT AREA	74,337 S.F.	
PROPOSED COVERAGE	40,600 S.F. / 53%	



knothe • bruce
ARCHITECTS

Phone: 7601 University Ave, Ste 201
608.836.3690 Middleton, WI 53562



ISSUED
Issued for LUA & UDC Submittals - February 27, 2023


PROJECT TITLE
**CASCADE -
THE AMERICAN
CENTER EASTPARK
FIFTH ADDITION**


4846 Eastpark Blvd.
Madison, WI
SHEET TITLE
Lot Coverage

Lot 49
SHEET NUMBER

C-3.1
PROJECT NO. 2155
© Knothe & Bruce Architects, LLC





LOT COVERAGE		
ZONING	TR-U2	
MAXIMUM LOT COVERAGE	80%	
LOT AREA	134,349 S.F.	
PROPOSED COVERAGE	79,200 S.F. / 59%	



knothe + bruce
ARCHITECTS

Phone: 7601 University Ave, Ste 201
608.836.3690 Middleton, WI 53562


ISSUED
Issued for LUA & UDC Submittals - February 27, 2023


PROJECT TITLE
**CASCADE -
THE AMERICAN
CENTER EASTPARK
FIFTH ADDITION**

4846 Eastpark Blvd.
Madison, WI
SHEET TITLE
**Lot Coverage
North**

Lot 50
SHEET NUMBER

C-3.2
PROJECT NO. **2155**
© Knothe & Bruce Architects, LLC





SEE SHEET C-1.3A FOR LOT COVERAGE DATA

kb2
knothe • bruce
ARCHITECTS
Phone: 7601 University Ave, Ste 201
608.836.3690 Middleton, WI 53562

ISSUED
Issued for LUA & UDC Submittals - February 27, 2023

PROJECT TITLE
**CASCADE -
THE AMERICAN
CENTER EASTPARK
FIFTH ADDITION**

4846 Eastpark Blvd.
Madison, WI
SHEET TITLE
**Lot Coverage
South**



Lot 50
SHEET NUMBER

C-3.3
PROJECT NO. **2155**
© Knothe & Bruce Architects, LLC

CASCADE - PHASE 1 - SITE IMPROVEMENTS

THE AMERICAN CENTER LOTS 49-50

CITY OF MADISON, WISCONSIN




SHEET NO.	DESCRIPTION
C1	TITLE SHEET
C2	NOTES & LEGENDS
C3	EXISTING CONDITIONS
C4	EROSION CONTROL PLAN
C5	PHASE 1 OVERALL SITE & UTILITY PLAN
C6	LOT 49 SITE & UTILITY PLAN
C7	LOT 50 NORTH SITE & UTILITY PLAN
C8	LOT 50 SOUTH SITE & UTILITY PLAN
C9	PHASE 1 OVERALL GRADING PLAN
C10	LOT 49 GRADING PLAN
C11	LOT 50 NORTH GRADING PLAN
C12	LOT 50 SOUTH GRADING PLAN
C13	LOT 49 FIRE ACCESS PLAN



THE LOCATION OF EXISTING UTILITIES, BOTH UNDERGROUND AND OVERHEAD ARE APPROXIMATE ONLY AND HAVE NOT BEEN INDEPENDENTLY VERIFIED BY THE OWNER OR ITS REPRESENTATIVE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR DETERMINING THE EXACT LOCATION OF ALL EXISTING UTILITIES WHETHER SHOWN ON THESE PLANS OR NOT, BEFORE COMMENCING WORK, AND SHALL BE FULLY RESPONSIBLE FOR ANY AND ALL DAMAGES WHICH MIGHT BE CAUSED BY THE CONTRACTOR'S FAILURE TO EXACTLY LOCATE AND PRESERVE ANY AND ALL UTILITIES.

CALL DIGGER'S HOTLINE
1-800-242-8511

SITE BENCHMARKS

- 

TOP NUT OF HYDRANT
ELEV = 910.30
- 

TOP NUT OF HYDRANT
ELEV = 921.17
- 

TOP NUT OF HYDRANT
ELEV = 921.85
- 

TOP NUT OF HYDRANT
ELEV = 910.30

NOT FOR CONSTRUCTION

Title Sheet

Cascade Phase 1 - The American Center Lots 49-50

City of Madison

Dane County, Wisconsin

REVISIONS		REVISIONS	
NO.	DATE	NO.	DATE

DATE

2/27/2023

DRAFTER

BBAR

CHECKED

SCHU

PROJECT NO.

210303

C1

TOPOGRAPHIC LINEWORK LEGEND

FD

EXISTING FIBER OPTIC LINE

G

EXISTING GAS LINE

UE

EXISTING UNDERGROUND ELECTRIC LINE

SAN

EXISTING SANITARY SEWER LINE (SIZE NOTED)

ST

EXISTING STORM SEWER LINE (SIZE NOTED)

EXISTING EDGE OF TREES

WH

EXISTING WATER MAIN (SIZE NOTED)

820

EXISTING MAJOR CONTOUR

818

EXISTING MINOR CONTOUR

EXISTING EDGE OF PAVEMENT

EXISTING EDGE OF GRAVEL

EXISTING GRAVEL SURFACE

EXISTING CONCRETE SURFACE

EXISTING ASPHALT SURFACE

SITE PLAN LEGEND

PROPERTY BOUNDARY

CURB AND GUTTER (REVERSE CURB HATCHED)

PROPOSED CHAIN LINK FENCE

PROPOSED CONCRETE

PROPOSED ASPHALT

PROPOSED SIGN

PROPOSED HANDICAP PARKING

ABBREVIATIONS

TC - TOP OF CURB

FF - FINISHED FLOOR

FL - FLOW LINE

SW - TOP OF WALK

TW - TOP OF WALL

BW - BOTTOM OF WALL

GRADING LEGEND

820

PROPOSED MAJOR CONTOURS

818

PROPOSED MINOR CONTOURS

DITCH CENTERLINE

SILT FENCE

DISTURBED LIMITS

BERM

DRAINAGE DIRECTION

1048.61

EXISTING SPOT ELEVATIONS

1048.61

PROPOSED SPOT ELEVATIONS

STONE WEEPER

VELOCITY CHECK

INLET PROTECTION

EROSION MAT CLASS II, TYPE A

EROSION MAT CLASS I, TYPE B

EROSION MAT CLASS III, TYPE C

EROSION MAT CLASS II, TYPE A

TRACKING PAD

RIP RAP

PROPOSED UTILITY LEGEND

STORM SEWER PIPE

STORM SEWER MANHOLE

STORM SEWER ENDWALL

STORM SEWER CURB INLET

STORM SEWER CURB INLET W/MANHOLE

STORM SEWER FIELD INLET

ROOF DRAIN CLEANOUT

SANITARY SEWER PIPE (GRAVITY)

SANITARY SEWER LATERAL PIPE

SANITARY SEWER MANHOLE

SANITARY SEWER CLEANOUT

WATER MAIN

WATER SERVICE LATERAL PIPE

FIRE HYDRANT

WATER VALVE

CURB STOP

PROPOSED PIPE INSULATION

ABBREVIATIONS

STMH - STORM MANHOLE

FI - FIELD INLET

CI - CURB INLET

CB - CATCH BASIN

EW - ENDWALL

SMH - SANITARY MANHOLE

TOPOGRAPHIC SYMBOL LEGEND

EXISTING SIGN (TYPE NOTED)

EXISTING CURB INLET

EXISTING STORM MANHOLE

EXISTING SANITARY MANHOLE

EXISTING FIRE HYDRANT

EXISTING WATER MAIN VALVE

EXISTING CURB STOP

EXISTING GAS VALVE

EXISTING LIGHT POLE

EXISTING TV PEDESTAL

EXISTING TELEPHONE MANHOLE

EXISTING TELEPHONE PEDESTAL

EXISTING DECIDUOUS TREE

GENERAL NOTES:

1.

THE CONTRACTOR IS RESPONSIBLE FOR ANY DAMAGE CAUSED DURING CONSTRUCTION TO PUBLIC PROPERTY, PRIVATE PROPERTY OR UTILITIES.
2.

THE CONTRACTOR SHALL SUBMIT SHOP DRAWINGS FOR REVIEW BY THE ENGINEER, PRIOR TO PLACING AN ORDER OF ANY SUCH ITEM.
3.

EXISTING TOPOGRAPHIC INFORMATION IS BASED ON FIELD OBSERVATIONS AND/OR PLAN OF RECORD DRAWINGS. CONTRACTOR SHALL VERIFY TOPOGRAPHIC INFORMATION PRIOR TO STARTING CONSTRUCTION.
4.

RIGHT OF WAY (ROW) AND PROPERTY LINES ARE APPROXIMATE. CONTRACTOR SHALL BE RESPONSIBLE FOR PROTECTING EXISTING PROPERTY CORNER MONUMENTATION. ANY MONUMENTS DISTURBED BY CONTRACTOR SHALL BE REPLACED AT THE CONTRACTORS EXPENSE.
5.

CONTRACTOR SHALL COORDINATE WITH DRY UTILITY COMPANY'S REGARDING ANY POTENTIAL CONFLICTS AND COORDINATE RELOCATIONS AS MAY BE REQUIRED. CONTRACTOR SHALL ALSO COORDINATE THE PROPOSED INSTALLATION OF NEW FACILITIES AS REQUIRED.

DEMOLITION NOTES:

1.

CONTRACTOR SHALL KEEP ALL CITY STREETS FREE AND CLEAR OF CONSTRUCTION RELATED DIRT/DUST/DEBRIS.
2.

COORDINATE EXISTING UTILITY REMOVAL/ABANDONMENT WITH LOCAL AUTHORITIES AND UTILITY COMPANIES HAVING JURISDICTION.
3.

ALL SAWCUTTING SHALL BE FULL DEPTH TO PROVIDE A CLEAN EDGE TO MATCH NEW CONSTRUCTION. MATCH EXISTING ELEVATIONS AT POINTS OF CONNECTION FOR NEW AND EXISTING PAVEMENT, CURB, SIDEWALKS, ETC. ALL SAWCUT LOCATIONS SHOWN ARE APPROXIMATE AND MAY BE FIELD ADJUSTED TO ACCOMMODATE CONDITIONS, JOINTS, MATERIAL TYPE, ETC. REMOVE MINIMUM AMOUNT NECESSARY FOR INSTALLATION OF PROPOSED IMPROVEMENTS.
4.

CONTRACTOR SHALL PROVIDE AND SHALL BE RESPONSIBLE FOR ANY NECESSARY TRAFFIC CONTROL SIGNAGE AND SAFETY MEASURES DURING DEMOLITION AND CONSTRUCTION OPERATIONS WITHIN OR NEAR THE PUBLIC ROADWAY.
5.

COORDINATE TREE REMOVAL WITH LANDSCAPE ARCHITECT. ALL TREES TO BE REMOVED SHALL BE REMOVED IN THEIR ENTIRETY AND STUMPS SHALL BE GROUND TO 12" BELOW PROPOSED SUBGRADE.
6.

CONTRACTOR SHALL OBTAIN ANY NECESSARY DEMOLITION AND UTILITY PLUGGING PERMITS.
7.

ANY DAMAGE TO THE CITY PAVEMENT, INCLUDING DAMAGE RESULTING FROM CURB REPLACEMENT, WILL REQUIRE RESTORATION IN ACCORDANCE WITH THE CITY ENGINEERING PATCHING CRITERIA.

SITE PLAN NOTES:

1.

CONCRETE TO BE 5" THICK, CONSTRUCTED ON A BASE OF 4" COMPACTED SAND OR CRUSHED STONE.
2.

CONCRETE FOR DRIVEWAYS AND SIDEWALK AT DRIVEWAY ENTRANCES SHALL BE 7" THICK, CONSTRUCTED ON A BASE OF 5" COMPACTED SAND OR CRUSHED STONE.
3.

ALL DIMENSIONS WITH CURB & GUTTER ARE REFERENCED TO THE FACE OF CURB.
4.

CONTRACTOR SHALL DEEP TILL ANY DISTURBED AREAS AFTER CONSTRUCTION IS COMPLETE AND BEFORE RESTORING.
5.

CONTRACTOR TO OBTAIN ANY NECESSARY DRIVEWAY CONNECTION, RIGHT OF WAY AND EXCAVATION PERMITS PRIOR TO CONSTRUCTION.
6.

ALL ABANDONED DRIVEWAYS ADJACENT TO THE SITE SHALL BE REPLACED WITH CURB AND THE TERRACE SHALL BE RESTORED WITH GRASS.
7.

ANY SIDEWALK AND CURB & GUTTER ABUTTING THE PROPERTY SHALL BE REPLACED IF IT IS DAMAGED DURING CONSTRUCTION.

GRADING NOTES:

1.

CONTOURS ARE SHOWN FOR PURPOSES OF INDICATING ROUGH GRADING. FINAL GRADE SHALL BE ESTABLISHED ON PAVED SURFACES BY USING SPOT GRADES ONLY.
2.

ALL GRADES SHOWN REFERENCE FINISHED ELEVATIONS.
3.

CROSS SLOPE OF SIDEWALKS SHALL BE 2.0% UNLESS OTHERWISE NOTED.
4.

LONGITUDINAL GRADE OF SIDEWALK RAMPS SHALL NOT EXCEED 8.33% (1:12) AND SHALL BE IN ACCORDANCE WITH ADA REQUIREMENTS.
5.

LONGITUDINAL GRADE OF SIDEWALK SHALL NOT EXCEED 5.0% OR THE ADJACENT STREET GRADE WHICHEVER IS GREATER.
6.

ACCESSIBLE ROUTES SHALL BE 5.0% MAX LONGITUDINAL SLOPE AND 1.5% MAX CROSS SLOPE. ACCESSIBLE LOADING AREAS OR LANDINGS SHALL BE 2.0% MAX SLOPE IN ANY DIRECTION. RAMPS SHALL BE 8.33% MAX SLOPE.
7.

NO LAND DISTURBANCE ACTIVITIES SHALL BEGIN UNTIL ALL EROSION CONTROL BMP'S ARE INSTALLED.
8.

SEE DETAIL SHEETS FOR EROSION CONTROL NOTES AND CONSTRUCTION SEQUENCE.

UTILITY NOTES:

1.

CONTRACTOR SHALL OBTAIN ANY NECESSARY WORK IN RIGHT OF WAY, EXCAVATION, UTILITY CONNECTION, PLUGGING AND ABANDONMENT PERMITS PRIOR TO CONSTRUCTION.
2.

CONTRACTOR TO VERIFY EXISTING UTILITY LOCATIONS AND ELEVATIONS PRIOR TO STARTING WORK.
3.

SANITARY & STORM SEWER LENGTHS SHOWN ARE FROM CENTER OF STRUCTURE TO CENTER OF STRUCTURE. STORM SEWER END SECTIONS ARE INCLUDED IN THE LENGTH AND SLOPE OF THE PIPE.
4.

CONTRACTOR SHALL INVESTIGATE ALL UTILITY CROSSINGS PRIOR TO CONSTRUCTION AND NOTIFY ENGINEER OF ANY CONFLICTS.
5.

CONTRACTOR SHALL BE RESPONSIBLE FOR ADJUSTING ALL UTILITY STRUCTURES TO FINISHED GRADE (MANHOLE RIMS, WATER VALVES, AND CURB STOPS), IF NECESSARY.
6.

FOR ALL SEWER AND WATER MAIN CROSSINGS: PROVIDE MINIMUM 18" SEPARATION WHEN WATER MAIN CROSSES BELOW SEWER AND MINIMUM 6" SEPARATION WHEN WATER MAIN CROSSES ABOVE SEWER.
7.

IF DEWATERING OPERATIONS EXCEED 70 GALLONS PER MINUTE OF PUMPING CAPACITY, A DEWATERING WELL PERMIT SHALL BE OBTAINED PRIOR TO STARTING ANY DEWATERING ACTIVITIES.
8.

A COPY OF THE APPROVED UTILITY PLANS, SPECIFICATIONS AND PLUMBING PERMIT APPROVAL LETTER SHALL BE ON-SITE DURING CONSTRUCTION AND OPEN TO INSPECTION BY AUTHORIZED REPRESENTATIVES OF THE DEPARTMENT OF SAFETY AND PROFESSIONAL SERVICES AND OTHER LOCAL INSPECTORS.
9.

PROPOSED UTILITY SERVICE LINES SHOWN ARE APPROXIMATE. COORDINATE THE EXACT LOCATIONS WITH THE PLUMBING DRAWINGS. COORDINATE THE LOCATION WITH THE PLUMBING CONTRACTOR AND/OR OWNER'S CONSTRUCTION REPRESENTATIVE PRIOR TO INSTALLATION OF ANY NEW UTILITIES.
10.

STORM BUILDING SEWER PIPE SHALL CONFORM TO ONE OF THE STANDARDS LISTED IN TABLE 384.30-6 OF SPS 384.30(3)(c).
11.

UNDERGROUND DRAIN AND VENT PIPE/TUBING SHALL CONFORM TO ONE OF THE STANDARDS LISTED IN TABLE 384.30-2 OF SPS 384.30(2).
12.

PRIVATE WATER SERVICES AND PRIVATE WATER MAINS SHALL CONFORM TO ONE OF THE STANDARDS LISTED IN TABLE 384.30-7 OF SPS 384.30(4)(d).
13.

PRIVATE SANITARY SEWER AND LATERALS SHALL BE POLYVINYL CHLORIDE (PVC) ASTM D3034 - SDR 35 OR APPROVED EQUAL MATERIAL THAT CONFORMS TO ONE OF THE STANDARDS LISTED IN TABLE 384.30-3 OF SPS 384.30(2)(c).
14.

A MEANS TO LOCATE BURIED UNDERGROUND EXTERIOR NON METALLIC SEWERS/MAINS AND WATER SERVICES/MAINS MUST BE PROVIDED WITH TRACER WIRE OR OTHER METHODS IN ORDER TO BE LOCATED PER SPS 382.10(11)(h) AND SPS 382.40(8)(k).
15.

EXTERIOR WATER SUPPLY PIPING SETBACKS AND CROSSINGS SHALL BE IN ACCORDANCE WITH SPS 382.40(8)(b.).
16.

NO PERSON MAY ENGAGE IN PLUMBING WORK IN THE STATE UNLESS LICENSED TO DO SO BY THE DEPARTMENT OF SAFETY AND PROFESSIONAL SERVICES PER S.145.06.
17.

SITE CONTRACTOR SHALL LEAVE SANITARY AND WATER LATERALS FIVE (5) FEET SHORT (HORIZONTALLY) FROM THE BUILDING. BUILDING PLUMBER SHALL VERIFY SIZE, LOCATION, AND INVERT ELEVATION OF PROPOSED SANITARY AND WATER LATERALS.
18.

IT IS THE CONTRACTOR'S RESPONSIBILITY TO VERIFY THAT THE EXISTING VALVES WILL HOLD THE PRESSURE TEST PRIOR TO CONNECTION. THE CITY IS NOT RESPONSIBLE FOR ANY COSTS INCURRED DUE TO THE CONTRACTOR NOT VERIFYING THAT THE EXISTING VALVE WILL HOLD THE PRESSURE TEST PRIOR TO CONNECTION. IF A NEW VALVE IS REQUIRED, THE APPLICANT WILL BE REQUIRED TO INSTALL ONE AT THEIR EXPENSE, AT THE POINT OF CONNECTION.
19.

CONTRACTOR TO CHLORINATE AND BACTERIA TEST BEFORE DOMESTIC SUPPLY PURPOSES
20.

CLEAN OUT ALL EXISTING AND PROPOSED STORM INLETS AND CATCH BASINS AT THE COMPLETION OF CONSTRUCTION.
21.

SANITARY SEWER MAIN AT BURY DEPTHS GREATER THAN 15' SHALL BE SDR 21. ALL OTHER SANITARY SEWER MAIN SHALL BE SDR 26.
22.

ALL WATER MAIN AND SERVICES SHALL BE INSTALLED AT A MINIMUM DEPTH OF 6.5' FROM TOP OF FINISHED GRADE ELEVATION TO TOP OF MAIN. PROVIDE 1.5' CLEAR SEPARATION IF WATER CROSSES BELOW SEWER AND MINIMUM 0.5' IF WATER CROSSES ABOVE.
23.

SANITARY MANHOLES WITH SEWER MAIN CONNECTIONS GREATER THAN 2' ABOVE THE LOWEST INVERT SHALL BE CONSTRUCTED WITH AN EXTERNAL DROP. MANHOLES WITH SEWER LATERAL CONNECTIONS GREATER THAT 2' ABOVE THE LOWEST INVERT SHALL BE CONSTRUCTED WITH AN INTERNAL DROP.
24.

INSTALL 1 SHEET OF 4'x8'x4" HIGH DENSITY STYROFOAM INSULATION AT ALL LOCATIONS WHERE STORM SEWER CROSSES WATER MAIN OR WATER LATERALS.

STREET TREE NOTES:

1.

ALL PROPOSED STREET TREE REMOVALS WITHIN THE RIGHT OF WAY SHALL BE REVIEWED BY CITY FORESTRY. STREET TREE REMOVALS REQUIRE APPROVAL AND A TREE REMOVAL PERMIT ISSUED BY CITY FORESTRY.
2.

CONTRACTOR SHALL TAKE PRECAUTIONS DURING CONSTRUCTION TO NOT DISFIGURE, SCAR, OR IMPAIR THE HEALTH OF ANY STREET TREE. CONTRACTOR SHALL OPERATE EQUIPMENT IN A MANNER AS TO NOT DAMAGE THE BRANCHES OF THE STREET TREES. ANY DAMAGE OR INJURY TO EXISTING STREET TREES (EITHER ABOVE OR BELOW GROUND) SHALL BE REPORTED IMMEDIATELY TO CITY FORESTRY.
3.

AS DEFINED BY SECTION 107.13 OF CITY OF MADISON STANDARD SPECIFICATIONS FOR PUBLIC WORKS CONSTRUCTION: NO EXCAVATION IS PERMITTED WITHIN 5 FEET OF THE TRUNK OF THE STREET TREE OR WHEN CUTTING ROOTS OVER 3 INCHES IN DIAMETER. IF EXCAVATION IS NECESSARY, THE CONTRACTOR SHALL CONTACT MADISON CITY FORESTRY PRIOR TO EXCAVATION. CITY OF MADISON FORESTRY PERSONNEL SHALL ASSES THE IMPACT TO THE TREE AND TO ITS ROOT SYSTEM PRIOR TO WORK COMMENCING.
4.

SECTION 107.13(g) OF THE CITY OF MADISON STANDARD SPECIFICATIONS FOR PUBLIC WORKS CONSTRUCTION ADDRESSES SOIL COMPACTION NEAR STREET TREES AND SHALL BE FOLLOWED BY CONTRACTOR. THE STORAGE OF PARKED VEHICLES, CONSTRUCTION EQUIPMENT, BUILDING MATERIALS, REFUSE, EXCAVATED SPOILS, OR DUMPING OF POISONOUS MATERIALS ON OR AROUND TREES AND ROOTS WITHIN 5 FEET OF THE TREE OR WITHIN THE PROTECTION ZONE IS PROHIBITED.
5.

STREET TREE PRUNING SHALL BE COORDINATED WITH CITY FORESTRY AT A MINIMUM OF TWO WEEKS PRIOR TO THE START OF CONSTRUCTION.

NOT FOR CONSTRUCTION

vierbicher

planners | engineers | advisors

Notes & Legends

Cascade Phase 1 - The American Center Lots 49-50

City of Madison

Dane County, Wisconsin

REVISIONS		REVISIONS	
NO.	DATE	NO.	DATE

DATE

2/27/2023

DRAFTER

BBAR


CHECKED

SCHU


PROJECT NO.

210303

c2



EXISTING STORM STRUCTURE TABLE				
NAME	TYPE	RIM/TC	INVERT	DIRECTION
S11	CIN	906.23	901.53	SE
			901.79	NW
S12	STMH	907.63	903.21	NE
			902.89	S
			903.16	NW
S13	CIN	907.57	903.68	SW
S14	CIN	912.70	909.19	SE
			909.24	NW
S15	CIN	919.28	914.88	E
			914.73	SE
			914.93	SW
S16	CIN	918.59	915.39	W
S17	CIN	920.61	917.21	N
S18	CIN	915.63	912.32	S
			912.07	NW
S19	CIN	911.41	907.32	N
			907.37	SE
S20	CIN	901.86	896.83	N
			897.30	E
			897.06	S
S21	CIN	902.02	898.32	W
S22	STMH	890.10	880.45	N
			880.45	E
			883.70	S
			880.40	W
S23	CIN	890.31	880.40	N
			880.40	E
			880.40	W
S24	CIN	890.38	882.20	NE
			881.73	W



EXISTING SANITARY STRUCTURE TABLE				
NAME	TYPE	RIM/TC	INVERT	DIRECTION
S1	SMH	903.36	891.16	SE
			891.03	NW
S2	SMH	905.86	889.66	SE
			889.61	SW
			890.81	NW
			895.64	NW
S3	SMH	909.73	899.71	SE
			899.85	NW
S4	SMH	917.44	907.37	SE
			907.47	NW
S5	SMH	921.62	911.72	SE
			911.76	W
			911.83	NW
S6	SMH	917.90	907.28	N
			907.35	E
S7	SMH	904.37	893.84	N
			893.93	S
S8	SMH	894.48	883.69	N
			883.78	S
S9	SMH	890.05	877.47	N
			876.55	S
			876.47	W

GENERAL NOTES:

- This plan is not intended to be a property survey as defined in Chapter A-E 7 of the Wisconsin Administrative Code. The property lines shown on this plan are based on found monumentation, Certified Survey Map #15829, recorded as Document # 5778376 and subsequent surveys of record.
- This plan is based upon field survey work performed on August 17, 18 and 24, 2022. Any changes in site conditions after August 24, 2022 are not reflected by this plan.
- This plan is referenced to the Wisconsin County Coordinate System-Dane Zone, NAD 83 (2011). Elevations are referenced to NAVD 88 (2012) datum. Field data was obtained using Robotic Total Station and GPS.
- All underground utilities have been located per markings placed on the ground or maps provided by the utilities (owners) and/or their authorized representatives. Markings are per Digger's Hotline ticket #20223311075 and #20223311078. No private locate request was made. Vierbicher does not warrant the locations marked or mapped by others. Sewer and water pipe sizes were obtained from the City of Madison Gtweb site. Some storm sewer pipe sizes were measured during the survey.
- No attempt has been made as a part of this plan to obtain or show data concerning condition, or capacity of any utility or municipal/public service facility. For information regarding these utilities contact the appropriate agencies.
- Surveyor has made no investigation or independent search for easements of record, encumbrances, restrictive covenants, or ownership title evidence, or any other facts that a title search might reveal, except those easements shown on the Creek Crossing At St. Francis plat.

- SURVEY LEGEND**
- BENCHMARK
 - FOUND CHISELED "X"
 - PUBLIC LAND CORNER AS NOTED
 - FOUND NAIL
 - FOUND 1" Ø IRON PIPE
 - FOUND P.K. NAIL
 - FOUND 1 1/4" Ø IRON ROD
 - FOUND 3/4" Ø IRON ROD
 - SET NAIL

- TOPOGRAPHIC SYMBOL LEGEND**
- EXISTING SIGN (TYPE NOTED)
 - EXISTING CURB INLET
 - EXISTING STORM MANHOLE
 - EXISTING SANITARY MANHOLE
 - EXISTING FIRE HYDRANT
 - EXISTING WATER MAIN VALVE
 - EXISTING CURB STOP
 - EXISTING GAS VALVE
 - EXISTING LIGHT POLE
 - EXISTING TV PEDESTAL
 - EXISTING TELEPHONE MANHOLE
 - EXISTING TELEPHONE PEDESTAL
 - EXISTING DECIDUOUS TREE

- TOPOGRAPHIC LINEWORK LEGEND**
- FO FO EXISTING FIBER OPTIC LINE
 - G G EXISTING SILT FENCE
 - G G EXISTING GAS LINE
 - UE UE EXISTING UNDERGROUND ELECTRIC LINE
 - SAN SAN EXISTING SANITARY SEWER LINE (SIZE NOTED)
 - ST ST EXISTING STORM SEWER LINE (SIZE NOTED)
 - WH WH EXISTING WATER MAIN (SIZE NOTED)
 - 930 EXISTING MAJOR CONTOUR
 - 928 EXISTING MINOR CONTOUR
 - EXISTING EDGE OF PAVEMENT
 - EXISTING EDGE OF GRAVEL
 - EXISTING GRAVEL SURFACE
 - EXISTING CONCRETE SURFACE
 - EXISTING ASPHALT SURFACE

vierbicher
planners | engineers | advisors

Existing Conditions

Cascade Phase 1 - The American Center Lots 49-50

City of Madison

Dane County, Wisconsin

REVISIONS		REVISIONS	
NO.	DATE	NO.	DATE

DATE

2/27/2023

DRAFTER

BBAR


CHECKED


SCHU

PROJECT NO.

210303

C3





vierbicher
planners | engineers | advisors

Erosion Control Plan

Cascade Phase 1 - The American Center Lots 49-50
City of Madison
Dane County, Wisconsin

REVISIONS		REVISIONS	
NO.	DATE	NO.	DATE



DATE
2/27/2023

DRAFTER
BBAR

CHECKED
SCHU

PROJECT NO.
210303

C4



FINAL DESIGN FOR REGIONAL STORMWATER BASINS AND OUTLOT 21 COMPLETED BY CITY OF MADISON. ALL IMPROVEMENTS WITHIN PUBLIC PARCELS SHALL BE CONSTRUCTED PER THE CITY ISSUED CONSTRUCTION PLANS.


ALL WORK WITHIN LUMINOUS LANE, EASTPARK BLVD., AND DREAMER DRIVE RIGHT OF WAY AND ALL PUBLIC IMPROVEMENTS SHALL BE COMPLETED PER THE CITY OF MADISON ISSUED PLANS.

IMPROVEMENTS SOUTH OF DREAMER DRIVE ARE PART OF PHASE 2 CONSTRUCTION AND WILL BE INCLUDED IN A FUTURE SUBMITTAL

40' X 80' PUBLIC STORMWATER EASEMENT (THE AMERICAN CENTER PLAT EASTPARK FOURTH ADDITION)

25' STORMWATER EASEMENT (THE AMERICAN CENTER PLAT EASTPARK FOURTH ADDITION)

NOT FOR CONSTRUCTION



vierbicher
planners | engineers | advisors

Phase 1 Overall Site & Utility Plan

Cascade Phase 1 - The American Center Lots 49-50

City of Madison

Dane County, Wisconsin

REVISIONS		REVISIONS	
NO.	DATE	NO.	DATE

DATE
2/27/2023


DRAFTER
BBAR

CHECKED
SCHU

PROJECT NO.
210303


C5

FINAL DESIGN FOR REGIONAL STORMWATER BASINS AND OUTLOT 21 COMPLETED BY CITY OF MADISON. ALL IMPROVEMENTS WITHIN PUBLIC PARCELS SHALL BE CONSTRUCTED PER THE CITY ISSUED CONSTRUCTION PLANS.



STORM STRUCTURE TABLE				
STRUCTURE NAME	STRUCTURE TYPE	RIM/TC	INVERT	
S6	48" CONC CB	909.09	902.43	
S7	2' x 3' CI	908.97	905.05	
S8	48" CONC CB	912.42	907.60	
S9	48" CONC CB	915.27	911.27	
S10	2' x 3' CI	918.77	914.77	
S11	48" CONC FI	919.50	916.50	
S15	48" CONC FI	929.00	926.00	
S16	48" CONC STMH	927.06	923.18	
S17	48" CONC STMH	918.67	909.81	
S18	48" CONC FI	918.50	916.00	
S19	48" CONC STMH	920.66	918.70	
S20	48" CONC STMH	930.58	928.68	
S21	2' x 3' CI	922.88	919.29	
S26	18" EW	898.71	897.00	
S28	12" RCP EW	920.17	919.00	
S29	12" RCP EW	929.67	928.50	
S31	12" RCP EW	919.67	918.50	

STORM PIPE TABLE									
PIPE NAME	PIPE TYPE	SIZE (IN.)	FROM	TO	LENGTH (FT)	START INV	END INV	SLOPE	
P1	RCP	18	S26	S6	45	897.00	902.43	12.16%	
P2	RCP	12	S6	S7	6	904.93	905.05	2.00%	
P3	RCP	15	S8	S9	88	907.60	911.27	4.19%	
P4	RCP	12	S9	S10	81	911.27	914.77	4.32%	
P5	RCP	12	S10	S11	79	914.77	916.50	2.18%	
P10	RCP	12	S381	S17	47	909.34	909.81	1.00%	
P11	RCP	12	S17	S16	169	909.81	923.18	7.92%	
P12	RCP	12	S16	S14	85	923.18	926.00	3.32%	
P13	RCP	12	S16	S15	70	923.18	926.00	4.00%	
P14	RCP	12	S17	S18	90	909.81	916.00	6.91%	
P17	RCP	12	S29	S20	18	928.50	928.68	1.00%	
P18	RCP	12	S20		6	928.68	928.74	1.00%	
P21	RCP	15	S6	S8	112	902.68	907.60	4.39%	
P22	RCP	12	S28	S21	29	919.00	919.29	1.00%	
P23	RCP	12	S21	S12	116	919.29	922.50	2.77%	
P26	RCP	12	S31	S19	20	918.50	918.70	1.00%	
P27	RCP	12	S19		6	918.70	918.76	1.00%	



ALL WORK WITHIN THE LUMINOUS LANE RIGHT OF WAY AND ALL PUBLIC IMPROVEMENTS SHALL BE COMPLETED PER THE CITY OF MADISON ISSUED PLANS.

NOT FOR CONSTRUCTION



vierbicher
planners | engineers | advisors

Lot 49 Site & Utility Plan
Cascade Phase 1 - The American Center Lots 49-50
City of Madison
Dane County, Wisconsin

REVISIONS		REVISIONS	
NO.	DATE	NO.	DATE

DATE
2/27/2023

DRAFTER
BBAR


CHECKED
SCHU


PROJECT NO.
210303

C6

STORM PIPE TABLE								
PIPE NAME	PIPE TYPE	SIZE (IN.)	FROM	TO	LENGTH (FT)	START INV	END INV	SLOPE
P4	RCP	12	S9	S10	81	911.27	914.77	4.32%
P5	RCP	12	S10	S11	79	914.77	916.50	2.18%
P6	RCP	12	S27	S22	16	925.40	925.48	0.50%
P7	RCP	12	S22	S23	81	925.48	925.88	0.50%
P8	RCP	12	S23	S24	176	925.88	926.76	0.50%
P10	RCP	12	S381	S17	47	909.34	909.81	1.00%
P11	RCP	12	S17	S16	169	909.81	923.18	7.92%
P12	RCP	12	S16	S14	85	923.18	926.00	3.32%
P13	RCP	12	S16	S15	70	923.18	926.00	4.00%
P14	RCP	12	S17	S18	90	909.81	916.00	6.91%
P17	RCP	12	S29	S20	18	928.50	928.68	1.00%
P18	RCP	12	S20		6	928.68	928.74	1.00%

STORM STRUCTURE TABLE				
STRUCTURE NAME	STRUCTURE TYPE	RIM/TC	INVERT	
S9	48" CONC CB	915.27	911.27	
S10	2' x 3' CI	918.77	914.77	
S11	48" CONC FI	919.50	916.50	
S12	48" CONC FI	926.50	922.50	
S13	48" CONC STMH	930.92	928.68	
S14	48" CONC FI	929.00	926.00	
S15	48" CONC FI	929.00	926.00	
S16	48" CONC STMH	927.06	923.18	
S17	48" CONC STMH	918.67	909.81	
S18	48" CONC FI	918.50	916.00	
S19	48" CONC STMH	920.66	918.70	
S20	48" CONC STMH	930.58	928.68	
S21	2' x 3' CI	922.88	919.29	
S22	2' x 3' CI	929.75	925.48	
S23	2' x 3' CI	930.38	925.88	
S24	2' x 3' CI	931.33	926.76	
S25	2' x 3' CI	930.17	927.43	
S27	12" RCP EW	926.57	925.40	
S28	12" RCP EW	920.17	919.00	
S29	12" RCP EW	929.67	928.50	
S30	12" RCP EW	929.67	928.50	
S31	12" RCP EW	919.67	918.50	





vierbicher

planners engineers advisors

Lot 50 North Site & Utility Plan

Cascade Phase 1 - The American Center Lots 49-50

City of Madison

Dane County, Wisconsin

REVISIONS		REVISIONS	
NO.	DATE	NO.	DATE

DATE

2/27/2023

DRAFTER

BBAR



CHECKED

SCHU

PROJECT NO.

210303

C7



STORM STRUCTURE TABLE				
STRUCTURE NAME	STRUCTURE TYPE	RIM/TC	INVERT	
S9	48" CONC CB	915.27	911.27	
S10	2' x 3' CI	918.77	914.77	
S11	48" CONC FI	919.50	916.50	
S12	48" CONC FI	926.50	922.50	
S13	48" CONC STMH	930.92	928.68	
S14	48" CONC FI	929.00	926.00	
S15	48" CONC FI	929.00	926.00	
S16	48" CONC STMH	927.06	923.18	
S17	48" CONC STMH	918.67	909.81	
S18	48" CONC FI	918.50	916.00	
S19	48" CONC STMH	920.66	918.70	
S20	48" CONC STMH	930.58	928.68	
S21	2' x 3' CI	922.88	919.29	
S22	2' x 3' CI	929.75	925.48	
S23	2' x 3' CI	930.38	925.88	
S24	2' x 3' CI	931.33	926.76	
S25	2' x 3' CI	930.17	927.43	
S27	12" RCP EW	926.57	925.40	
S28	12" RCP EW	920.17	919.00	
S29	12" RCP EW	929.67	928.50	
S30	12" RCP EW	929.67	928.50	
S31	12" RCP EW	919.67	918.50	

STORM PIPE TABLE									
PIPE NAME	PIPE TYPE	SIZE (IN.)	FROM	TO	LENGTH (FT)	START INV	END INV	SLOPE	
P4	RCP	12	S9	S10	81	911.27	914.77	4.32%	
P5	RCP	12	S10	S11	79	914.77	916.50	2.18%	
P6	RCP	12	S27	S22	16	925.40	925.48	0.50%	
P7	RCP	12	S22	S23	81	925.48	925.88	0.50%	
P8	RCP	12	S23	S24	176	925.88	926.76	0.50%	
P10	RCP	12	S381	S17	47	909.34	909.81	1.00%	
P11	RCP	12	S17	S16	169	909.81	923.18	7.92%	
P12	RCP	12	S16	S14	85	923.18	926.00	3.32%	
P13	RCP	12	S16	S15	70	923.18	926.00	4.00%	
P14	RCP	12	S17	S18	90	909.81	916.00	6.91%	
P17	RCP	12	S29	S20	18	928.50	928.68	1.00%	
P18	RCP	12	S20		6	928.68	928.74	1.00%	

ALL WORK WITHIN THE DREAMER DRIVE RIGHT OF WAY AND ALL PUBLIC IMPROVEMENTS SHALL BE COMPLETED PER THE CITY OF MADISON ISSUED PLANS.

IMPROVEMENTS SOUTH OF DREAMER DRIVE ARE PART OF PHASE 2 CONSTRUCTION AND WILL BE INCLUDED IN A FUTURE SUBMITTAL

NOT FOR CONSTRUCTION

vierbicher
planners | engineers | advisors

Lot 50 South Site & Utility Plan

Cascade Phase 1 - The American Center Lots 49-50

City of Madison

Dane County, Wisconsin

REVISIONS		REVISIONS	
NO.	DATE	NO.	DATE



DATE: 2/27/2023

DRAFTER: BBAR

CHECKED: SCHU

PROJECT NO.: 210303


C8



FINAL DESIGN FOR REGIONAL STORMWATER BASINS AND OUTLOT 21 COMPLETED BY CITY OF MADISON. ALL IMPROVEMENTS WITHIN PUBLIC PARCELS SHALL BE CONSTRUCTED PER THE CITY ISSUED CONSTRUCTION PLANS.

ALL WORK WITHIN LUMINOUS LANE, EASTPARK BLVD., AND DREAMER DRIVE RIGHT OF WAY AND ALL PUBLIC IMPROVEMENTS SHALL BE COMPLETED PER THE CITY OF MADISON ISSUED PLANS.

NOT FOR CONSTRUCTION



vierbichter
planners | engineers | advisors

Phase 1 Overall Grading Plan
Cascade Phase 1 - The American Center Lots 49-50
City of Madison
Dane County, Wisconsin

REVISIONS		REVISIONS	
NO.	DATE	NO.	DATE



DATE
2/27/2023



DRAFTER
BBAR


CHECKED
SCHU

PROJECT NO.
210303

C9









vierbicher
planners | engineers | advisors

Lot 50 South Grading Plan

Cascade Phase 1 - The American Center Lots 49-50

City of Madison

Dane County, Wisconsin

REVISIONS		REVISIONS	
NO.	DATE	NO.	DATE

DATE

2/27/2023

DRAFTER

BBAR



CHECKED

SCHU




PROJECT NO.

210303

C12




- FIRE ACCESS LEGEND**
- HOSE LAY FROM FIRE LANE
 - HOSE LAY FROM HYDRANT
 - PROPOSED 20' FIRE LANE
 - PROPOSED 26' AERIAL ACCESS FIRE LANE
 - EXISTING WATER MAIN
 - EXISTING FIRE HYDRANT
 - EXISTING FIRE DEPARTMENT CONNECTION
 - WATER MAIN
 - FIRE HYDRANT
 - FIRE DEPARTMENT CONNECTION
 - FIRE LANE NO PARKING SIGN (12"x18") LOCATION(S) TO BE DETERMINED BY FIRE DEPARTMENT OR MUNICIPALITY



1
1
LADDER REACH DIAGRAMS

NOT FOR CONSTRUCTION



PARK AND STREET TREE PLANT LIST						
KEY	SCIENTIFIC NAME	COMMON NAME	QTY	SIZE	ROOT	STEM
DECIDUOUS TREES						
AF	<i>Acer x freemanii 'Jeffersred'</i>	Autumn Blaze Maple	3	2"	B&B	
CO	<i>Celtis occidentalis</i>	Common Hackberry	5	2"	B&B	
GB	<i>Ginkgo biloba</i>	Autumn Gold Ginkgo	4	2"	B&B	
GD	<i>Gymnocladus dioica 'Espresso-JFS'</i>	Espresso Kentucky Coffee Tree	6	2"	B&B	
GT	<i>Gleditsia triacanthos var. inermis 'Skyline'</i>	Skyline Honeylocust	12	2"	B&B	
QB	<i>Quercus bicolor</i>	Swamp White Oak	9	2"	B&B	
TA	<i>Tilia americana 'McKsentry'</i>	American Sentry Linden	3	2"	B&B	
UD	<i>Ulmus davidiana var. japonica x ulmus pumila</i>	New Horizon Elm	7	2"	B&B	
ORNAMENTAL TREES						
CC	<i>Crataegus crus-galli var. inermis</i>	Thornless Cockspur Hawthorn	5	2"	B&B	
MJ	<i>Malus 'Jewelcole'</i>	Red Jewel Crabapple	7	2"	B&B	
MR	<i>Malus 'JFS-KWS'</i>	Royal Raindrops Crabapple	6	2"	B&B	
EVERGREEN TREES						
PS	<i>Pinus strobus</i>	Eastern White Pine	24	6"	B&B	

- SM Decorative Stone Mulch.
1.5" Capitol Sand & Gravel washed stone over weed barrier fabric with Dimex EdgePro polyvinyl (black plastic) edging
- WM Brown Dyed Wood Mulch with Dimex EdgePro polyvinyl (black plastic) edging
- SOD Premium Kentucky Bluegrass sod
- SEED Premium sunny grass seed blend with straw mat.
(Class 1 Type B single net)
- LANDSCAPE NOTES:
- Please refer to Grading & Erosion Control Plan for final contour information.
 - See CIVIL PLANS for Stormwater Basin details.
 - Individual tree and shrub groupings in lawn areas to receive wood mulch rings with trench edge.
 - Add street trees per the direction of the City Forester, as required.



3570 Pioneer Road
Verona, WI 53593
PH: (608) 827-9401
FAX: (608) 827-9402
WEB: www.olsontoon.com


THE AMERICAN CENTER FIFTH ADDITION
OVERALL LANDSCAPE PLAN
Madison, Wisconsin

Date: January 6, 2023
Scale: 1"=40'-0"
Designer: kms
Job #

Seal:
To protect against legal liability,
the plans presented herein are
"schematic," and should not be
outsourced as "biddable" or
"construction documents" unless
approved by the Landscape
Designer. This is not an original
document unless stamped in
red, as ORIGINAL.

Revisions:
2023.01.26
2023.02.17
2023.02.24

Reference Name:
Cascade Development



SHEET NUMBER

L 100

LOT 49
PLANT LIST

KEY	SCIENTIFIC NAME	COMMON NAME	QTY	SIZE	ROOT	STEM
DECIDUOUS TREES						
AF	<i>Acer x freemanii 'Jefersred'</i>	Autumn Blaze Maple	4	2"	B&B	
GB	<i>Ginkgo biloba</i>	Autumn Gold Ginkgo	3	2"	B&B	
GT	<i>Gleditsia triacanthos var. inermis 'Skyline'</i>	Skyline Honeylocust	2	2"	B&B	
QB	<i>Quercus bicolor</i>	Swamp White Oak	2	2"	B&B	
TA	<i>Tilia americana 'McK Sentry'</i>	American Sentry Linden	7	2"	B&B	
ORNAMENTAL TREES						
SR	<i>Syringa reticulata 'Ivory Silk'</i>	Ivory Silk Japanese Tree Lilac	10	2"	B&B	
EVERGREEN TREES						
PG	<i>Picea glauca var. densata</i>	Black Hills Spruce	5	6'	B&B	
TO	<i>Thuja occidentalis 'Emerald Green'</i>	Emerald Green Arborvitae	5	6'	B&B	
EVERGREEN SHRUBS						
Pp	<i>Picea pungens 'Globosa'</i>	Dwarf Globe Blue Spruce	1	#5	Cont.	
Tm	<i>Taxus x media 'Tautoni'</i>	Taunton Yew	11	#5	Cont.	

DECIDUOUS SHRUBS						
Cc	<i>Cotinus coggygria 'NCC01'</i>	Winecraft Black Smokebush	2	#5	Cont.	
Dk	<i>Diervilla 'GZX885411'</i>	Kodiak Red Bush Honeysuckle	13	#3	Cont.	
Hp	<i>Hydrangea paniculata 'SMHPLQ'</i>	Little Quickfire Hydrangea	10	#3	Cont.	
Iv	<i>Itea virginica 'Sprich'</i>	Little Henry Dwarf Virginia Sweetspire	12	#3	Cont.	
Po	<i>Physocarpus opulifolius 'SMPOTW'</i>	Tiny Wine Ninebark	21	#3	Cont.	
Rr	<i>Rosa 'BAlset'</i>	Sunrise Sunset Rose	10	#3	Cont.	
St	<i>Spiraea betulifolia 'Tor'</i>	Tor Birchleaf Spirea	27	#3	Cont.	
Vd	<i>Viburnum dentatum 'Christom'</i>	Blue Muffin Arrowwood Viburnum	3	#5	Cont.	
ORNAMENTAL GRASSES & PERENNIALS						
ca	<i>Calamagrostis x acutiflora 'Karl Foerster'</i>	Karl Foerster Feather Reed Grass	9	#1	Cont.	
hb	<i>Hemerocallis 'Going Bananas'</i>	Going Bananas Daylily	21	#1	Cont.	
hs	<i>Hosta 'Rainbow's End'</i>	Rainbow's End Hosta	10	#1	Cont.	
hr	<i>Hemerocallis 'Rosy Returns'</i>	Rosy Returns Daylily	9	#1	Cont.	
hw	<i>Heuchera 'Wildberry'</i>	Dolce Wildberry Coralbell	12	#1	Cont.	
pa	<i>Perovskia atriplicifolia 'Little Spire'</i>	Little Spire Russian Sage	3	#1	Cont.	

- SM


Decorative Stone Mulch
1.5" Capitol Sand & Gravel washed stone over weed barrier fabric with Dimex EdgePro polyvinyl (black plastic) edging
- WM

Brown Dyed Wood Mulch with Dimex EdgePro polyvinyl (black plastic) edging
- SOD


Premium Kentucky Bluegrass sod
- SEED

Premium sunny grass seed blend with straw mat.
(Class 1 Type B single net)

- LANDSCAPE NOTES:
- Please refer to Grading & Erosion Control Plan for final contour information.
 - See CIVIL PLANS for Stormwater Basin details
 - Individual tree and shrub groupings in lawn areas to receive wood mulch rings with trench edge.
 - Add street trees per the direction of the City Forester, as required.



City of Madison, WI Landscape Worksheet			Lot 49		
Zoning District Category					
1/6/2023					
City of Madison, Wisconsin Landscape Worksheet					
DEVELOPED LOTS		SQUARE FEET		LANDSCAPE POINTS REQ.	
Total Developed Area				923	
74,312 sf (lot) - 18,924 (building footprint)		55,388			
		CREDITS / EXISTING LANDSCAPING		NEW / PROPOSED LANDSCAPING	
PLANT TYPE / ELEMENT	POINT VALUE	QUANTITY	POINTS ACHIEVED	QUANTITY	POINTS ACHIEVED
Overstory Deciduous	35		0	12	420
Tall Evergreen Tree	35		0	5	175
Ornamental Tree	15		0	10	150
Upright Evergreen Shrub (i.e. arborvitae)	10		0	5	50
Shrub, deciduous	3		0	98	294
Shrub, evergreen	4		0	12	48
Ornamental Grasses/Perennials	2		0	64	128
Ornamental/Decorative Fencing or Wall (4pts / 10LF)	4		0		0
Existing Significant Specimen Tree	14		0		0
Landscape Furniture for public seating and/or transit connections	5		0		0
			0		1265
			TOTAL POINTS ACHIEVED		1265



3570 Pioneer Road
Verona, WI 53593
PH: (608) 827-9401
FAX: (608) 827-9402
WEB: www.olsontoon.com

THE AMERICAN CENTER FIFTH ADDITION

LOT 49 LANDSCAPE PLAN


Madison, Wisconsin

Date: January 6, 2023
Scale: 1/16"=1'-0"
Designer: kms
Job #

Seal:
To protect against legal liability,
the plans presented herein are
"schematic," and should not be
outsourced as "biddable" or
"construction documents" unless
approved by the Landscape
Designer. This is not an original
document unless stamped in
red, as ORIGINAL.

Revisions:
2023.01.26
2023.02.17
2023.02.24

Reference Name:
Cascade Development



LOT 50
67 UNITS


City of Madison, WI Landscape Worksheet					Lot 50	
Zoning District Category						
1/6/2023						
City of Madison, Wisconsin Landscape Worksheet						
DEVELOPED LOTS					LANDSCAPE POINTS REQ.	
Total Developed Area			SQUARE FEET		1568	
134,789 sf (lot) - 40,694 (building footprint)			94,095			
			CREDITS / EXISTING LANDSCAPING		NEW / PROPOSED LANDSCAPING	
PLANT TYPE / ELEMENT	POINT VALUE	QUANTITY	POINTS ACHIEVED	QUANTITY	POINTS ACHIEVED	
Overstory Deciduous	35		0	25	875	
Tall Evergreen Tree	35		0	2	70	
Ornamental Tree	15		0	22	330	
Upright Evergreen Shrub (i.e. arborvitae)	10		0	24	240	
Shrub, deciduous	3		0	182	546	
Shrub, evergreen	4		0	23	92	
Ornamental Grasses/Perennials	2		0	229	458	
Ornamental/Decorative Fencing or Wall (4pts / 10LF)	4		0		0	
Existing Significant Specimen Tree	14		0		0	
Landscape Furniture for public seating and/or transit connections	5		0		0	
			0		2611	
				TOTAL POINTS ACHIEVED		2611

LOT 50
PLANT LIST

KEY	SCIENTIFIC NAME	COMMON NAME	QTY	SIZE	ROOT	STEM
DECIDUOUS TREES						
AF	<i>Acer x freemanii</i> 'Jefersred'	Autumn Blaze Maple	8	2"	B&B	
GB	<i>Ginkgo biloba</i>	Autumn Gold Ginkgo	1	2"	B&B	
GT	<i>Gleditsia triacanthos</i> var. <i>inermis</i> 'Skyline'	Skyline Honeylocust	11	2"	B&B	
TA	<i>Tilia americana</i> 'McK Sentry'	American Sentry Linden	5	2"	B&B	
ORNAMENTAL TREES						
MJ	<i>Malus</i> 'Jewelcole'	Red Jewel Crabapple	12	2"	B&B	
SR	<i>Syringa reticulata</i> 'Ivory Silk'	Ivory Silk Japanese Tree Lilac	10	2"	B&B	
EVERGREEN TREES						
PG	<i>Picea glauca</i> var. <i>densata</i>	Black Hills Spruce	2	6'	B&B	
TO	<i>Thuja occidentalis</i> 'Smagrad'	Emerald Green Arborvitae	3	6'	B&B	
TT	<i>Thuja occidentalis</i> 'Techny'	Techny Arborvitae	21	6'	B&B	
EVERGREEN SHRUBS						
Pp	<i>Picea pungens</i> 'Globose'	Dwarf Globe Blue Spruce	7	#5	Cont.	
Tm	<i>Taxus x media</i> 'Tautoni'	Taunton Yew	16	#5	Cont.	
DECIDUOUS SHRUBS						
Am	<i>Aronia melanocarpa</i> 'Morton'	Iroquois Beauty Chokeberry	12	#3	Cont.	
Cc	<i>Cotinus coggygria</i> 'NCC01'	Winecraft Black Smokebush	1	#5	Cont.	
Cs	<i>Cornus alba</i> 'Bailhalo'	Ivory Halo Red Twig Dogwood	2	#5	Cont.	
Dk	<i>Diervilla</i> 'G2X88541'	Kodiak Red Bush Honeysuckle	11	#3	Cont.	
Hp	<i>Hydrangea paniculata</i> 'SMHPLQF'	Little Quickfire Hydrangea	30	#3	Cont.	
Iv	<i>Itea virginica</i> 'Sprich'	Little Henry Dwarf Virginia Sweetspire	25	#3	Cont.	
Pa	<i>Physocarpus opulifolius</i> 'Jefam'	Amber Jubilee Ninebark	1	#3	Cont.	
Po	<i>Physocarpus opulifolius</i> 'SMPOTW'	Tiny Wine Ninebark	29	#3	Cont.	
Rr	<i>Rosa</i> 'Balsel'	Sunrise Sunset Rose	14	#3	Cont.	
Sb	<i>Syringa</i> 'SMS/BP7'	Blooming Dark Purple Lilac	5	#5	Cont.	
St	<i>Spiraea betulifolia</i> 'Tor'	Tor Birchleaf Spirea	50	#3	Cont.	
Vd	<i>Viburnum dentatum</i> 'Christom'	Blue Muffin Arrowwood Viburnum	2	#5	Cont.	
ORNAMENTAL GRASSES & PERENNIALS						
ca	<i>Calamagrostis x acutiflora</i> 'Karl Foerster'	Karl Foerster Feather Reed Grass	97	#1	Cont.	
hb	<i>Hemerocallis</i> 'Going Bananas'	Going Bananas Daylily	35	#1	Cont.	
hs	<i>Hosta</i> 'Rainbow's End'	Rainbow's End Hosta	20	#1	Cont.	
hr	<i>Hemerocallis</i> 'Rosy Returns'	Rosy Returns Daylily	12	#1	Cont.	
pa	<i>Perovskia atriplicifolia</i> 'Little Spire'	Little Spire Russian Sage	29	#1	Cont.	
rf	<i>Rudbeckia x</i> 'American Gold Rush'	Am. Gold Rush Black-eyed Susan	36	#1	Cont.	


- △ SM Decorative Stone Mulch
1.5" Capitol Sand & Gravel washed stone over weed barrier fabric with Dimex EdgePro polyvinyl (black plastic) edging
- △ WM Brown Dyed Wood Mulch with Dimex EdgePro polyvinyl (black plastic) edging
- SOD Premium Kentucky Bluegrass sod
- SEED Premium sunny grass seed blend with straw mat.
(Class 1 Type B single net)

- LANDSCAPE NOTES:
- Please refer to Grading & Erosion Control Plan for final contour information.
 - See CIVIL PLANS for Stormwater Basin details
 - Individual tree and shrub groupings in lawn areas to receive wood mulch rings with trench edge.
 - Add street trees per the direction of the City Forester, as required.



SHEET NUMBER

L 104



3570 Pioneer Road
Verona, WI 53593
PH: (608) 827-9401
FAX: (608) 827-9402
WEB: www.olsontoon.com



THE AMERICAN CENTER FIFTH ADDITION
LOT 50 LANDSCAPE PLAN
Madison, Wisconsin

Date: January 6, 2023
Scale: 1/16"=1'-0"
Designer: kms
Job #

Seal:
To protect against legal liability,
the plans presented herein are
"schematic," and should not be
outsourced as "biddable" or
"construction documents" unless
approved by the Landscape
Designer. This is not an original
document unless stamped in
red, as ORIGINAL.

Revisions:
2023.01.26
2023.02.17
2023.02.24

Reference Name:
Cascade Development



3570 Pioneer Road
Verona, WI 53593
PH: (608) 827-9401
FAX: (608) 827-9402
WEB: www.olsontoon.com

THE AMERICAN CENTER FIFTH ADDITION

LOT 50 LANDSCAPE PLAN

Madison, Wisconsin

Date: January 6, 2023
Scale: 1/16"=1'-0"
Designer: kms
Job #

Seal:
To protect against legal liability,
the plans presented herein are
"schematic," and should not be
outsourced as "biddable" or
"construction documents" unless
approved by the Landscape
Designer. This is not an original
document unless stamped in
red, as ORIGINAL.

Revisions:
2023.01.26
2023.02.17
2023.02.24

Reference Name:
Cascade Development

SHEET NUMBER

L 105