Project Name: Kendall Avenue, Chestnut Street and Walnut Street Reconstruction Assessment District - 2008

Project Engineer Jim Wolfe 266,4099

Project Limits Kendall Avenue

Chestnut Street Walnut Street

from Highland Ave. to N. Allen St. from Chamberlain Ave. to University Ave from Chamberlain Ave. to Kendall Ave.

22 ft (Kendall), 24 ft (Chestnut & Walnut)

Asphaltic

Asphaltic

2007

Street **Existing Proposed** Project Type Reconstruction

Last Surfaced 1975 (Kendall), 1977(Chestnut), 1985 (Walnut)

Pavement Rating 5 (Kendall), 4 (Chestnut & Walnut) Curb Rating 4 (Kendall, Chestnut, Walnut)

Width 22 ft (Kendall), 24 ft (Chestnut & Walnut)

Surface Type (Kendall & Chestnut) Asphalt over concrete

Surface Type (Walnut) Asphalt

Sidewalk **Existing Proposed**

Work Required Replace As Necessary

Storm Sewer Existing **Proposed** Work Required Replace Deteriorated Sections

10 Year Design Storm Size 15-24 inches 24-36 inches

Material VC Concrete Year 1922-1924 2007

Sanitary Sewer Proposed Existing

Work Required Complete Replacement Size 6 Inch (Substandard), 8 Inch (Chestnut only) 8 Inch **PVC** Material VC

Water Main Existing Proposed

1917-1922

Work Required Complete Replacement Size 6-8 Inch 6-8 Inch Material Cast Iron Ductile Iron Year 1921-1925 2007

Parking Existing Proposed Parking Conditions Parking One Side Only Same

Street Lighting Existing Proposed Street Lighting On Wood Poles Same

Cost **Total Cost** \$1,730,000

Adjacent Property Assessments \$160,000 City Share \$1,570,000

Assessment Policy

Street Concrete Items Owner 50% / City 50% Sanitary Sewer Lateral Replacements Owner 25% / City 75%

Assessments payable in one lump sum or over a period of 8 years, with 5% interest charged on unpaid balance

All remaining contract items to be paid for by the City of Madison

Schedule

Year

Start Date 5-May-08 Length of Project 3-4 Months

Traffic Calming None

Traffic Detours Project area open to local traffic only

Real Estate Requirements Not Required