

15104: North Shore Drive - Path

Project Engineer		Aaron Canton Ph: 242-4763 email: acanton@cityofmadison.com
Project Limits Alder: 4 Verveer		Southwest Path to S Bedford Street
Project Description		This project includes reconstructing the existing sidewalk along the north-side of North Shore Drive between the Southwest Path and S Bedford St. The new path will connect to the new Brittingham Path to be built with the John Nolen Drive reconstruction project in 2026. A raised crossing is included at the S Bedford St intersection. Storm sewer will be adjusted/added as needed. The right-turn lane from North Shore Dr to S Bedford St will be removed with this project for the future Brittingham Path.
Path	Existing	Proposed
	6-ft wide concrete sidewalk	10-ft wide asphalt path
Storm Sewer	Existing	Proposed
	Storm inlets at Bedford-NSD intersection	Adjust/Add inlets as needed for curb changes
Parking N/A	Existing	Proposed
Lighting N/A	Existing	Proposed
	Street Lighting	Existing lighting will remain and light path
Land Purchases N/A		
Trees No Tree removals anticipated		
Assessment Policy No Assessments		
Schedule		
Advertise for bids	December 2024	
Anticipated Construction Start	Spring 2025	
Approximate Duration	Approx. 2 Months	
Costs		
Estimated Total Cost:	\$	480,000.00
Assessments:	\$	-
City Engineering Cost:	\$	480,000.00
Correspondence		
Transportation Commission (May 16, 2024)		
Public Informational Meeting (with John Nolen Drive on May 23, 2024)		