

**Official Project Name: Chamberlain Avenue Reconstruction Assessment District - 2007****Project Engineer** Jim Wolfe 266.4099**Project Limits** Chamberlain Ave. from University Ave. to the North end

<b>Street</b>	<b>Existing</b>	<b>Proposed</b>
Project Type		Reconstruction or Resurface
Last Surfaced	1926	
Pavement Rating	3	
Curb Rating	4	
Width	22 Feet	22 Feet
Surface Type	Concrete	Asphaltic

<b>Sidewalk</b>	<b>Existing</b>	<b>Proposed</b>
Work Required		Replace As Necessary

<b>Storm Sewer</b>	<b>Existing</b>	<b>Proposed</b>
Work Required		Replace Deteriorated Sections
Design Storm		10 Year
Size	12 inches	18 - 24 inches
Material	Concrete	Concrete
Year	1969	2007

<b>Sanitary Sewer</b>	<b>Existing</b>	<b>Proposed</b>
Work Required		Complete Replacement
Size	6 Inch (Substandard)	8 Inch
Material	VC	PVC
Year	1925	2007

<b>Water Main</b>	<b>Existing</b>	<b>Proposed</b>
Work Required		Complete Replacement
Size	4 Inch (Substandard)	6 Inch
Material	Cast Iron	Ductile Iron
Year	1925	2007
Note: At this time, water main work to be conducted solely by the Water Utility and will not be included in the contract for this project		

<b>Parking</b>	<b>Existing</b>	<b>Proposed</b>
Parking Conditions	Parking West Side Only	Same

<b>Street Lighting</b>	<b>Existing</b>	<b>Proposed</b>
Street Lighting	On Steel Poles	Same

<b>Cost</b>	
Total Cost	\$185,000
Adjacent Property Assessments	\$19,000
City Share	\$166,000

**Assessment Policy**  
 Street Concrete Items Owner 50% / City 50%  
 Sanitary Sewer Lateral Replacements Owner 25% / City 75%  
 Assessments payable in one lump sum or over a period of 8 years, with 5% interest charged on unpaid balance  
 All remaining contract items to be paid for by the City of Madison

**Schedule**  
 Start Date 2-Jul-07  
 Length of Project 3-4 Months  
 Note: Project to be bid and coordinated with Kendall Avenue Reconstruction

**Traffic Calming** Not Included**Traffic Detours** Describe**Real Estate Requirements** Not Required**Correspondence** None