## **HAWTHORNE COURT RECONSTRUCTION ASSESSMENT DISTRICT - 2023**

Project Engineer **Project Limits** 

Emma Almy ph: 261-5537 email: ealmy@cityofmadison.com Hawthorne Court from University Avenue to State Street

Proposed

Proposed

Alder: 2 Bennett

(see map on reverse)

**Existing** 

Н	la۷	wtl	hο	rne	Co	urt

Driveways

Project Type: Street Reconstruction Last Surfaced 2010 Reconstruction **New Pavement** Pavement Rating 5 New C&G Curb Rating 7 Width 14' 11.5' Surface Type Asphalt Concrete Traffic Patterns Two-way traffic Convert to one-way northbound

Sidewalk, Terraces, & Driveways

2' walk on west side, 1.5' walk on east side 6' sidewalk (5' sidewalk with 1' curb head) Terraces None None Asphalt Asphalt

Storm Sewer Existing Proposed Work Required: Remove/replace storm sewer main, inlets, and private storm (5) along Hawthorne

New 18" or 21" Pipe Material Clav Concrete Year 1980s 2026

Sanitary Sewer Existing

Work Required: Remove/replace sewer and laterals along Hawthorne 10" New 8" Pipe Clay Material **PVC** Year 1950s 2026

Water Main Existing Proposed

Work Required: Remove/replace existing main, hydrants, and services Size 6" Material Sand cast iron Ductile Iron Year 1920s 2026

Parking

None

**Street Lighting** Existing Proposed City lighting on City poles Area Street Lighting MG&E lighting on utility poles

#### **Traffic Signals**

None

#### **Land Purchases**

None

#### Trees

The tree that is within the project limits (440 Hawthorne Ct) may have the roots trimmed during construction.

#### **Assessment Policy**

Replace 4.75' of Concrete Pavement Owner 100% / City 0% Remainder of Pavement, if any Owner 0% / City 100% Install New Sidewalk Owner 0% / City 100% Replace Curb & Gutter Owner 0% / City 100% Sanitary Laterals to Property Line Owner 25% / City 75% Sanitary Sewer Main Owner 0% / City 100% Storm Sewer Main Owner 0% / City 100% Private Storm Sewer Lateral Owner 100% / City 0%

Assessments payable in one lump sum or over a period of 8 years, with 4% interest charged on unpaid balance.

# Schedule

Advertise for bids Spring 2026 **Anticipated Construction Start** Spring/Summer 2026 Approximate Duration Approx. 4 months

### Costs

Total Cost: \$1,190,000.00 Assessments: \$47,090.85

City Engineering Cost: \$1,142,909.15

# Correspondence

Public information meeting July 18, 2023 via Zoom.

see Map on reverse

