



Official Project Name Madison Street Reconstruction Assessment District-2012

Project Engineer LeAnne Hannan 266-4057

Project Limits Grant St. to Van Buren St
Alder: Sue Ellingson

Street	Existing	Proposed
Project Type		Reconstruction
Last Surfaced	1959	
Pavement Rating	5	
Curb Rating	3	
Width	28 ft	same
Surface Type	Asphaltic	Asphaltic
Traffic (Average Vehicles per Day)	not available	Same

Sidewalk	Existing	Proposed
Work Required		Replace As Necessary

Storm Sewer	Existing	Proposed
Work Required		
Design Storm		relocate from terrace to street
Size	18" & 21"	24"
Material	VP	RCP
Year	1911	

Sanitary Sewer	Existing	Proposed
Work Required		Complete Replacement
Size	8"	8"
Material	VP	PVC
Year	1909	

Water Main	Existing	Proposed
Work Required		Complete Replacement
Size	6"	8"
Material	SACI UL	DI
Year	1906 & 1911	

Parking	Existing	Proposed
Parking Conditions	Parking Both Sides	Same

Street Lighting	Existing	Proposed
Street Lighting	On MG&E wood poles	Same

Cost
 Total Cost
 Adjacent Property Assessments
 City Share \$0

Assessment Policy
 Street Concrete Items Owner 50% / City 50%
 Sanitary Sewer Lateral Replacements Owner 25% / City 75%
 Assessments payable in one lump sum or over a period of 8 years, with 3% interest charged on unpaid balance
 All remaining contract items to be paid for by the City of Madison

Schedule
 Start Date 30-Jul-12
 Length of Project 2.5 months

Traffic Calming A petition has been submitted, this will start the review process for the possible installation of traffic calming (speed humps) in the future.

Traffic Detours none

Real Estate Requirements Not Required

Tree Information trimming prior to construction, no removals anticipated at this time

Correspondence

Melissa Schultz

Requested that someone be available, at the PIM, to discuss traffic calling.
Traffic Engineering was unable to provide a staff member to attend the meeting,
but a copy of the flow chart outlining the approval process was provided.