


Aerial Locator Map  
432- 436 State St.  
January 24, 2022






W. Gilman St.

State Street




Site Plan  
432- 436 State St.  
June 24, 2022







Roof Plan




Fourth Floor Plan




First Floor Plan




Loft




Third Floor Plan



Lower Level Floor Plan



Fifth Floor Plan




Second Floor Plan



Floor Plans  
432- 436 State St.  
June 24, 2022



LANDSCAPE PLAN: AT GRADE



LANDSCAPE PLAN: ROOF DECK



PLANT SCHEDULE

DECIDUOUS SHRUBS	BOTANICAL / COMMON NAME	ROOT COND.	SIZE	QTY
Cf	Cornus stolonifera 'Farrow' TM / Arctic Fire Red Twig Dogwood	Cont.	3 Gal.	5
Sc	Sambucus canadensis / American Elderberry	Cont.	5 Gal.	3
EVERGREEN SHRUBS	BOTANICAL / COMMON NAME	ROOT COND.	SIZE	QTY
Jt	Juniperus chinensis 'Trautman' / Trautman Juniper	Cont.	5' ht.	2
Jp	Juniperus procumbens 'Nano' / Dwarf Japanese Garden Juniper	Cont.	3 Gal.	6
Tm	Taxus x media 'Everlow' / Everlow Anglo-Japanese Yew	Cont.	5 Gal.	7
PERENNIALS	BOTANICAL / COMMON NAME	ROOT COND.	SIZE	QTY
cr	Cimicifuga racemosa / Black Cohosh	Cont.	1 Gal.	6
gm	Geranium macrorrhizum 'Bevan's Variety' / Bevan's Variety Bigroot Geranium	Cont.	1 Gal.	29
pq	Parthenocissus quinquefolia engelmannii / Engelmann Virginia Creeper	Cont.	2 Gal.	1
ss	Schizachyrium scoparium 'Blue Heaven' / Blue Heaven Little Bluestem	Cont.	1 Gal.	51

PLANT MATERIAL NOTES:

- ALL PLANTINGS SHALL CONFORM TO QUALITY REQUIREMENTS AS PER ANSI Z60.1.
- ALL PLANT MATERIAL SHALL BE TRUE TO SPECIES, VARIETY AND SIZE SPECIFIED, NURSERY GROWN IN ACCORDANCE WITH GOOD HORTICULTURAL PRACTICES, AND UNDER CLIMATIC CONDITIONS SIMILAR TO THOSE OF THE PROJECT SITE.
- CONTACT LANDSCAPE ARCHITECT, IN WRITING, TO REQUEST ANY PLANT MATERIAL SUBSTITUTIONS DUE TO AVAILABILITY ISSUES.
- ALL PLANTS SHALL BE GUARANTEED TO BE IN HEALTHY AND FLOURISHING CONDITION DURING THE GROWING SEASON FOLLOWING INSTALLATION. ALL PLANT MATERIAL SHALL BE GUARANTEED FOR ONE YEAR FROM THE TIME OF INSTALLATION.

LANDSCAPE MATERIAL NOTES:

- CONTRACTOR SHALL PROVIDE A SUITABLE AMENDED TOPSOIL BLEND FOR ALL PLANTING AREAS WHERE SOIL CONDITIONS ARE UNSUITABLE FOR PLANT GROWTH. TOPSOIL SHALL CONFORM TO QUALITY REQUIREMENTS AS PER SECTION 625.2(1) OF THE "STANDARD SPECIFICATIONS FOR HIGHWAY CONSTRUCTION." PROVIDE A MINIMUM OF 18" OF TOPSOIL IN ALL PLANTING AREAS AND 6" OF TOPSOIL IN AREAS TO BE SEEDED/SODDED.

- LANDSCAPE BEDS TO BE MULCHED WITH UNDYED SHREDDED HARDWOOD BARK MULCH TO 3" DEPTH MIN. AND EDGED WITH COMMERCIAL GRADE ALUMINUM LANDSCAPE EDGING, PERMALOC CLEANLINE 3/4"x4" OR EQUAL, COLOR BLACK ANODIZED.

SOD PLANTING NOTES:

- ALL DISTURBED AREAS, UNLESS OTHERWISE NOTED, TO BE REPAIRED WITH TURFGRASS SOD. SELECT SOD GROWN IN MINERAL SOILS WITH ESTABLISHED ROOT SYSTEM. SOD GROWN IN PEAT WILL BE REJECTED. STAGGER SEAMS AND ROLL TO ENSURE SOIL CONTACT. MAINTAIN ADEQUATE SOIL MOISTURE UNTIL FINAL ACCEPTANCE.

REVISIONS	NO.	DATE	REVISIONS	REMARKS
	1	5/9/22	PLAN UPDATE	

DATE: 02/07/2022  
DRAFTER: SVN  
CHECKED: TSCH  
PROJECT NO.: 210421



















Flat Lock Metal  
DMI  
Weathered Zinc




Composite Panel  
James Hardie  
Iron Gray



Brick Veneer  
Interstate Brick  
Arctic White



Masonry Base Veneer  
RockCast  
Light Gray



Cast Stone Elements  
RockCast  
Crystal White




Window Trim - Black



EXTERIOR MATERIAL SCHEDULE		
BUILDING ELEMENT	MANUFACTURER	COLOR
(#1) - FLAT LOCK METAL SIDING	DMI	WEATHERED ZINC
COMPOSITE TRIM	DMI	COLOR TO MATCH ADJ.
(#2) - COMPOSITE PANEL	JAMES HARDIE	IRON GRAY
(#2.1) - COMPOSITE PANEL	JAMES HARDIE	MATCH WINDOW COLOR
(#3) - BRICK VENEER	INTERSTATE BRICK	ARCTIC WHITE
(#4) - MASONRY VENEER	ROCKCAST	LIGHT GRAY
(#5) - CAST STONE BANDS & SILLS	ROCKCAST	CRYSTAL WHITE
(#6) - COMPOSITE WINDOWS	ANDERSEN 100	BLACK
(#7) - ALUM. STOREFRONT	N/A	BLACK
(#8) - INSULATED METAL DOORS/FRAMES	N/A	BLACK
CANOPY & BAY SOFFITS	TBD	COLOR TO MATCH ADJ. TRIM/SIDING
(#9) - TENSION ROD DECK ASSEMBLY	N/A	BLACK
(#10) - RAILINGS & HANDRAILS	SUPERIOR	BLACK
TREATED-EXPOSED DECK BEAMS	N/A	BROWN TREATED

434-444 State Street  
MADISON, WI  
5/10/2022  
KBA #1939






NOT FOR CONSTRUCTION




1 COLORED ELEVATION - WEST  
A-2.3 1/8" = 1'-0"




2 COLORED ELEVATION - SOUTH  
A-2.3 1/8" = 1'-0"



EXTERIOR MATERIAL SCHEDULE		
BUILDING ELEMENT	MANUFACTURER	COLOR
(#1) - FLAT LOCK METAL SIDING	DMI	WEATHERED ZINC
COMPOSITE TRIM	DMI	COLOR TO MATCH ADJ.
(#2) - COMPOSITE PANEL	JAMES HARDIE	IRON GRAY
(#2.1) - COMPOSITE PANEL	JAMES HARDIE	MATCH WINDOW COLOR
(#3) - BRICK VENEER	INTERSTATE BRICK	ARCTIC WHITE
(#4) - MASONRY VENEER	ROCKCAST	LIGHT GRAY
(#5) - CAST STONE BANDS & SILLS	ROCKCAST	CRYSTAL WHITE
(#6) - COMPOSITE WINDOWS	ANDERSEN 100	BLACK
(#7) - ALUM. STOREFRONT	N/A	BLACK
(#8) - INSULATED METAL DOORS/FRAMES	N/A	BLACK
CANOPY & BAY SOFFITS	TBD	COLOR TO MATCH ADJ. TRIM/SIDING
(#9) - TENSION ROD DECK ASSEMBLY	N/A	BLACK
(#10) - RAILINGS & HANDRAILS	SUPERIOR	BLACK
TREATED-EXPOSED DECK BEAMS	N/A	BROWN TREATED




NOT FOR CONSTRUCTION



**1** COLORED ELEVATION - EAST  
A-2.4 1/8" = 1'-0"



**2** COLORED ELEVATION - NORTH  
A-2.4 1/8" = 1'-0"





EXTERIOR MATERIAL SCHEDULE		
BUILDING ELEMENT	MANUFACTURER	COLOR
(#1) - FLAT LOCK METAL SIDING	DMI	WEATHERED ZINC
COMPOSITE TRIM	DMI	COLOR TO MATCH ADJ.
(#2) - COMPOSITE PANEL	JAMES HARDIE	IRON GRAY
(#2.1) - COMPOSITE PANEL	JAMES HARDIE	MATCH WINDOW COLOR
(#3) - BRICK VENEER	INTERSTATE BRICK	ARCTIC WHITE
(#4) - MASONRY VENEER	ROCKCAST	LIGHT GRAY
(#5) - CAST STONE BANDS & SILLS	ROCKCAST	CRYSTAL WHITE
(#6) - COMPOSITE WINDOWS	ANDERSEN 100	BLACK
(#7) - ALUM. STOREFRONT	N/A	BLACK
(#8) - INSULATED METAL DOORS/FRAMES	N/A	BLACK
CANOPY & BAY SOFFITS	TBD	COLOR TO MATCH ADJ. TRIM/SIDING
(#9) - TENSION ROD DECK ASSEMBLY	N/A	BLACK
(#10) - RAILINGS & HANDRAILS	SUPERIOR	BLACK
TREATED-EXPOSED DECK BEAMS	N/A	BROWN TREATED

**GENERAL NOTES:**

1. THE APPLICANT SHALL REPLACE ALL SIDEWALK AND CURB AND GUTTER THAT ABUTS THE PROPERTY THAT IS DAMAGED BY THE CONSTRUCTION, OR ANY SIDEWALK AND CURB AND GUTTER WHICH THE CITY ENGINEER DETERMINES NEEDS TO BE REPLACED BECAUSE IT IS NOT AT A DESIRABLE GRADE, REGARDLESS OF WHETHER THE CONDITION EXISTED PRIOR TO BEGINNING CONSTRUCTION.
2. ALL WORK IN THE PUBLIC RIGHT OF WAY SHALL BE PERFORMED BY A CITY-LICENSED CONTRACTOR.
3. ALL DAMAGE TO THE PAVEMENT ON CITY STREETS AND ADJACENT TO THIS DEVELOPMENT SHALL BE RESTORED IN ACCORDANCE WITH THE CITY OF MADISON'S PAVEMENT PATCHING CRITERIA.
4. ALL PROPOSED STREET TREE REMOVALS WITHIN THE RIGHT OF WAY SHALL BE REVIEWED BY CITY FORESTRY BEFORE THE PLAN COMMISSION MEETING. STREET TREE REMOVALS REQUIRE APPROVAL AND A TREE REMOVAL PERMIT ISSUED BY CITY FORESTRY. ANY STREET TREE REMOVALS REQUESTED AFTER THE DEVELOPMENT PLAN IS APPROVED BY THE PLAN COMMISSION OR THE BOARD OF PUBLIC WORKS AND CITY FORESTRY WILL REQUIRE A MINIMUM OF A 72-HOUR REVIEW PERIOD WHICH SHALL INCLUDE THE NOTIFICATION OF THE ALDERPERSON WITHIN WHO'S DISTRICT IS AFFECTED BY THE STREET TREE REMOVAL(S) PRIOR TO A TREE REMOVAL PERMIT BEING ISSUED.
5. AS DEFINED BY THE SECTION 107.13 OF CITY OF MADISON STANDARD SPECIFICATIONS FOR PUBLIC WORKS CONSTRUCTION: NO EXCAVATION IS PERMITTED WITHIN 5 FEET OF THE TRUNK OF THE STREET TREE OR WHEN CUTTING ROOTS OVER 3 INCHES IN DIAMETER. IF EXCAVATION IS NECESSARY, THE CONTRACTOR SHALL CONTACT MADISON CITY FORESTRY (266-4816) PRIOR TO EXCAVATION. CITY OF MADISON FORESTRY PERSONNEL SHALL ASSESS THE IMPACT TO THE TREE AND TO ITS ROOT SYSTEM PRIOR TO WORK COMMENCING. TREE PROTECTION SPECIFICATIONS CAN BE FOUND ON THE FOLLOWING WEBSITE: [CITYOFMADISON.COM/BUSINESS/PW/SPECS.CFM](http://CITYOFMADISON.COM/BUSINESS/PW/SPECS.CFM)
6. CONTRACTOR SHALL TAKE PRECAUTIONS DURING CONSTRUCTION TO NOT DISFIGURE, SCAR, OR IMPAIR THE HEALTH OF ANY STREET TREE. CONTRACTOR SHALL OPERATE EQUIPMENT IN A MANNER AS TO NOT DAMAGE THE BRANCHES OF THE STREET TREE(S). THIS MAY REQUIRE USING SMALLER EQUIPMENT AND LOADING AND UNLOADING MATERIALS IN A DESIGNATED SPACE AWAY FROM TREES ON THE CONSTRUCTION SITE. ANY DAMAGE OR INJURY TO EXISTING STREET TREES (EITHER ABOVE OR BELOW GROUND) SHALL BE REPORTED IMMEDIATELY TO CITY FORESTRY AT 266-4816. PENALTIES AND REMEDIATION SHALL BE REQUIRED.
7. SECTION 107.13(G) OF CITY OF MADISON STANDARD SPECIFICATIONS FOR PUBLIC WORKS CONSTRUCTION ADDRESSES SOIL COMPACTION NEAR STREET TREES AND SHALL BE FOLLOWED BY CONTRACTOR. THE STORAGE OF PARKED VEHICLES, CONSTRUCTION EQUIPMENT, BUILDING MATERIALS, REFUSE, EXCAVATED SPOILS OR DUMPING OF POISONOUS MATERIALS ON OR AROUND TREES AND ROOTS WITHIN FIVE (5) FEET OF THE TREE OR WITHIN THE PROTECTION ZONE IS PROHIBITED.
8. ON THIS PROJECT, STREET TREE PROTECTION ZONE FENCING IS REQUIRED. THE FENCING SHALL BE ERECTED BEFORE THE DEMOLITION, GRADING OR CONSTRUCTION BEGINS. THE FENCE SHALL INCLUDE THE ENTIRE WIDTH OF TERRACE AND, EXTEND AT LEAST 5 FEET ON BOTH SIDES OF THE OUTSIDE EDGE OF THE TREE TRUNK. DO NOT REMOVE THE FENCING TO ALLOW FOR DELIVERIES OR EQUIPMENT ACCESS THROUGH THE TREE PROTECTION ZONE.
9. STREET TREE PRUNING SHALL BE COORDINATED WITH MADISON FORESTRY AT A MINIMUM OF TWO WEEKS PRIOR TO THE START OF CONSTRUCTION FOR THIS PROJECT. ALL PRUNING SHALL FOLLOW THE AMERICAN NATIONAL STANDARDS INSTITUTE (ANSI) A300 - PART 1 STANDARDS FOR PRUNING.
10. AT LEAST ONE WEEK PRIOR TO STREET TREE PLANTING, CONTRACTOR SHALL CONTACT CITY FORESTRY AT (608) 266-4816 TO SCHEDULE INSPECTION AND APPROVAL OF NURSERY TREE STOCK AND REVIEW PLANTING SPECIFICATIONS WITH THE LANDSCAPER.
11. APPROVAL OF PLANS FOR THIS PROJECT DOES NOT INCLUDE ANY APPROVAL TO PRUNE, REMOVE, OR PLANT TREES IN THE PUBLIC RIGHT-OF-WAY. PERMISSION FOR SUCH ACTIVITIES MUST BE OBTAINED FROM THE CITY FORESTER (266-4816).
12. THE PUBLIC RIGHT-OF-WAY IS THE SOLE JURISDICTION OF THE CITY OF MADISON AND IS SUBJECT TO CHANGE AT ANY TIME. NO ITEMS SHOWN ON THIS SITE PLAN IN THE RIGHT-OF-WAY ARE PERMANENT AND MAY NEED TO BE REMOVED AT THE APPLICANT'S EXPENSE UPON NOTIFICATION BY THE CITY.


**SHEET INDEX:**

SITE	
C-1.1	SITE PLAN
C-1.2	FIRE DEPARTMENT ACCESS
C-1.3	LOT COVERAGE
C-1.4	USABLE OPEN SPACE
C101	EXISTING CONDITIONS & DEMOLITION PLAN
C102	OVERALL SITE PLAN
C103	DETAILED SITE PLAN
C201	GRADING & EROSION PLAN
C202	UTILITY PLAN
LANDSCAPE PLAN	
L101	LANDSCAPE PLAN
ARCHITECTURAL	
A-1.0	BASEMENT PLAN
A-1.1	FIRST FLOOR PLAN
A-1.2	SECOND FLOOR PLAN
A-1.3	THIRD FLOOR PLAN
A-1.4	FOURTH FLOOR PLAN
A-1.5	FIFTH FLOOR PLAN
A-2.1	EXTERIOR ELEVATIONS
A-2.2	EXTERIOR ELEVATIONS
A-2.3	ELEVATIONS COLORED
A-2.4	ELEVATIONS COLORED EXTERIOR RENDERINGS



**Site Development Data:**

Zoning	DC Downtown Core District
Densities:	
Lot Area	6,928 S.F. / .16 ACRES
Dwelling Units	23-26 units
Lot Area / D.U.	301 - 266 S.F./D.U.
Density	144 - 163 units / Acre
Lot Coverage	6,311 S.F. (91%)
Usable Open Space	1,636 S.F.
Building Height	5 stories
Commercial Area	5,719 - 6,445 S.F.
Dwelling Unit Mix:	
Studio	20-23
One Bedroom	3
Total Dwelling Units	23-26
Bicycle Parking:	
Basement - Long-term	26
Surface - Commercial/Guests	8 (within State St. R.O.W.)
Total	34



ISSUED  
Issued for UDC Informational - Jan. 24, 2022  
Land Use & UDC Submittal - February 07, 2022  
Updated Land Use & UDC Submittal - May 10, 2022

PROJECT TITLE  
**430, 432, 444  
State Street**

Madison, Wisconsin  
SHEET TITLE  
**Site Plan**

SHEET NUMBER

**C-1.1**  
PROJECT NO. **1939**  
© Knothe & Bruce Architects, LLC

**1** SITE PLAN  
C-1.1 1" = 10'-0"

