



Official Project Name Sanitary Sewer Replacement with Resurfacing-East Gorham Street 2008

Project Engineer LeAnne Hannan 266-4057

Project Limits Butler St E. Johnson St
Alder: Brenda Konkol

Street	Existing	Proposed
Project Type		Resurfacing w/complete pavement replacement from Livingston to E. Johnson, spot repairs from Butler to Livingston, conc pavt repairs west of Baldwin
Last Surfaced	1976, 1987	
Pavement Rating	5,6	
Curb Rating	8	
Width	30 & 36 feet	same with realignment and narrowing from Few to the east
Surface Type	Asphaltic	Asphaltic
Traffic (Average Vehicles per Day)	15,000 - 21,250	Same

Sidewalk	Existing	Proposed
Work Required		Replace As Necessary

Storm Sewer	Existing	Proposed
Work Required		replace as necessary
Design Storm		10 Year
Size	12" & 15"	12,15 & 18 inch
Material	VP	Concrete
Year	1951, 2003	2007

Sanitary Sewer	Existing	Proposed
Work Required		Replacement Livingston-Few
Size	6" & 8"	8 Inch
Material	VP	PVC
Year	1904-1906	2007

Water Main	Existing	Proposed
Work Required		Replacement Livingston-Few
Size	4" & 6"	8 Inch
Material	SACI UL	
Year	1882, 1937 1939	2007

Parking	Existing	Proposed
Parking Conditions	Parking One Side	Same

Street Lighting	Existing	Proposed
Street Lighting	On MG&E wood poles	Same

Cost

Total Cost \$2,160,000
street \$715,000 storm \$34,000
sanitary \$876,000 water \$485,000
street lights \$32,000 traffic signals \$18,000

Adjacent Property Assessments \$177,800
City Share \$1,982,200

Assessment Policy

Street Concrete Items Owner 50% / City 50%
Sanitary Sewer Lateral Replacements Owner 25% / City 75%
Assessments payable in one lump sum or over a period of 8 years, with 5% interest charged on unpaid balance
All remaining contract items to be paid for by the City of Madison

Schedule

Start Date

19-May-08

Length of Project

3 1/2 months, 9/1/08 completion date required

Traffic Calming

Not Included, except for narrowing of pavement east of Few St.

Traffic Detours

none

Real Estate Requirements

Not Required

Tree Information

trimming prior to construction

Correspondence

2/18/08 Betsy Parker, 1125 E Gorham--1. Separate from lead pipe replace?
2. Lead pipe and this project simultaneous? 3. Are they expected to pay for both projects 4. What if they can't pay (directed her to Comptrollers office)

2/27/08 Mr Otteson, 1047 E Gorham--clarification on curb thru driveway being included in replacement quantity.

2/27/08 William Rhode 1209 E Gorham. General questions, he can't attend the hearing. Feels that the street needs work.