



Project Engineer Steve Sonntag 267-1997

Project Limits
 Emmet St. from S. Fair Oaks Ave. to Garrison St.
 N. Franklin St. from E. Washington Ave. to E. Gorham St.
 School Rd. from Northort Dr. to Tory Dr.
 Upham St. from North St. to Seventh St.

Emmet St., N. Franklin St. & Schoil Rd.

Existing	Proposed
Project Type Reurfacing - replace pavement and curb as necessary	
Last Surfaced 1992, 1982, 1987	
Pavement Rating (out of 10) 6 (Emm.) 4-5 (Frank & Sch.)	
Curb Rating (out of 10) 8(Emm.) 6-7 (Frank.& Sch.)	
Widths 24 ft. (Emm.) 36 ft. (Fran. & Sch.)	Match Existing Widths
Surface Type asphalt	Asphalt on all streets

Upham St.

Existing	Proposed
Project Type Reconstruction	
Last Surfaced 1992	
Pavement Rating (out of 10) 5	
Curb Rating (out of 10) 5	
Widths 28 ft.	Match Existing Widths
Surface Type asphalt	asphalt

Sidewalk

Existing	Proposed
Work Required on both sides of streets except Emmet(S-side only), some recent repairs	Replace As Necessary

Storm Sewer

Existing	Proposed
Work Required Repair inlets and leads as needed	
Design Storm Size 12-24 inch	10 year match existing
Material Clay, and Conc	Concrete
Year Installed 1995, 1949, 1961, 1917	2010

Sanitary Sewer

Existing	Proposed
Work Required Complete Replacement (main & laterals)	
Size 6 inch 18 inch(Upham)	8 Inch, 18 inch(Franklin & Upham)
Material Clay	PVC
Year 1923, 1929, 1956, 1923	2010

Water Main

Existing	Proposed
Work Required Complete Replacement	
Size 6 inch	8 inch
Material Cast Iron	Ductile Iron
Year 1921,1884, 1956, 1922	2010

Parking

Parking conditions will return to the same as existing once construction is complete

Street Lighting

No change to existing lighting is proposed

Trees

All trees at risk due to lateral replacments and size of trees
 New tree protection specifications will be used

Assessment Policy

Street Concrete Items Owner 50% / City 50%
 Sanitary Sewer Lateral Replacements Owner 25% / City 75%
 Assessments payable in one lump sum or over a period of 8 years, with 3.5% interest charged on unpaid balance
 All remaining contract items to be paid for by the City of Madison

Schedule

Start Date June 28, 2010
 Expected Length of Project 3.5 Months for the entire project each street will be approximatlely 45-60 days

Traffic Calming

None

Traffic Detours

Local access only

Real Estate Requirements

Not Required

Correspondence

Several phone calls regarding assessments





