Ohmeda Drive Assessment District - 2022

Project Engineer Project Limits	- · · · · · · · · · · · · · · · · · · ·	ndrew Zwieg ph: 266-9219 email: azwieg@cityofmadison.com emrite Drive to 1,800 feet north and will end in a cul-de-sac	
Froject Limits	remine Drive to 1,000 feet north and will er	iu iii a cui-ue-sac	
Alder: 16 Currie	(see map on reverse)		
Ohmeda Drive	Existing	Proposed	
Project Type: Street Reconstruction			
Last Surfaced	Ohmeda: 2022 (New Asphalt By GE)	Reconstruction	
Pavement Rating	Ohmeda: 10	New Pavement	
Curb Rating	Ohmeda: 3	West Side: New Curb & Gutter; East Side: Grave Shoulder	
Width	Ohmeda: Varies 52-feet - 30-feet	Ohmeda: Varies 24-feet - 37-feet	
Surface Type	Asphalt	Asphalt	
Traffic Mitigation	None	Narrow Street	
Sidewalk, Terraces, & Driveways			
Sidewalks	None	Ohmeda: New Sidewalk West Side	
Terraces	Typical Section - Rural	Ohmeda:	
Driveways	Asphalt	Urban Section: Concrete; Rural Section: Asphalt	
Storm Sewer	Existing	Proposed	
Work Required: Install new storm sewer a			
Size	12"	Varies 12-inch - 30-inch	
Material	Concrete	Concrete	
Year	2009	2023	
Culverts	Existing	Proposed	
Work Required: Replace existing culverts			
Size	36-Inch	54-Inch	
Material	Steel	Concrete	
Year	Unknown	2023	
Sanitary Sewer	Existing	Proposed	
Work Required: Install new sanitary sewe			
Size	None	8-Inch	
Material	None	PVC	
Year	None	2023	
Water Main	Existing	Proposed	
Work Required: Install new water main in		40.1	
Size	None	12-Inch	
Material	None	Ductile Iron	
Year	None	2023	
Parking			
Ohmeda - existing parking on both sides Ohmeda - proposed parking on one side			
Street Lighting	Existing	Proposed	
Area Street Lighting	GE lighting on individual poles	·	
Padastrian Lighting	None	MG&E lighting on individual poles	
Pedestrian Lighting	None	None	
Traffic Signals			

Land Purchases

Ohmeda Drive currently serves the GE facility and until recently was mostly a private driveway. However, GE sold a portion of their property for new development. As part of the development, a CSM was recorded placing a Ohmeda Drive with City right-of-way.

All the existing trees along the west right-of-way boundary are planned for removal to accommodate construction of a sidewalk. There are 17 (6410 Femrite Road (4-Green Ash), (2-Box Elder, 2-Black Cherry, 6- European Buckthorn, 1-Nothern Red Oak, 1 Bur Oak, 1-White Mulberry) planned tree removals along the east side of the street to accommodate construction of the new drainage ditch.

Assessment Policy

Driveway Apron Replacement	Owner 50% / City 50%
New Driveway Aprons	Owner 100% / City 0%
New Sidewalk	Owner 100% / City 0%
Curb & Gutter Replacement*	Owner 50% / City 50%
New Curb & Gutter*	Owner 100% / City 0%
10' Pavement Reconstruction	Owner 100% / City 0%
Intersection Curb & Pavement	Owner 0% / City 100%
Street Lighting*	Owner 100% / City 0%
Sanitary Sewer Main	Owner 100% / City 0%
Sanitary Laterals to Property Line	Owner 100% / City 0%
Water Main	Owner 100% / City 0%
Water Services	Owner 100% / City 0%
Storm Sewer Main Within Street	Owner 100% / City 0%
Culverts For Drainage Ditch	Owner 0% / City 100%
Private Storm Connection (if any)	Owner 100% / City 0%

Assessments payable in one lump sum or over a period of 8 years, with 2% interest charged on unpaid balance.

^{*}Curb & pavement assessed per linear ft. of frontage

Schedule

Advertise for bids Anticipated Construction Start Approximate Duration December 2022 April 2022 Approx. 4 months

Costs

Total Cost: \$3,323,890.60 Assessments: \$1,921,078.49 City Engineering Cost: \$1,402,812.11

Correspondence

Transportation Commsission informational presentation September 9, 2022. Regular virtual meetings, phone calls, and email correspondence with each property owner and the development team to discuss the assessments, street design, and the construction schedule.



Tree Removal Locations

6410 Femrite Road (4-Green Ash), (2-Box Elder, 2-Black Cherry, 6- European Buckthorn, 1-Nothern Red Oak, 1 Bur Oak, 1-White Mulberry)