


PRELIMINARY PLAT OF HERRLING PROPERTY

BEING A REDIVISION OF OUTLOTS 1 AND 2 OF CERTIFIED SURVEY MAP NO. 15568, BEING LOCATED IN A PART OF THE NORTHWEST 1/4, NORTHEAST 1/4, SOUTHWEST 1/4 AND SOUTHEAST 1/4 OF THE SOUTHEAST 1/4 OF SECTION 20, TOWN 7 NORTH, RANGE 8 EAST, IN THE CITY OF MADISON, DANE COUNTY, WISCONSIN.



DEVELOPER:

OUTLOT 1 - C.S.M. #15568
UNITED FINANCIAL GROUP, INC.
660 W. RIDGEVIEW DRIVE
APPLETON, WI 54911
PHONE: (920) 968-8100
FAX: (920) 731-1696

ENGINEER / SURVEYOR:

OUTLOT 2 - C.S.M. #15568
WESTWIND MADISON, INC.
9201 WATERSIDE STREET
MIDDLETON, WI 53562
PHONE: (608) 831-5343



DEVELOPMENT NOTES:

- Subdivision contains 138.92 Acres of land, more or less. The dedication of right-of-way on Mineral Point Road and Pioneer Rd results in a net subdivision of 137.31 Acres.
- The property is subject to the "Final City of Madison and Town of Middleton Cooperative Plan" dated September 29, 2003, which includes the following development requirements:
 - Transition Area - defined 1/4 mile from the centerline of Pioneer Road, shall have a residential density limit of 4 units per net acre and maximum 4 units per multi-family residential structure.
 - 80-foot wide landscaped building setback shall be provided from Pioneer Road right-of-way.
- All lots to be served by Sanitary Sewer and Watermain.
- Public Roads to have Concrete Curb and Gutter, Concrete Sidewalks, Asphalt Pavement with Storm Sewer.
- All lots to have Underground Telephone, Electric, and Gas Service.
- Public Sanitary Sewer and Watermain infrastructure shall connect to the Existing Utilities in Mineral Point Road to the South and Elderberry Road to the East.
- The Subject Property is proposed to be Zoned: "SR-C2" (Suburban Residential-Consistent District), "SR-C3" (Suburban Residential-Consistent District), "TR-V2" (Tradition Residential-Varied District), "TR-U1" (Traditional Residential-Urban District), "SR-Y2" (Suburban Residential-Varied District), and "PR" (Parks and Recreation).
- Outlet designations:
 - Dedicated to the Public for Stormwater Management and Drainage purposes.
 - Dedicated to the Public for Stormwater Management and Drainage purposes.
 - Dedicated to the Public for Stormwater Management and Drainage purposes.
 - Dedicated to the Public for Stormwater Management and Drainage purposes.
 - Dedicated to the Public for Stormwater Drainage, Stormwater Management and Public Bike and Pedestrian Path Purposes.
 - Dedicated to the Public for Public Stormwater Drainage, Stormwater Management and Public Bike and Pedestrian Path Purposes.
 - Dedicated to the Public for Park purposes.
 - Dedicated to the Public for Regional Stormwater Management, Stormwater Management and Drainage purposes. Public Sidewalk Bike Path Easement.
 - Dedicated to the Public for Regional Stormwater Management and Drainage purposes.
 - Dedicated to the Public for Stormwater Management and Drainage purposes.
 - Dedicated to the Public for Stormwater Management and Drainage purposes.

DEVELOPMENT SUMMARY TABLE	
WEST OF TRANSITION LINE	EAST OF TRANSITION LINE
TOTAL AREA = 59.12 ac (excluding ROW) [59.55 ac currently]	TOTAL AREA = 78.19 ac (excluding ROW) [78.50 ac currently]
NET AREA = 37.08 acres [excludes ROW, Local Ponds, Regional Ponds]	NET AREA = 42.37 acres [excludes ROW, Local Ponds, Regional Ponds, Park & Greenway Corridor]
TOTAL UNITS = 148 units (3.99 units/net acre)	

PROPOSED USES	
Lot #	Proposed Zoning District
1-127	SR-C2
128-131	TR-V2
130-133	SR-C3
134-138	TR-U1
139	SR-V2
140-142	TR-U1
143	SR-V2
144-146	TR-V2

HERRLING PROPERTY					
PROPOSED ZONING DISTRICT REQUIREMENTS					
	Single-Family Detached SF-C2 District Requirements	Single-Family Detached SF-C3 District Requirements	TR-V2 District Requirements		Multi-Family TR-U1 District Requirements (>8 units)
Proposed Use	Single-Family Detached	Single-Family Detached	4 unit	Multi-Family (>4 unit permitted by Conditional Use)	Multi-Family (>8 units)
Lot Area (sq. ft.)	6,000	6,000	8,000/Four-unit	2,000/d.u.	1,000/d.u. + 300 per bedroom >2
Lot Width	50 ft.	50 ft.	50 ft.	60 ft.	50 ft.
Front Yard Setback	30 ft.	25 ft.	20 ft.	20 ft.	15 ft. or avg.
Maximum Front Yard Setback	N/A	N/A	30 ft. max.	30 ft. max.	N/A
Side Yard Setback	One-story: 6'/Two-story: 7'	One-story: 5'/Two-story: 6'	10 ft.	10 ft.	10 ft.
Rev. Corner Side Yard Setback	15 ft.	15 ft.	12 ft.	12 ft.	12 ft.
Rear Yard Setback	Lesser of 30' lot depth or 35 ft.	Lesser of 30' lot depth or 35 ft.	Lesser of 25% lot depth or 25 ft.	Lesser of 25% lot depth or 25 ft.	Lesser of 25% lot depth or 30 ft.
Maximum Height	2 stories / 35 ft.	2 stories / 35 ft.	3 stories / 40 ft.	3 stories / 65 ft.	4 stories / 52 ft.
Maximum Lot Coverage	50%	60%	70%	70%	75%
Usable Open Space (sq. ft. per d.u.)	1,000	750	500	500	320



PROJECT:
HERRLING PROPERTY
NEIGHBORHOOD DEVELOPMENT
CITY OF MADISON, WI
BY: United Financial Group, Inc.
660 W. Ridgeview Drive
Appleton, WI 54911

REVISION HISTORY
DATE: 3/08/19
DESCRIPTION: CITY SUBMITTAL
2/16/20 PER CITY REVIEW
1/05/24 RE-APPROVAL

DATE:
JANUARY 5, 2024
JOB NUMBER:
12-041-311-02

DESCRIPTION:
PRELIMINARY PLAT
SHEET
1 OF 1

