

# URBAN DESIGN COMMISSION APPLICATION

# UDC

City of Madison  
Planning Division  
Madison Municipal Building, Suite 017  
215 Martin Luther King, Jr. Blvd.  
P.O. Box 2985  
Madison, WI 53701-2985  
(608) 266-4635



## FOR OFFICE USE ONLY:

Date Received \_\_\_\_\_ ☐ Initial Submittal  
Paid \_\_\_\_\_ ☐ Revised Submittal

**Complete all sections of this application, including the desired meeting date and the action requested.** If your project requires both UDC and Land Use application submittals, a completed [Land Use Application](#) and accompanying submittal materials are also required to be submitted.

*If you need an interpreter, translator, materials in alternate formats or other accommodations to access these forms, please call the Planning Division at (608) 266-4635.*

*Si necesita interprete, traductor, materiales en diferentes formatos, u otro tipo de ayuda para acceder a estos formularios, por favor llame al (608) 266-4635.*

*Yog tias koj xav tau ib tug neeg txhais lus, tus neeg txhais ntawv, los sis xav tau cov ntaub ntawv ua lwm hom ntawv los sis lwm cov kev pab kom paub txog cov lus qhia no, thov hu rau Koog Npaj (Planning Division) (608) 266-4635.*

## 1. Project Information

Address (list all addresses on the project site): 521 E Washington Avenue

Title: \_\_\_\_\_

## 2. Application Type (check all that apply) and Requested Date

UDC meeting date requested August 14, 2024

- ☐ New development ☐ Alteration to an existing or previously-approved development  
☐ Informational ☐ Initial Approval ☒ Final Approval

## 3. Project Type

- ☒ Project in an Urban Design District  
☐ Project in the Downtown Core District (DC), Urban Mixed-Use District (UMX), or Mixed-Use Center District (MXC)  
☐ Project in the Suburban Employment Center District (SEC), Campus Institutional District (CI), or Employment Campus District (EC)  
☐ Planned Development (PD)  
☐ General Development Plan (GDP)  
☐ Specific Implementation Plan (SIP)  
☐ Planned Multi-Use Site or Residential Building Complex

### Signage

- ☐ Comprehensive Design Review (CDR)  
☐ Modifications of Height, Area, and Setback  
☐ Sign Exceptions as noted in [Sec. 31.043\(3\)](#), MGO

### Other

- ☐ Please specify \_\_\_\_\_

## 4. Applicant, Agent, and Property Owner Information

**Applicant name** John Leja  
**Street address** 8301 Machine Drive, Suite 102  
**Telephone** 608-831-3326

**Company** LZ Ventures  
**City/State/Zip** Madison, WI 53717  
**Email** jleja@me.com

**Project contact person** Duane Johnson  
**Street address** 8401 Greenway Blvd. Ste 900  
**Telephone** 608-836-3690

**Company** Knothe & Bruce Architects  
**City/State/Zip** Middleton, WI 53562  
**Email** djohnson@knothebruce.com

**Property owner (if not applicant)** \_\_\_\_\_  
**Street address** \_\_\_\_\_ **City/State/Zip** \_\_\_\_\_  
**Telephone** \_\_\_\_\_ **Email** \_\_\_\_\_

## Introduction

The City of Madison's Urban Design Commission (UDC) has been created to:

- Encourage and promote high quality in the design of new buildings, developments, remodeling, and additions so as to maintain and improve the established standards of property values within the City.
- Foster civic pride in the beauty and nobler assets of the City, and in all other ways possible assure a functionally efficient and visually attractive City in the future.

## Types of Approvals

There are three types of requests considered by the UDC:

- Informational Presentation. A request for an Informational Presentation to the UDC may be requested prior to seeking any approvals to obtain early feedback and direction before undertaking detailed design efforts. Applicants should provide details on the context of the site, design concept, site and building plans, and other relevant information to help the UDC understand the proposal and provide feedback. (Does not apply to CDR's or Signage Modification requests)
- Initial Approval. Applicants may, at their discretion, request Initial Approval of a proposal by presenting preliminary design information. As part of their review, the Commission will provide feedback on the design information that should be addressed at Final Approval stage.
- Final Approval. Applicants may request Final Approval of a proposal by presenting all final project details. Recommendations or concerns expressed by the UDC in the Initial Approval must be addressed at this time.

## Presentations to the Commission

The Urban Design Commission meets virtually via Zoom, typically on the second and fourth Wednesdays of each month at 4:30 p.m. Applicant presentations are strongly encouraged, although not required. Prior to the meeting, each individual speaker is required to complete an online registration form to speak at the meeting. A link to complete the online registration will be provided by staff prior to the meeting. Please note that individual presentations will be limited to a **maximum of three (3) minutes**. The pooling of time may be utilized to provide one speaker more time to present, however the additional time will be based on the number of registrants from the applicant team, i.e. two (2) applicant registrants = six (6) minutes for one (1) speaker.

Primarily, the UDC is interested in the appearance and design quality of projects. Emphasis should be given to the site plan, landscape plan, lighting plan, building elevations, exterior building materials, color scheme, and graphics. Please note that presentation slides, in a PDF file format, are required to be submitted **the Friday before** the UDC meeting.



The items listed below are minimum application requirements for the type of approval indicated. Please note that the UDC and/or staff may require additional information in order to have a complete understanding of the project.

## 1. Informational Presentation

- ☐ Locator Map
- ☐ Letter of Intent (If the project is within an Urban Design District, a summary of how the development proposal addresses the district criteria is required)
- ☐ Contextual site information, including photographs and layout of adjacent buildings/structures
- ☐ Site Plan
- ☐ Two-dimensional (2D) images of proposed buildings or structures.

Providing additional information beyond these minimums may generate a greater level of feedback from the Commission.

### Requirements for All Plan Sheets

1. Title block
2. Sheet number
3. North arrow
4. Scale, both written and graphic
5. Date
6. Fully dimensioned plans, scaled at 1"= 40' or larger

**\*\* All plans must be legible, including the full-sized landscape and lighting plans (if required)**

## 2. Initial Approval

- ☐ Locator Map
- ☐ Letter of Intent (If the project is within a Urban Design District, a summary of how the development proposal addresses the district criteria is required)
- ☐ Contextual site information, including photographs and layout of adjacent buildings/structures
- ☐ Site Plan showing location of existing and proposed buildings, walks, drives, bike lanes, bike parking, and existing trees over 18" diameter
- ☐ Landscape Plan and Plant List (*must be legible*)
- ☐ Building Elevations in both black & white and color for all building sides, including material and color callouts
- ☐ PD text and Letter of Intent (if applicable)

Providing additional information beyond these minimums may generate a greater level of feedback from the Commission.

## 3. Final Approval

All the requirements of the Initial Approval (see above), **plus**:

- ☐ Grading Plan
- ☐ Lighting Plan, including fixture cut sheets and photometrics plan (must be legible)
- ☐ Utility/HVAC equipment location and screening details (with a rooftop plan if roof-mounted)
- ☐ Site Plan showing site amenities, fencing, trash, bike parking, etc. (if applicable)
- ☐ PD text and Letter of Intent (if applicable)
- ☐ Samples of the exterior building materials
- ☐ Proposed sign areas and types (if applicable)

## 4. Signage Approval (*Comprehensive Design Review (CDR), Sign Modifications, and Sign Exceptions (per [Sec. 31.043\(3\)](#))*)

- ☐ Locator Map
- ☐ Letter of Intent (a summary of how the proposed signage is consistent with the CDR or Signage Modifications criteria is required)
- ☐ Contextual site information, including photographs of existing signage both on site and within proximity to the project site
- ☐ Site Plan showing the location of existing signage and proposed signage, dimensioned signage setbacks, sidewalks, driveways, and right-of-ways
- ☐ Proposed signage graphics (fully dimensioned, scaled drawings, including materials and colors, and night view)
- ☐ Perspective renderings (emphasis on pedestrian/automobile scale viewsheds)
- ☐ Illustration of the proposed signage that meets [Ch. 31, MGO](#) compared to what is being requested
- ☐ Graphic of the proposed signage as it relates to what the [Ch. 31, MGO](#) would permit



## 5. Required Submittal Materials

### ☐ Application Form

- A completed application form is required for each UDC appearance. For projects also requiring Plan Commission approval, applicants must also have submitted an accepted application for Plan Commission consideration prior to obtaining any formal action (Initial or Final Approval) from the UDC.

### ☐ Letter of Intent

- If the project is within an Urban Design District, a summary of how the development proposal addresses the district criteria is required.
- For signage applications, a summary of how the proposed signage is consistent with the applicable Comprehensive Design Review (CDR) or Signage Modification review criteria is required.

### ☐ Development Plans (Refer to checklist on Page 4 for plan details)

### ☐ Filing Fee (Refer to Section 7 (below) for a list of application fees by request type)

### ☐ Electronic Submittal

- Complete electronic submittals must be received prior to the application deadline before an application will be scheduled for a UDC meeting. Late materials will not be accepted. All plans must be legible and scalable when reduced. Individual PDF files of each item submitted should be submitted via email to [UDCapplications@cityofmadison.com](mailto:UDCapplications@cityofmadison.com). The email must include the project address, project name, and applicant name.
- Email Size Limits. Note that an individual email cannot exceed 20MB and it is the responsibility of the applicant to present files in a manner that can be accepted. Applicants who are unable to provide the materials electronically should contact the Planning Division at (608) 266-4635 for assistance.

### ☐ Notification to the District Alder

- Please provide an email to the District Alder notifying them that you are filing this UDC application. Please send this as early in the process as possible and provide a copy of that email with the submitted application.

## 6. Applicant Declarations

- Prior to submitting this application, the applicant is required to discuss the proposed project with Urban Design Commission staff. This application was discussed with Jessica Vaughn on 3/19/24.
- The applicant attests that all required materials are included in this submittal and understands that if any required information is not provided by the application deadline, the application will not be placed on an Urban Design Commission agenda for consideration.

Name of applicant John Leja Relationship to property Owner

Authorizing signature of property owner John J Leja Date 5/13/24  
John J Leja (May 10, 2024 10:18 CDT)

## 7. Application Filing Fees

Fee payments are due by the submittal date. Payments received after the submittal deadline may result in the submittal being scheduled for the next application review cycle. Fees may be paid in-person, via US Mail, or City drop box. If mailed, please mail to: *City of Madison Building Inspection, P.O. Box 2984, Madison, WI 53701-2984*. The City's drop box is located outside the Municipal Building at 215 Martin Luther King, Jr. Blvd. on the E Doty Street side of the building. Please make checks payable to *City Treasurer*, and include a completed application form or cover letter indicating the project location and applicant information with all checks mailed or submitted via the City's drop box.

Please consult the schedule below for the appropriate fee for your request:

- ☐ Urban Design Districts: \$350 (per [§33.24\(6\) MGO](#)).
- ☐ Minor Alteration in the Downtown Core District (DC) or Urban Mixed-Use District (UMX) : \$150 (per [§33.24\(6\)\(b\) MGO](#))
- ☐ Comprehensive Design Review: \$500 (per [§31.041\(3\)\(d\)\(1\)\(a\) MGO](#))
- ☐ Minor Alteration to a Comprehensive Sign Plan: \$100 (per [§31.041\(3\)\(d\)\(1\)\(c\) MGO](#))
- ☐ All other sign requests to the Urban Design Commission, including, but not limited to: appeals from the decisions of the Zoning Administrator, requests for Sign Modifications (of height, area, and setback), and additional sign code approvals: \$300 (per [§31.041\(3\)\(d\)\(2\) MGO](#))

A filing fee is not required for the following project applications if part of the combined application process involving both Urban Design Commission and Plan Commission:

- Project in the Downtown Core District (DC), Urban Mixed-Use District (UMX), or Mixed-Use Center District (MXC)
- Project in the Suburban Employment Center District (SEC), Campus Institutional District (CI), or Employment Campus District (EC)
- Planned Development (PD): General Development Plan (GDP) and/or Specific Implementation Plan (SIP)
- Planned Multi-Use Site or Residential Building Complex



July 22, 2024

Jessica Vaughn  
Madison Municipal Building, Suite 017  
215 Martin Luther King Jr. Blvd  
P.O. Box 2985  
Madison, Wisconsin 53701-2985



Re: Letter of Intent  
521 E Washington Ave – UDC Final  
**KBA Project #2379**

Ms. Jessica Vaughn,

The following is submitted together with the plans and application for the Urban Design Commission's Final consideration and approval:

**Organizational structure:**

Owner:	LZ Ventures c/o Angie Black Carlson Black O'Callaghan & Battenberg 222 W. Washington Ave., Suite 705 Madison, WI 53703 <a href="mailto:angie.black@carlsonblack.com">angie.black@carlsonblack.com</a>	Architect:	Knothe & Bruce Architects, LLC 8401 Greenway Blvd. Ste 900 Middleton, WI 53562 608-836-3690 Contact: Duane Johnson <a href="mailto:djohnson@knothebruce.com">djohnson@knothebruce.com</a>
Engineer:	Wyser Engineering 300 E Front Street Mt. Horeb, WI 53572 (608) 437-1862 Contact: Wade Wyse <a href="mailto:Wade.wyse@wyserengineering.com">Wade.wyse@wyserengineering.com</a>	Landscape Design:	Figure-Ground LLC Middleton, WI 53562 (608) 345-5101 Contact: Joe Porter <a href="mailto:jporter@figureground-design.com">jporter@figureground-design.com</a>

**Introduction:**

This proposed project involves the redevelopment of the current site at 521 E Washington Avenue which has a two-level commercial office building, located on the southern corner of S Blair Street and E Washington Avenue. The proposed redevelopment would consist of a new 8-story building with administrative offices on the first floor and partial basement and 70 residential units on floors 2 through 8. There will be 8 surface parking stalls accessed off Blair St. The facility would be utilized by Porchlight for their administrative headquarters as well as long-term stable affordable housing, this would replace their current facility located on Brooks Street.

Porchlight and LZ Ventures have fostered a mutual respect and great working relationship which has developed over the past 15 years sharing the same block with Porchlights current facility on Brooks St and LZ's Grand Central and X-01 student housing facilities. This is an incredible opportunity for Porchlight to substantially improve its housing and services and therefore ultimately fulfill its mission of reducing homelessness and providing affordable housing, and LZ ventures is excited to be a part of the solution. The proposed facility would have studio apartments, instead of the current (single room occupancy) SRO's which are at Brooks St. location. This would be life changing for the residents and greatly reduce

Porchlights operational and maintenance commitments, freeing up funds to be used elsewhere. In addition, this central location will provide residents with more convenient accessibility to transportation, including the new Bus Rapid Transit line, city services, employment opportunities and living needs. Due to the generosity of LZ Ventures, this project requires no financial assistance from the city or state. This project will be a much-needed upgrade for the Porchlight non-profit organization to help with home and job placement, improving the lives of Madison citizens.

The site is located on the south corner of E. Washington Avenue and S Blair St. It is composed of one parcel in a UMX zoning district, the site is approximately 0.24 acres in area.

This application requests demolition of the existing structure and conditional use approval to allow greater than 8 dwelling units for the development of the new Porchlight facility. An application for a Certified Survey Map is being submitted contemporaneously to remove the underlying lot lines to complete the building parcel.

### **Downtown Plan & Urban Design District**

The property is within the boundaries of the City of Madison Downtown Plan adopted in July 2012. The Plan was the product of 4 plus years of work including 125 group meetings with neighborhood and community groups, City Boards and Commissions, business owners and many other interested parties.

The Plan places the site within the Downtown Core which is recommended for the highest intensity of development within the city. One of the Plan's key recommendations is to accommodate future growth within the downtown. The Plan's Parcel Analysis Map identifies the site as an "underutilized site and/or obsolete building" and one of the sites for potential redevelopment to accommodate the City's growth for a 20-year horizon. The parcel analysis considered among other factors; parcel size, existing use, building condition, architectural character, and land valuation.

The Downtown Plan also provides guidelines for building height and designates this site as having a maximum building height of 8 stories.

The property is also located within Urban Design District #4 (UDD 4), which establishes the purpose of improving the appearance of those major transportation corridors east of the Capitol Square. UDD 4 has limited scope for building design. It does speak to general compatibility of building designs and for building materials to be low maintenance and harmonious with others in the area and to avoid large unbroken exterior facades.

### **Project Description:**

The proposed development is an 8-story residential building with 70 studio apartments, administrative offices and 8 surface parking stalls. The apartments are designed to help lower income residents. Employee parking is provided on-site, and the proposed redevelopment will not be requesting residential parking permits.

The project is well located to take advantage of public transportation as well as bike paths and is within walking distance of a grocery store as well as restaurants. There is also an abundance of streets with dedicated bike lanes within the area.

The proposed design of this building will incorporate simple balanced massing and a thoughtful use of



materials. Sitting at the intersection of East Washington & Blair Streets; The most prominent architectural feature occurs at this important intersection. A proud massing announces the presence of the building as well as the main entry into this facility. A durable masonry base anchors the building, balanced by open aluminum storefront windows which bathe the interior administrative spaces with natural light. The projecting masses above contrast the lighter colored masonry with a dark metal skin. This low maintenance material will best serve the tenants functional needs and create visual interest as wraps around the building. Recessed reliefs in the volume of the building add an embellishment of color to the elevations in addition to identifying entry & vertical circulation. Window louvers add a textural change to the planar form of the otherwise clean metal wall cladding.

### **Urban Design Commission Input:**

While developing this project, there have been numerous meetings with the city, alder and neighborhood members. These include the Preapplication meeting on March 19, 2024, the DAT Meeting on April 18, 2024, and the UDC Informational meeting on May 8, 2024. In addition, we achieved initial approval at the June 26, 2024, UDC meeting

Specifically, we would like to address the following conditions outlined from the UDC Initial approval meeting:

- The applicant shall provide additional information related to the landscape design and details of the “seating area” shown on the site plan, including providing a screen fence and/or landscaping.
  - *The patio has been further developed and detailed on sheet AC101P*
  - *We introduced LED benches and screened the patio from the adjacent parking area with a mix of concrete and metal panel screen walls interrupted by raised planters with vine trellises. Additionally, flexible gathering areas remain unprogrammed, which could be left open or have additional furniture installed by the tenant as the need arises.*
  - *We revised the first-floor plan to have direct access from the interior to this area by relocating the trash room, this will greatly improve the use and access to the outdoor space and allow better access for dumpsters to the trash truck*
- Revise the corner element to include a more defined building corner that is more cohesive with the other building corners, and with a higher level of design at the pedestrian level. Consideration should be given to including a canopy feature, removal of the white frame, or relocating the accent color to the ground floor, etc. for example.
  - *We looked at a few different options for the main corner element and decided the submitted design accomplished the most goals from the last UDC meeting and was preferred by our clients*
  - *We made the entry corner at street level all glass to differentiate it from other parts of the building*
  - *We eliminated the use of the off white MCM panel and instead use the midnight bronze used on the other corners, eliminating a material that has always been met with some resistance*
  - *The new midnight bronze corner features extends above the other materials and returns down to above the glass entry forming a unique entry corner form and doubles as an entry canopy*
  - *As recommended by multiple commission members, we reintroduced the colonial red metal to the stair tower features on the E Wash and parking lot sides of the building, the windows at these areas were also combined to look like a continuous curtainwall type window element*

**Project Schedule:**

It is anticipated that the construction will begin in January 2025 with a final completion in November 2025.

Thank you for your time reviewing our proposal.

Sincerely,

A handwritten signature in black ink, appearing to read "D. Johnson", written in a cursive style.

Duane Johnson, AIA, Partner





# WPX LED Wall Packs



Catalog  
Number

WPX1 LED P1 30K


Notes

Type

LABEL - A

Hit the Tab key or mouse over the page to see all interactive elements.

## Specifications



Front View

Side View

Luminaire	Height (H)	Width (W)	Depth (D)	Side Conduit Location		Weight
				A	B	
WPX1	8.1" (20.6 cm)	11.1" (28.3 cm)	3.2" (8.1 cm)	4.0" (10.3 cm)	0.6" (1.6 cm)	6.1 lbs (2.8kg)
WPX2	9.1" (23.1 cm)	12.3" (31.1 cm)	4.1" (10.5 cm)	4.5" (11.5 cm)	0.7" (1.7 cm)	8.2 lbs (3.7kg)
WPX3	9.5" (24.1 cm)	13.0" (33.0 cm)	5.5" (13.7 cm)	4.7" (12.0 cm)	0.7" (1.7 cm)	11.0 lbs (5.0kg)

## Ordering Information

EXAMPLE: WPX2 LED 40K MVOLT DDBXD

Series	Color Temperature	Voltage	Options	Finish
WPX1 LED P1	1,550 Lumens, 11W <sup>1</sup>	30K 3000K	MVOLT 120V - 277V	(blank) None
WPX1 LED P2	2,900 Lumens, 24W	40K 4000K	347 347V <sup>3</sup>	E4WH Emergency battery backup, CEC compliant (4W, 0°C min) <sup>2</sup>
WPX2 LED	6,000 Lumens, 47W	50K 5000K	E14WC Emergency battery backup, CEC compliant (14W, -20°C min) <sup>2</sup>	PE Photocell <sup>3</sup>
WPX3 LED	9,200 Lumens, 69W			

Note: The lumen output and input power shown in the ordering tree are average representations of all configuration options. Specific values are available on request.

### NOTES

1. All WPX wall packs come with 6kV surge protection standard, except WPX1 LED P1 package which comes with 2.5kV surge protection standard. Add SPD6KV option to get WPX1 LED P1 with 6kV surge protection. Sample nomenclature: WPX1 LED P1 40K MVOLT SPD6KV DDBXD
2. Battery pack options only available on WPX1 and WPX2.
3. Battery pack options not available with 347V and PE options.

## FEATURES & SPECIFICATIONS

### INTENDED USE

The WPX LED wall packs are designed to provide a cost-effective, energy-efficient solution for the one-for-one replacement of existing HID wall packs. The WPX1, WPX2 and WPX3 are ideal for replacing up to 150W, 250W, and 400W HID luminaires respectively. WPX luminaires deliver a uniform, wide distribution. WPX is rated for -40°C to 40°C.

### CONSTRUCTION

WPX feature a die-cast aluminum main body with optimal thermal management that both enhances LED efficacy and extends component life. The luminaires are IP66 rated, and sealed against moisture or environmental contaminants.

### ELECTRICAL

Light engine(s) configurations consist of high-efficacy LEDs and LED lumen maintenance of L90/100,000 hours. Color temperature (CCT) options of 3000K, 4000K and 5000K with minimum CRI of 70. Electronic drivers ensure system power factor >90% and THD <20%. All luminaires have 6kV surge protection (Note: WPX1 LED P1 package comes with a standard surge protection rating of 2.5kV. It can be ordered with an optional 6kV surge protection). All photocell (PE) operate on MVOLT (120V - 277V) input.

Note: The standard WPX LED wall pack luminaires come with field-adjustable drive current feature. This feature allows tuning the output current of the LED drivers to adjust the lumen output (to dim the luminaire).

### INSTALLATION

WPX can be mounted directly over a standard electrical junction box. Three 1/2 inch conduit ports on three sides allow for surface conduit wiring. A port on the back surface allows poke-through conduit wiring on surfaces that don't have an electrical junction box. Wiring can be made in the integral wiring compartment in all cases. WPX is only recommended for installations with LEDs facing downwards.

### LISTINGS

CSA Certified to meet U.S. and Canadian standards. Suitable for wet locations. IP66 Rated. DesignLights Consortium® (DLC) qualified product. Not all versions of this product may be DLC qualified. Please check the DLC Qualified Products List at [www.designlights.org/QPL](http://www.designlights.org/QPL) to confirm which versions are qualified. International Dark Sky Association (IDA) Fixture Seal of Approval (FSA) is available for all products on this page utilizing 3000K color temperature only.

### WARRANTY

5-year limited warranty. This is the only warranty provided and no other statements in this specification sheet create any warranty of any kind. All other express and implied warranties are disclaimed. Complete warranty terms located at: [www.acuitybrands.com/CustomerResources/Terms\\_and\\_conditions.aspx](http://www.acuitybrands.com/CustomerResources/Terms_and_conditions.aspx).

Note: Actual performance may differ as a result of end-user environment and application. All values are design or typical values, measured under laboratory conditions at 25°C. Specifications subject to change without notice.



One Lithonia Way • Conyers, Georgia 30012 • Phone: 1-800-705-SERV (7378) • [www.lithonia.com](http://www.lithonia.com)  
© 2020-2022 Acuity Brands Lighting, Inc. All rights reserved.

WPX LED  
Rev. 03/08/22

## Performance Data

### Electrical Load

Luminaire	Input Power (W)	120V	208V	240V	277V	347V
WPX1 LED P1	11W	0.09	0.05	0.05	0.04	0.03
WPX1 LED P2	24W	0.20	0.12	0.10	0.09	0.07
WPX2	47W	0.39	0.23	0.20	0.17	0.14
WPX3	69W	0.58	0.33	0.29	0.25	0.20

### Projected LED Lumen Maintenance

Data references the extrapolated performance projections in a 25°C ambient, based on 6,000 hours of LED testing (tested per IESNA LM-80-08 and projected per IESNA TM-21-11).

To calculate LLF, use the lumen maintenance factor that corresponds to the desired number of operating hours below. For other lumen maintenance values, contact factory.

Operating Hours	50,000	75,000	100,000
Lumen Maintenance Factor	>0.94	>0.92	>0.90

### Lumen Output

Luminaire	Color Temperature	Lumen Output
WPX1 LED P1	3000K	1,537
	4000K	1,568
	5000K	1,602
WPX1 LED P2	3000K	2,748
	4000K	2,912
	5000K	2,954
WPX2	3000K	5,719
	4000K	5,896
	5000K	6,201
WPX3	3000K	8,984
	4000K	9,269
	5000K	9,393

### Lumen Ambient Temperature (LAT) Multipliers

Use these factors to determine relative lumen output for average ambient temperatures from 0-50°C (32-122°F).

Ambient	Ambient	Lumen Multiplier
0°C	32°F	1.05
5°C	41°F	1.04
10°C	50°F	1.03
15°C	59°F	1.02
20°C	68°F	1.01
25°C	77°F	1.00
30°C	86°F	0.99
35°C	95°F	0.98
40°C	104°F	0.97

### HID Replacement Guide

Luminaire	Equivalent HID Lamp	WPX Input Power
WPX1 LED P1	100W	11W
WPX1 LED P2	150W	24W
WPX2	250W	47W
WPX3	400W	69W

### Emergency Egress Battery Packs

The emergency battery backup is integral to the luminaire — no external housing or back box is required. The emergency battery will power the luminaire for a minimum duration of 90 minutes and deliver minimum initial output of 550 lumens. Both battery pack options are CEC compliant.

Battery Type	Minimum Temperature Rating	Power (Watts)	Controls Option	Ordering Example
Standard	0°C	4W	E4WH	WPX2 LED 40K MVOLT <b>E4WH</b> DDBXD
Cold Weather	-20°C	14W	E14WC	WPX2 LED 40K MVOLT <b>E14WC</b> DDBXD


## Photometric Diagrams

To see complete photometric reports or download .ies files for this product, visit the Lithonia Lighting [WPX LED](https://www.lithonia.com) homepage. Tested in accordance with IESNA LM-79 and LM-80 standards


#### LEGEND

0.1 fc
0.2 fc
0.5 fc
1.0 fc


WPX1 LED P1




WPX1 LED P2



WPX2 LED



WPX3 LED



Mounting Height = 12 Feet.



# D-Series Size 0

## Amber Series



### LED Area Luminaire



d<sup>series</sup>

## Specifications

EPA:	0.44 ft <sup>2</sup> (0.04 m <sup>2</sup> )
Length:	26.18" (66.5 cm)
Width:	14.06" (35.7 cm)
Height H1:	2.26" (5.7 cm)
Height H2:	7.46" (18.9 cm)
Weight:	23 lbs (10.4 kg)



Catalog  
Number

DSX0 LED P1 AMBLW AMCRI T3M

Notes

Type

LABEL - B

Hit the Tab key or mouse over the page to see all interactive elements.

## Introduction

The modern styling of the D-Series features a highly refined aesthetic that blends seamlessly with its environment. The D-Series offers the benefits of the latest in Amber LED technology into a high performance, high efficacy, long-life luminaire.

The photometric performance results in sites with excellent uniformity, greater pole spacing and lower power density. D-Series outstanding photometry aids in reducing the number of poles required in area lighting.

## Ordering Information

EXAMPLE: DSX0 LED P6 AMBPC AMCRI T3M MVOLT SPA NLTAIR2 PIRHN DDBXD

DSX0 LED						
Series	LEDs	Color temperature <sup>2</sup>	Color Rendering Index <sup>2</sup>	Distribution	Voltage	Mounting
DSX0 LED	<b>Forward optics</b> P1 P5 P2 P6 P3 P4 <b>Rotated optics</b> P10 <sup>1</sup> P12 <sup>1</sup> P11 <sup>1</sup>	AMBLW Limited Wavelength Amber AMBPC Phosphor Converted Amber	AMCRI	AFR Automotive front row T1S Type I short T2M Type II medium T3M Type III medium T3LG Type III low glare <sup>3</sup> T4M Type IV medium T4LG Type IV low glare <sup>3</sup> TFTM Forward throw medium	T5M Type V medium T5LG Type V low glare T5W Type V wide BLC3 Type III backlight control <sup>3</sup> BLC4 Type IV backlight control <sup>3</sup> LCCO Left corner cutoff <sup>3</sup> RCCO Right corner cutoff <sup>3</sup> MVOLT (120V-277V) <sup>4</sup> HVOLT (347V-480V) <sup>5,6</sup> XVOLT (277V-480V) <sup>7,8</sup>	<b>Shipped included</b> SPA Square pole mounting (#8 drilling, 3.5" min. SQ pole) RPA Round pole mounting (#8 drilling, 3" min. RND pole) SPA5 Square pole mounting (#5 drilling, 3" min. SQ pole) <sup>9</sup> RPA5 Round pole mounting (#5 drilling, 3" min. RND pole) <sup>9</sup> SPA8N Square narrow pole mounting (#8 drilling, 3" min. SQ pole) WBA Wall bracket <sup>10</sup> MA Mast arm adapter (mounts on 2.3/8" OD horizontal tenon)

Control options	Other options	Finish (required)
<b>Shipped installed</b> NLTAIR2 PIRHN nLight AIR gen 2 enabled with bi-level motion / ambient sensor, 8-40' mounting height, ambient sensor enabled at 2fc <sup>11, 12, 18, 19</sup> PIR High/low, motion/ambient sensor, 8-40' mounting height, ambient sensor enabled at 2fc <sup>13, 18, 19</sup> PER NEMA twist-lock receptacle only (controls ordered separate) <sup>14</sup> PER5 Five-pin receptacle only (controls ordered separate) <sup>14, 19</sup>	PER7 Seven-pin receptacle only (controls ordered separate) <sup>14, 19</sup> FAO Field adjustable output <sup>15, 19</sup> BL30 Bi-level switched dimming, 30% <sup>16, 19</sup> BL50 Bi-level switched dimming, 50% <sup>16, 19</sup> DMG 0-10v dimming wires pulled outside fixture (for use with an external control, ordered separately) <sup>17</sup> <b>Shipped installed</b> HS Houseside shield (black finish standard) <sup>20</sup> L90 Left rotated optics <sup>1</sup> R90 Right rotated optics <sup>1</sup> CCE Coastal Construction <sup>21</sup> <b>Shipped separately</b> EGSR External Glare Shield (reversible, field install required, matches housing finish) BSDB Bird Spikes (field install required)	DDBXD Dark Bronze DBLXD Black DNAXD Natural Aluminum DWHXD White DDBTXD Textured dark bronze DBLBXD Textured black DNATXD Textured natural aluminum DWHGXD Textured white



One Lithonia Way • Conyers, Georgia 30012 • Phone: 1-800-705-SERV (7378) • [www.lithonia.com](http://www.lithonia.com)  
© 2011-2024 Acuity Brands Lighting, Inc. All rights reserved.

DSX0-LED AMBER  
Rev. 03/26/24  
Page 1 of 10

## Ordering Information

### Accessories

Ordered and shipped separately.

DLL127F 1.5 JU	Photocell - SSL twist-lock (120-277V) <sup>22</sup>
DLL347F 1.5 CUL JU	Photocell - SSL twist-lock (347V) <sup>22</sup>
DLL480F 1.5 CUL JU	Photocell - SSL twist-lock (480V) <sup>22</sup>
DSHORT SBK	Shorting cap <sup>22</sup>
DSX0HS P#	House-side shield (enter package number P1-6, P10-12 in place of #)
DSXRPA (FINISH)	Round pole adapter (#8 drilling, specify finish)
DSXRPA5 (FINISH)	Round pole adapter #5 drilling (specify finish)
DSXSPA5 (FINISH)	Square pole adapter #5 drilling (specify finish)
DSX0EGSR (FINISH)	External glare shield (specify finish)
DSX0BDB (FINISH)	Bird spike deterrent bracket (specify finish)


### NOTES

- Rotated optics available with packages P10, P11 and P12. Must be combined with option L90 or R90.
- AMBLW only available in package P1, P4 and P10. AMCRI must be specified with AMBLW or AMBPC.
- T3LG, T4LG, BLC3, BLC4, LCCO, RCCO not available with option HS.
- MVOLT driver operates on any line voltage from 120-277V (50/60 Hz).
- HVOLT driver operates on any line voltage from 347-480V (50/60 Hz).
- HVOLT not available with package P1, P2 and P10 when combined with option NLTAIR2 PIRHN or option PIR.
- XVOLT operates with any voltage between 277V and 480V (50/60 Hz).
- XVOLT not available in packages P1, P2 or P10.
- SPA5 and RPA5 for use with #5 drilling only (Not for use with #8 drilling).
- WBA cannot be combined with Type 5 distributions plus photocell (PER).
- NLTAIR2 and PIRHN must be ordered together. For more information on nLight Air 2.
- NLTAIR2 PIRHN not available with other controls including PIR, PER, PER5, PER7, FAO, BL30, BL50 and DMG. NLTAIR2 PIRHN not available with P1, P2 and P10 using HVOLT. NLTAIR2 PIRHN not available with P1, P2 and P10 using XVOLT.
- PIR not available with NLTAIR2, PER, PER5, PER7, FAO BL30, BL50 and DMG. PIR not available with P1, P2 and P10 using XVOLT.
- PER/PER5/PER7 not available with NLTAIR2, PIR, BL30, BL50. Photocell ordered and shipped as a separate line item from Acuity Brands Controls. See accessories. Shorting Cap included.
- FAO not available with other dimming control options NLTAIR2 PIRHN, PIR, PER5, PER7, BL30, BL50, or DMG.
- BL30 and BL50 are not available with NLTAIR2 PIRHN, PIR, PER, PER5, PER7, FAO and DMG.
- DMG not available with NLTAIR2 PIRHN, PIR, PER, PER5, PER7, BL30, BL50 and FAO.
- Reference Motion Sensor Default Settings table on page 4 to see functionality.
- Reference Controls Options table on page 4.
- Option HS not available with T3LG, T4LG, BLC3, BLC4, LCCO and RCCO distribution. Also available as a separate accessory; see Accessories information.
- CCE option not available with option BSDB and EGSR. Contact Technical Support for availability.
- Requires luminaire to be specified with PER, PER5 or PER7 option. See Controls Table on page 4.

## Shield Accessories




External Glare Shield (EGSR)




House Side Shield (HS)

## Drilling

### HANDHOLE ORIENTATION (from top of pole)



Handhole



### Tenon Mounting Slipfitter

Tenon O.D.	Mounting	Single Unit	2 @ 180	2 @ 90	3 @ 90	3 @ 120	4 @ 90
2-3/8"	RPA	AS3-5 190	AS3-5 280	AS3-5 290	AS3-5 390	AS3-5 320	AS3-5 490
2-7/8"	RPA	AST25-190	AST25-280	AST25-290	AST25-390	AST25-320	AST25-490
4"	RPA	AST35-190	AST35-280	AST35-290	AST35-390	AST35-320	AST35-490

Mounting Option	Drilling Template	Single	2 @ 180	2 @ 90	3 @ 90	3 @ 120	4 @ 90
Head Location		Side B	Side B & D	Side B & C	Side B, C & D	Round Pole Only	Side A, B, C & D
Drill Nomenclature	#8	DM19AS	DM28AS	DM29AS	DM39AS	DM32AS	DM49AS
Minimum Acceptable Outside Pole Dimension							
SPA	#8	3.5"	3.5"	3.5"	3.5"		3.5"
RPA	#8	3"	3"	3"	3"	3"	3"
SPA5	#5	3"	3"	3"	3"		3"
RPA5	#5	3"	3"	3"	3"	3"	3"
SPA8N	#8	3"	3"	3"	3"		3"

### DSX0 Area Luminaire - EPA

\*Includes luminaire and integral mounting arm. Other tenons, arms, brackets or other accessories are not included in this EPA data.

Fixture Quantity & Mounting Configuration	Single DM19	2 @ 180 DM28	2 @ 90 DM29	3 @ 90 DM39	3 @ 120 DM32	4 @ 90 DM49
Mounting Type						
DSX0 with SPA	0.44	0.88	0.96	1.18	---	1.16
DSX0 with SPA5, SPA8N	0.51	1.02	1.06	1.26	---	1.29
DSX0 with RPA, RPA5	0.51	1.02	1.06	1.26	1.24	1.29
DSX0 with MA	0.64	1.28	1.24	1.67	1.70	1.93


















# Photometric Diagrams

To see complete photometric reports or download .ies files for this product, visit Lithonia Lighting's [homepage](#).


Isofootcandle plots for the DSX0 LED P6 AMBPC AMCRI. Distances are in units of mounting height (15').

## LEGEND


- 0.1 fc
- 0.5 fc
- 1.0 fc



### AMBPC - Phosphor Converted Amber



### AMBLW - True Limited Wavelength Amber



## Performance Data

### FAO Dimming Settings

FAO Position	% Wattage	% Lumen Output
8	100%	100%
7	93%	95%
6	80%	85%
5	66%	73%
4	54%	61%
3	41%	49%
2	29%	36%
1	15%	20%

\*Note: Calculated values are based on original performance package data. When calculating new values for given FAO position, use published values for each package based on input watts and lumens by optic type.

### Electrical Load - AMBPC (Phosphor Converted Amber)

					Current (A)					
	Performance Package	LED Count	Drive Current (mA)	Wattage	120V	208V	240V	277V	347V	480V
Forward Optics (Non-Rotated)	P1	20	530	35	0.29	0.17	0.14	0.13	0.10	0.07
	P2	20	700	46	0.39	0.22	0.19	0.17	0.13	0.10
	P3	20	1050	71	0.59	0.34	0.30	0.26	0.20	0.15
	P4	40	530	69	0.57	0.33	0.29	0.25	0.20	0.14
	P5	40	700	91	0.76	0.44	0.38	0.33	0.26	0.19
	P6	40	1050	139	1.16	0.67	0.58	0.50	0.40	0.29
Rotated Optics (Requires L90 or R90)	P10	30	530	52	0.43	0.25	0.22	0.19	0.15	0.11
	P11	30	700	69	0.58	0.33	0.29	0.25	0.20	0.14
	P12	30	1050	106	0.88	0.51	0.44	0.38	0.30	0.22

### Electrical Load - AMBLW (Limited Wavelength Amber)

					Current (A)					
	Performance Package	LED Count	Drive Current (mA)	Wattage	120V	208V	240V	277V	347V	480V
Forward Optics (Non-Rotated)	P1	20	530	27	0.23	0.13	0.11	0.10	0.08	0.06
	P4	40	530	55	0.46	0.26	0.23	0.20	0.16	0.11
Rotated Optics (Requires L90 or R90)	P10	30	530	41	0.34	0.20	0.17	0.15	0.12	0.08

### Motion Sensor Default Settings

Option	Unoccupied Dimmed Level	High Level (when occupied)	Photocell Operation	Dwell Time	Ramp-up Time	Dimming Fade Rate
PIR	30%	100%	Enabled @ 2FC	7.5 min	3 sec	5 min
NLTAIR2 PIRHN	30%	100%	Enabled @ 2FC	7.5 min	3 sec	5 min

### Controls Options

Nomenclature	Description	Functionality	Primary control device	Notes
FAO	Field adjustable output device installed inside the luminaire; wired to the driver dimming leads.	Allows the luminaire to be manually dimmed, effectively trimming the light output.	FAO device	Cannot be used with other controls options that need the 0-10V leads
DS (not available on DSX0)	Drivers wired independently for 50/50 luminaire operation	The luminaire is wired to two separate circuits, allowing for 50/50 operation.	Independently wired drivers	Requires two separately switched circuits. Consider nLight AIR as a more cost effective alternative.
PERS or PER7	Twist-lock photocell receptacle	Compatible with standard twist-lock photocells for dusk to dawn operation, or advanced control nodes that provide 0-10V dimming signals.	Twist-lock photocells such as DLL Elite or advanced control nodes such as ROAM.	Pins 4 & 5 to dimming leads on driver, Pins 6 & 7 are capped inside luminaire. Cannot be used with other controls options that need the 0-10V leads.
PIR	Motion sensor with integral photocell. Sensor suitable for 8' to 40' mounting height.	Luminaires dim when no occupancy is detected.	Acuity Controls rSBG	Cannot be used with other controls options that need the 0-10V leads.
NLTAIR2 PIRHN	nLight AIR enabled luminaire for motion sensing, photocell and wireless communication.	Motion and ambient light sensing with group response. Scheduled dimming with motion sensor over-ride when wirelessly connected to the nLight Eclipse.	nLight Air rSBG	nLight AIR sensors can be programmed and commissioned from the ground using the CIAIRity Pro app. Cannot be used with other controls options that need the 0-10V leads.
BL30 or BL50	Integrated bi-level device that allows a second control circuit to switch all light engines to either 30% or 50% light output	BLC device provides input to 0-10V dimming leads on all drivers providing either 100% or dimmed (30% or 50%) control by a secondary circuit	BLC UVOLT1	BLC device is powered off the 0-10V dimming leads, thus can be used with any input voltage from 120 to 480V



## Performance Data

### Lumen Output

Lumen values are from photometric tests performed in accordance with IESNA LM-79-08. Data is considered to be representative of configurations shown within the tolerances described within LM-79. Contact factory for performance data on any configurations not shown here.

#### FORWARD OPTICS

Performance Package	LED Count	Drive Current (mA)	Distribution Type	AMBPC (Phosphor Converted)							AMBLW (Limited Wavelength)					
				System Watts	Lumens	B	U	G	LPW		System Watts	Lumens	B	U	G	LPW
P1	20	530	T1S	35W	3,118	1	0	1	90	27W	1,359	0	0	1	50	
			T2M		2,889	1	0	1	83		1,259	0	0	1	46	
			T3M		2,922	1	0	2	84		1,273	0	0	1	46	
			T3LG		2,610	1	0	1	75		1,138	0	0	1	42	
			T4M		2,966	1	0	2	85		1,292	0	0	1	47	
			T4LG		2,697	0	1	1	78		1,176	0	1	1	43	
			TFTM		2,986	1	0	2	86		1,301	0	0	1	47	
			T5M		3,051	2	0	1	88		1,330	1	0	0	49	
			T5W		3,101	3	0	1	89		1,351	1	0	1	49	
			T5LG		3,060	1	0	0	88		1,334	1	0	0	49	
			BLC3		2,125	0	0	1	61		926	0	0	0	34	
			BLC4		2,195	0	0	1	63		957	0	0	1	35	
			RCCO		2,145	0	0	1	62		935	0	0	1	34	
			LCCO		2,145	0	0	1	62		935	0	0	1	34	
			AFR		3,118	1	0	1	90		1,359	0	0	1	50	
P2	20	700	T1S	46W	3,912	1	0	1	84							
			T2M		3,624	1	0	2	78							
			T3M		3,666	1	0	2	79							
			T3LG		3,275	1	0	1	71							
			T4M		3,720	1	0	2	80							
			T4LG		3,384	1	2	1	73							
			TFTM		3,746	1	0	2	81							
			T5M		3,828	3	0	1	82							
			T5W		3,890	3	0	1	84							
			T5LG		3,839	2	0	0	83							
			BLC3		2,666	0	0	1	57							
			BLC4		2,754	0	0	2	59							
			RCCO		2,690	0	0	1	58							
			LCCO		2,690	0	0	1	58							
			AFR		3,912	1	0	1	84							
P3	20	1050	T1S	71W	5,257	1	0	1	74							
			T2M		4,870	1	0	2	69							
			T3M		4,927	1	0	2	70							
			T3LG		4,401	1	0	1	62							
			T4M		5,000	1	0	2	71							
			T4LG		4,548	1	2	1	64							
			TFTM		5,035	1	0	2	71							
			T5M		5,145	3	0	1	73							
			T5W		5,228	3	0	2	74							
			T5LG		5,159	2	0	1	73							
			BLC3		3,584	0	0	1	51							
			BLC4		3,701	0	0	2	52							
			RCCO		3,616	0	0	1	51							
			LCCO		3,616	0	0	1	51							
			AFR		5,257	1	0	1	74							

## Performance Data

### Lumen Output

Lumen values are from photometric tests performed in accordance with IESNA LM-79-08. Data is considered to be representative of configurations shown within the tolerances described within LM-79. Contact factory for performance data on any configurations not shown here.

#### FORWARD OPTICS

Performance Package	LED Count	Drive Current (mA)	Distribution Type	AMBPC (Phosphor Converted)							AMBLW (Limited Wavelength)					
				System Watts	Lumens	B	U	G	LPW		System Watts	Lumens	B	U	G	LPW
P4	40	530	T1S	69W	6,120	1	0	1	89		55W	2,471	0	0	1	45
			T2M		5,669	1	0	2	83			2,289	1	0	1	42
			T3M		5,735	1	0	3	83			2,316	1	0	1	42
			T3LG		5,123	1	0	1	75			2,069	0	0	1	38
			T4M		5,821	1	0	3	85			2,350	1	0	2	43
			T4LG		5,294	1	2	1	77			2,138	0	1	1	39
			TFTM		5,861	1	0	3	85			2,367	1	0	1	43
			T5M		5,989	3	0	1	87			2,418	2	0	1	44
			T5W		6,086	3	0	2	89			2,457	2	0	1	45
			T5LG		6,006	2	0	1	87			2,425	1	0	0	44
			BLC3		4,172	0	0	2	61			1,685	0	0	1	31
			BLC4		4,309	0	0	2	63			1,740	0	0	1	32
			RCCO		4,209	0	0	2	61			1,700	0	0	1	31
			LCCO		4,209	0	0	2	61			1,700	0	0	1	31
			AFR		6,120	1	0	1	89			2,471	0	0	1	45
P5	40	700	T1S	91W	7,549	1	0	2	84							
			T2M		6,993	1	0	3	77							
			T3M		7,075	1	0	3	77							
			T3LG		6,319	1	0	1	69							
			T4M		7,180	1	0	3	79							
			T4LG		6,530	1	2	2	71							
			TFTM		7,230	1	0	3	79							
			T5M		7,387	3	0	2	81							
			T5W		7,507	3	0	2	82							
			T5LG		7,409	3	0	1	81							
			BLC3		5,146	0	0	2	56							
			BLC4		5,315	0	0	2	58							
			RCCO		5,192	0	0	2	57							
			LCCO		5,192	0	0	2	57							
			AFR		7,549	1	0	2	84							
P6	40	1050	T1S	139W	9,665	1	0	2	70							
			T2M		8,953	2	0	3	65							
			T3M		9,057	2	0	3	65							
			T3LG		8,090	1	0	2	58							
			T4M		9,192	2	0	3	66							
			T4LG		8,360	1	2	2	60							
			TFTM		9,256	2	0	3	67							
			T5M		9,457	4	0	2	68							
			T5W		9,611	4	0	2	69							
			T5LG		9,485	3	0	1	68							
			BLC3		6,588	0	0	2	47							
			BLC4		6,804	0	0	3	49							
			RCCO		6,647	1	0	2	48							
			LCCO		6,647	1	0	2	48							
			AFR		9,665	1	0	2	70							

## Performance Data

### Lumen Output


Lumen values are from photometric tests performed in accordance with IESNA LM-79-08. Data is considered to be representative of configurations shown within the tolerances described within LM-79. Contact factory for performance data on any configurations not shown here.

#### ROTATED OPTICS



Performance Package	LED Count	Drive Current (mA)	Distribution Type	AMBPC (Phosphor Converted)							AMBLW (Limited Wavelength)					
				System Watts	Lumens	B	U	G	LPW		System Watts	Lumens	B	U	G	LPW
P10	30	530	T1S	52W	4,633	2	0	2	90		41W	1,714	1	0	1	42
			T2M		4,292	3	0	3	83			1,588	1	0	1	39
			T3M		4,341	3	0	3	84			1,606	1	0	1	40
			T3LG		3,878	2	0	2	75			1,435	1	0	1	35
			T4M		4,406	3	0	3	85			1,630	1	0	1	40
			T4LG		4,007	2	0	2	77			1,483	1	0	1	37
			TFTM		4,437	3	0	3	86			1,642	1	0	1	40
			T5M		4,533	3	0	1	88			1,677	1	0	1	41
			T5W		4,606	3	0	1	89			1,705	2	0	1	42
			T5LG		4,546	2	0	1	88			1,682	1	0	0	41
			BLC3		3,158	2	0	2	61			1,169	1	0	1	29
			BLC4		3,261	2	0	2	63			1,207	1	0	1	30
			RCCO		3,187	3	0	3	62			1,179	2	0	2	29
			LCCO		3,186	0	0	1	62			1,179	0	0	1	29
			AFR		4,633	2	0	2	90			1,714	1	0	1	42
P11	30	700	T1S	69W	5,869	2	0	2	85							
			T2M		5,437	3	0	3	79							
			T3M		5,499	3	0	3	79							
			T3LG		4,913	2	0	2	71							
			T4M		5,581	3	0	3	81							
			T4LG		5,076	2	0	2	73							
			TFTM		5,620	3	0	3	81							
			T5M		5,742	3	0	1	83							
			T5W		5,835	3	0	2	84							
			T5LG		5,759	2	0	1	83							
			BLC3		4,000	2	0	2	58							
			BLC4		4,131	3	0	3	60							
			RCCO		4,036	3	0	3	58							
			LCCO		4,036	0	0	1	58							
			AFR		5,869	2	0	2	85							
P12	30	1050	T1S	106W	7,928	3	0	3	75							
			T2M		7,344	3	0	3	70							
			T3M		7,428	3	0	3	70							
			T3LG		6,636	2	0	2	63							
			T4M		7,539	3	0	3	71							
			T4LG		6,857	2	0	2	65							
			TFTM		7,592	3	0	3	72							
			T5M		7,757	3	0	2	73							
			T5W		7,882	4	0	2	75							
			T5LG		7,779	3	0	1	74							
			BLC3		5,403	3	0	3	51							
			BLC4		5,581	3	0	3	53							
			RCCO		5,453	3	0	3	52							
			LCCO		5,452	0	0	2	52							
			AFR		7,928	3	0	3	75							





## Dimensions




**DSX0 with RPA, RPA5, SPA5, SPA8N mount**  
Weight: 25 lbs




**DSX0 with WBA mount**  
Weight: 27 lb




**DSX0 with MA mount**  
Weight: 28 lbs




**SPA (STANDARD ARM)**




**RPA**




**SPA5**



**RPA5**





**SPA8N**



## nLight Sensor Coverage Pattern

### NLTAIR2 PIRHN



## FEATURES & SPECIFICATIONS

### INTENDED USE

The sleek design of the D-Series Size 0 reflects the embedded high performance LED technology. It is ideal for many commercial and municipal applications, such as parking lots, plazas, campuses, and pedestrian areas.

### CONSTRUCTION

Single-piece die-cast aluminum housing has integral heat sink fins to optimize thermal management through conductive and convective cooling. Modular design allows for ease of maintenance and future light engine upgrades. The LED driver is mounted in direct contact with the casting to promote low operating temperature and long life. Housing driver compartment is completely sealed against moisture and environmental contaminants (IP66). Vibration rated per ANSI C136.31 for 3G. Low EPA (0.44 ft²) for optimized pole wind loading.

### FINISH

Exterior parts are protected by a zinc-infused Super Durable TGIC thermoset powder coat finish that provides superior resistance to corrosion and weathering. A tightly controlled multi-stage process ensures a minimum 3 mils thickness for a finish that can withstand extreme climate changes without cracking or peeling. Available in both textured and non-textured finishes.

### COASTAL CONSTRUCTION (CCE)

Optional corrosion resistant construction is engineered with added corrosion protection in materials and/or pre-treatment of base material under super durable paint. Provides additional corrosion protection for applications near coastal areas. Finish is salt spray tested to over 5,000 hours per ASTM B117 with scribe rating of 10. Additional lead-times may apply.

### OPTICS

Precision-molded proprietary silicone lenses are engineered for superior area lighting distribution, uniformity, and pole spacing. The D-Series Size 0 has zero uplight and qualifies as a Nighttime Friendly™ product, meaning it is consistent with the LEED® and Green Globes™ criteria for eliminating wasteful uplight.

### ELECTRICAL

Light engine(s) configurations consist of amber LEDs mounted to metal-core circuit boards to maximize heat dissipation and promote long life. Class 1 electronic drivers are designed to have a power factor >90%, THD <20%, and an expected life of 100,000 hours with <1% failure rate. Easily serviceable 10kV surge protection device meets a minimum Category C Low operation (per ANSI/IEEE C62.41.2).

### STANDARD CONTROLS

The DSX0 LED area luminaire has a number of control options. DSX Size 0, comes standard with 0-10V dimming driver. Dusk to dawn controls can be utilized via optional NEMA twist-lock photocell receptacles. PIR integrated motion sensor with on-board photocell feature field-adjustable programming and are suitable for mounting heights up to 40 feet. Control option BL features a bi-level device that allows a second control circuit to switch all light engines to either 30% or 50% light output.

### nLIGHT AIR CONTROLS

The DSX0 LED area luminaire is also available with nLight® AIR for the ultimate in wireless control. This powerful controls platform provides out-of-the-box basic motion sensing and photocontrol functionality and is suitable for mounting heights up to 40 feet. Once commissioned using a smartphone and the easy-to-use CLAIRITY app, nLight AIR equipped luminaires can be grouped, resulting in motion sensor and photocell group response without the need for additional equipment. Scheduled dimming with motion sensor over-ride can be achieved when used with the nLight Eclipse. Additional information about nLight Air can be found [here](#).

### INSTALLATION

Integral mounting arm allows for fast mounting using Lithonia standard #8 drilling and accommodates pole drilling's from 2.41 to 3.12" on center. The standard "SPA" option for square poles and the "RPA" option for round poles use the #8 drilling. For #5 pole drillings, use SPA5 or RPA5. Additional mountings are available including a wall bracket (WBA) and mast arm (MA) option that allows luminaire attachment to a 2 3/8" horizontal mast arm.

### LISTINGS

UL listed to meet U.S. and Canadian standards. UL Listed for wet locations. Light engines are IP66 rated; luminaire is IP66 rated. Rated for -40°C minimum ambient.

### GOVERNMENT PROCUREMENT

BAA – Buy America(n) Act: Product with the BAA option qualifies as a domestic end product under the Buy American Act as implemented in the FAR and DFARS. Product with the BAA option also qualifies as manufactured in the United States under DOT Buy America regulations.

BABA – Build America Buy America: Product with the BAA option also qualifies as produced in the United States under the definitions of the Build America, Buy America Act.

Please refer to [www.acuitybrands.com/buy-american](http://www.acuitybrands.com/buy-american) for additional information.

### WARRANTY

5-year limited warranty. This is the only warranty provided and no other statements in this specification sheet create any warranty of any kind. All other express and implied warranties are disclaimed. Complete warranty terms located at: [www.acuitybrands.com/support/warranty/terms-and-conditions](http://www.acuitybrands.com/support/warranty/terms-and-conditions)

**Note:** Actual performance may differ as a result of end-user environment and application. All values are design or typical values, measured under laboratory conditions at 25 °C. Specifications subject to change without notice.

## FEATURES & SPECIFICATIONS

**INTENDED USE** — The 3" Wafer-Thin LED recessed downlight with remote driver box combines high quality light output and efficiency while eliminating the pot light housing for competitive affordability. This innovative wafer-slim Type IC design allows easy installation for new construction or remodel from below the ceiling without the requirement of a pot light housing for insulation. The LED module maintains at least 70% light output for 36,000 hours. These LED Wafer downlights are intended for closets, attics, hallways, bathrooms, kitchens, basements, soffits, entry ways, porches, garages, stairwells, corridors, nursing/retirement homes, condos, elevators, apartments, and any other small areas.

**CONSTRUCTION** — IC rated driver and fixture - approved for direct contact with insulation. Aluminum die cast outer frame. Durable, powder coat paint to prevent rust. Round fixture with integral edge-lit LED's. Plenum rated cable connector to connect from module to remote driver box. Isolated driver integrated inside steel remote box with four 7/8" knockouts with slots for pryout. Suitable for pulling wires with the 12 cubic-inch wiring compartment to accommodate up to (8) 14 gauge insulated conductors, or (6) 12 gauge insulated conductors; making the Wafer LED Downlights much easier to wire in 2in/2out (plus ground) daisy-chain applications and contractor friendly.

**INSTALLATION** — Ideal for shallow ceiling plenum; no housing required. Steel spring clip for easy installation. 3" cut out template is provided to ensure a correct sized hole is cut into ceiling for proper installation of the trim. Size of hole should not exceed 3 1/8 inches for this product. Suitable for installation in t-grid and drop ceiling applications. 6" plenum space required for installation of remote driver box.

**OPTICS** — Wafer-Thin downlight edge-lit LED technology uses light guided plate to distribute light. Polycarbonate lens provides even illumination throughout the space. Utilizes 2700K, 3000K, and 4000K color temperature LEDs.

**ELECTRICAL** — Connect directly to 120V power supply via provided UL recognized driver. Driver and Fixture Wet location approved and IC rated. High efficient driver with power factor > 0.9. Ambient operating temperature: -40°F (-40°C) to +104°F (+40°C). Dimming down to 10% (See page 2 for recommended dimmers). Standard input wattage is 8W, 68 lumens per watt. Actual wattage may differ by +/- 5% when operating at 120V +/- 10%. Replaces 50W incandescent.

**LISTINGS** — CSA certified to US and Canadian safety standards. ENERGY STAR® qualified. Wet location. Air Tight certified in accordance with ASTM E283-2004. NOM certified.

**WARRANTY** — 5-year limited warranty. Complete warranty terms located at:

[www.acuitybrands.com/support/warranty/terms-and-conditions](http://www.acuitybrands.com/support/warranty/terms-and-conditions)




**Note:** Actual performance may differ as a result of end-user environment and application.

All values are design or typical values, measured under laboratory conditions at 25 °C.

Specifications subject to change without notice.

### Specifications

Aperture:	2.2 (5.6)
Ceiling opening:	3 (7.6)
Overlap trim:	3.4 (8.6)
Height:	1.1 (2.8)



All dimensions are in inches (centimeters) unless otherwise indicated.

## Wafer LED Recessed Downlight

# WF3 3" LED Module

IC/Non-IC

New Construction/Remodel



Matte black



Brushed nickel



Oil-rubbed bronze

### ORDERING INFORMATION

For shortest lead times, configure product using **standard options (shown in bold)**.

**Example: WF3 LED 30K MW**

WF3	LED		
Series	Lamp	CCT/CRI/W/Lumens <sup>1</sup>	Finish
<b>WF3</b> 3" wafer-thin LED downlight	<b>LED</b> LED	<b>27K<sup>2</sup></b> 2700K/80CRI/8W/540L <b>30K</b> 3000K/80CRI/8W/550L <b>40K</b> 4000K/80CRI/7.9W/590L	<b>MW</b> Matte white <b>MB</b> Matte black <b>BN</b> Brushed nickel <b>ORB</b> Oil-rubbed bronze

### Accessories: Order as separate catalog number.

WF3 PAN R12	3" new construction pan, retail pack of 12
WFEXC6 U	6' FT4 cable
WFEXC10 U	10' FT4 cable
WFEXC20 U	20' FT4 cable



WF3\_Pan



Extension Cable

### Notes

- Total system delivered lumens.
- Available in Matte White only.




WF3 3" LED Wafer Module


PHOTOMETRICS

Distribution Curve	Distribution Data	Output Data	Coefficient of Utilization	Illuminance Data at 30" Above Floor for a Single Luminaire
--------------------	-------------------	-------------	----------------------------	--


WF3 LED 27K, 2700 K LEDs, 8 watts, 545 lumens, 68.1 lm/w, test no. ISF 30891P2



WF3 LED 30K, 3000 K LEDs, 8 watts, 550 lumens, 68.8 lm/w, test no. ISF 30891



WF3 LED 40K, 4000 K LEDs, 7.9 watts, 590 lumens, 74.7 lm/w, test no. ISF 31230




DIMMER COMPATIBILITY

COMPATIBLE DIMMERS					
Leviton	Lutron			Sensorswitch	Synergy/Leviton
6633-PA	Maestro MACL-153M (TX)	Diva/Skylark DVRP-253PCTRP-253P	Panel Module HW/LP-RPM-4A-120	nSP5 PCD 2W	ISD 600 I 120/IPI06
IPL06-LED/INC mode	Maestro Wireless MRF2-6ELV	Skylark CTCL-150	Panel Module HW/LP-RPM-4U-120	nSP5 PCD ELV 120	ISD 400 ELV 120/IPE04
6615-P	Gen 3.0 DVCL-153P (T9)	Caseta Wireless PD-SNE	Grafik QS/Wallbox LQRJ-WPM-6P		
	Maestro MSCL-OP153M	Maestro MACL-LFQ	Grafik Eye 3000 Family HWI-WPM-6D-120		
	Caseta Wireless PD-6WCL	RadioRA2 RRD-6NA	HomeWorksQS / my Room LQSE-4A1-D/ MQSE-4A1-D/MQSE-3A1/MQSE-2A1-D,120V		
	Grafik T GT-SNEM / GTJ-SNEM	HomeWorks HQRD-6NA	Homeworks QS LQSE-4A-120-D		


\*Requires Lutron Smart Bridge L-BDG2-WH for wireless applications (sold separately)

## ENERGY DATA

3" ENERGY DATA - 2700K	
Lumens	540
Color temperature	2700K
CRI	80
Lumens/Watt	67.5
Min. starting temperature	-40°C (-40°F)
EMI/RFI	FCC Title 47 CFR, Part 15, Class B
Sound rating	Class A standards
Input voltage	120V
Total Harmonic Distortion	13.5%
Min. power factor	0.97
Input frequency	50/60 Hz
Rated wattage	8W
Input power	8W
Input current	0.07A




3" ENERGY DATA - 3000K	
Lumens	550
Color temperature	3000K
CRI	80
Lumens/Watt	68.75
Min. starting temperature	-40°C (-40°F)
EMI/RFI	FCC Title 47 CFR, Part 15, Class B
Sound rating	Class A standards
Input voltage	120V
Total Harmonic Distortion	13.5%
Min. power factor	0.97
Input frequency	50/60 Hz
Rated wattage	8
Input power	8W
Input current	0.07A



## ENERGY DATA

3" ENERGY DATA - 4000K	
Lumens	590
Color temperature	4000K
CRI	80
Lumens/Watt	74.68
Min. starting temperature	-40°C (-40°F)
EMI/RFI	FCC Title 47 CFR, Part 15, Class B
Sound rating	Class A standards
Input voltage	120V
Total Harmonic Distortion	13.5%
Min. power factor	0.97
Input frequency	50/60 Hz
Rated wattage	7.9
Input power	7.9W
Input current	0.07A



Catalog Number	WF4 LED 50K
Notes	
Type	LABEL - D

## FEATURES & SPECIFICATIONS

**INTENDED USE** — The 4" Wafer™ LED Downlight with Switchable White provides high-quality light output and efficiency featuring a switch for easy color temperature adjustment - while eliminating the need for recessed housings. The innovative, slim design allows for easy retrofit, remodel or new construction installation from below the ceiling. The Wafer LED downlight is wet location listed – making it ideal for use in a breadth of outdoor residential, hospitality, commercial and multifamily applications. The LED module maintains at least 70% light output for 50,000 hours.

**CONSTRUCTION** — Aluminum die cast outer frame. Durable, powder coat paint to prevent rust. FT4 plenum rated cable connector to connect from module to remote driver box. IC rated driver with convenience and value of two remote selectable color temperature options, each with a setting choice to choose either 2700K, 3000K, and 3500K or 3000K, 4000K, and 5000K using the switch. The isolated driver integrated inside steel remote box with four 7/8" knockouts with slots for pryout. Suitable for pulling wires with the 12 cubic-inch wiring compartment to accommodate up to (6) 14 gauge insulated conductors; making the Wafer LED Downlights much easier to wire in 2in/2out (plus ground) daisy-chain applications and contractor friendly.

**INSTALLATION** — Ideal for shallow ceiling plenum; no housing required. Steel spring clip for easy installation. 4" cut out template is provided to ensure a correct sized hole is cut into ceiling for proper installation of the trim. Size of hole should not exceed 4 1/4 inches for this product. Suitable for installation in t-grid and drop ceiling applications. 3" plenum space required for installation of the remote driver box.

**OPTICS** — Edge-lit LED technology uses light guided plate to distribute light. Polycarbonate lens provides even illumination throughout the space.

**ELECTRICAL** — Connect directly to 120V Class-2 (CAN ICES-005 (B) / NMB-005 (B)) LED driver. High efficient driver with power factor > 0.9. Ambient operating temperature: -40°F (-40°C) to +104°F (+40°C). Dimming down to 10% with most standard incandescent dimmers (see list of approved dimmers). Replaces 65W incandescent for 750 lumens..

**LISTINGS** — CSA certified to US and Canadian safety standards. ENERGY STAR® certified. Wet location. Air Tight certified in accordance with ASTM E283-2004. NOM Certified. Can be used to comply with California Title 24 Part 6 High Efficacy LED light Source Requirements.

**WARRANTY** — 5-year limited warranty. This is the only warranty provided and no other statements in this specification sheet create any warranty of any kind. All other express and implied warranties are disclaimed. Complete warranty terms located at:

[www.acuitybrands.com/support/warranty/terms-and-conditions](http://www.acuitybrands.com/support/warranty/terms-and-conditions)




**Note:** Actual performance may differ as a result of end-user environment and application.

All values are design or typical values, measured under laboratory conditions at 25 °C.

Specifications subject to change without notice.

### Specifications

Aperture:	3.2 (8.1)
Ceiling opening:	4.2 (10.7)
Overlap trim:	4.7 (12.0)
Height:	1.1 (2.8)



All dimensions are in inches (centimeters) unless otherwise indicated.

# Wafer LED Recessed Downlight WF4 4" LED Switchable White Color Temperature

IC/Non-IC  
New Construction/Remodel



### ORDERING INFORMATION

For shortest lead times, configure product using **standard options (shown in bold)**.

**Example:** WF4 LED 30K40K50K 90CRI MW

WF4	LED			
Series	Lamp	CCT/W/Lumens <sup>1</sup>	CRI	Finish
WF4 4" wafer-thin LED downlight	LED LED	<b>27K30K35K</b> 2700K/10.5W/730L 3000K/10.5W/800L 3500K/10.5W/780L <b>30K40K50K</b> 3000K/10.5W/750L 4000K/10.5W/810L 5000K/10.5W/790L	<b>90CRI</b> 90CRI	<b>MW</b> Matte White <b>MB</b> Matte Black <b>BN</b> Brush Nickel <b>ORB</b> Oil-Rubbed Bronze

### Accessories: Order as separate catalog number.

WF8643 Pan U	Universal new construction pan
WFJB U	Remodel joist bar
WFEXC6 SW3PIN FT4	3-Pin 6ft Cable
WFEXC10 SW3PIN FT4	3-Pin 10ft Cable
WFEXC20 SW3PIN FT4	3-Pin 20ft Cable
WF4GR MW JZ	4" round oversized trim ring



WF8643 New Construction Pan



Remodel Joist Bar



WFEXC6 Cable

### Notes


<sup>1</sup> Total system delivered lumens.

# WF4 Switchable White 4" LED Wafer Module


## PHOTOMETRICS

Distribution Curve	Distribution Data	Output Data	Coefficient of Utilization	Illuminance Data at 30" Above Floor for a Single Luminaire
--------------------	-------------------	-------------	----------------------------	--


**WF4 LED 27K30K35K**, 2700 K LEDs, input watts: 11, delivered lumens: 732, LM/W=67, test no. ISF 36826P1




**WF4 LED 27K30K35K**, 3000 K LEDs, input watts: 10, delivered lumens: 830, LM/W=83, test no. ISF 36826P2



**WF4 LED 27K30K35K**, 3500 K LEDs, input watts: 10, delivered lumens: 784, LM/W=78, test no. ISF 36826P3



**WF4 LED 30K40K50K**, 3000 K LEDs, input watts: 11, delivered lumens: 753, LM/W=68, test no. ISF 36826P4






# WF4 Switchable White 4" LED Wafer Module


## PHOTOMETRICS

Distribution Curve	Distribution Data	Output Data	Coefficient of Utilization	Illuminance Data at 30" Above Floor for a Single Luminaire
--------------------	-------------------	-------------	----------------------------	--

WF4 LED 30K40K50K, 4000 K LEDs, input watts: 11, delivered lumens: 840, LM/W=76, test no. ISF 36826P5



WF4 LED 30K40K50K, 5000 K LEDs, input watts: 10, delivered lumens: 791, LM/W=79, test no. ISF 36826P6



## ENERGY DATA

WF4 LED 27K30K35K			
Color Temperature	2700K	3000K	3500K
Lumens	730	800	780
CRI	90	90	90
Rated wattage	10.7	10.1	10.4
Lu/Watts	68.2	79.2	75.0
Min. starting temp	-40°C (-40°F)	-40°C (-40°F)	-40°C (-40°F)
EMI/RFI	FCC Title 47 CFR, Part 15, Class B	FCC Title 47 CFR, Part 15, Class B	FCC Title 47 CFR, Part 15, Class B
Sound rating	Class A Standards	Class A Standards	Class A Standards
Input voltage	120V	120V	120V
Min. power factor	0.97	0.97	0.97
Input frequency	50/60 Hz	50/60 Hz	50/60 Hz
Input power	120V	120V	120V
Input current	0.09A	0.09A	0.09A

WF4 LED 30K40K50K			
Color Temperature	3000K	4000K	5000K
Lumens	750	810	790
CRI	90	90	90
Rated wattage	10.6	10.6	10.1
Lu/Watts	70.8	76.4	78.2
Min. starting temp	-40°C (-40°F)	-40°C (-40°F)	-40°C (-40°F)
EMI/RFI	FCC Title 47 CFR, Part 15, Class B	FCC Title 47 CFR, Part 15, Class B	FCC Title 47 CFR, Part 15, Class B
Sound rating	Class A Standards	Class A Standards	Class A Standards
Input voltage	120V	120V	120V
Min. power factor	0.97	0.97	0.97
Input frequency	50/60 Hz	50/60 Hz	50/60 Hz
Input power	120V	120V	120V
Input current	0.09A	0.09A	0.09A

# WF4 Switchable White 4" LED Wafer Module

## LIGHTING PERFORMANCE DATA



LIGHTING PERFORMANCE DATA DONNÉES SUR LE RENDEMENT DE L'ÉCLAIRAGE	
Light Appearance (CCT) Aspect de la lumière (CCT)	
2700K soft white   blanc doux	
730 lumens   70 lumens per watt	
3000K warm white   blanc chaud	
800 lumens   76 lumens per watt	
3500K neutral white   blanc neutre	
780 lumens   74 lumens per watt	
Watts	10.5
Color Accuracy (CRI) Précision des couleurs (CRI)	90



LIGHTING PERFORMANCE DATA DONNÉES SUR LE RENDEMENT DE L'ÉCLAIRAGE	
Light Appearance (CCT) Aspect de la lumière (CCT)	
3000K warm white   blanc chaud	
750 lumens   71 lumens per watt	
4000K cool white   blanc froid	
810 lumens   77 lumens per watt	
5000K daylight   lumière du jour	
790 lumens   75 lumens per watt	
Watts	10.5
Color Accuracy (CRI) Précision des couleurs (CRI)	90

## FCSL510



Date:

Approved:

Type: **LABEL - E**

Fixture:

Project:

**FCSL510** 12 inch wide IP65 rated exterior recessed cut-off large step light for masonry applications. Corrosion resistant, die-cast aluminum construction, this fixture provides illumination for damp, dry or wet areas.



### SPECIFICATIONS

#### PHYSICAL

dimensions	11.75" W x 13.75" H x 4.75" D
weight	5 lbs
housing	Marine grade, corrosion resistant, heavy gauge aluminum faceplate
lens	Clear glass lens
mounting	Concrete pour, masonry applications
ingress protection	IP65 : dry, damp or wet locations with extruded silicone gasket to seal out contaminants
faceplate finish	Six stage chemical iron phosphate conversion pre-treatment. Polyester powder coat finish, 18 µm Min., 5000hr salt spray test (ASTM B117) compliant with Florida / AAMA 2604 specification.

#### PERFORMANCE

color temperature	2700K	3000K	3500K	4000K	
lumen output	1100 lm				
lifetime	> 70,000 hours / L70 or better				
color consistency	3 SDCM / 85 CRI				
operating temperature	-13°F to 104°F (-25°C to 40°C)				
junction temperature	73°C @ T <sup>a</sup> 25°C				
warranty	5-Year limited warranty (refer to website for details)				

#### ELECTRICAL

input voltage	Universal 120 - 277 VAC   optional: 347 VAC (integral)
power supply	Integral Class II, electronic high-power factor > 94% @ 120V
certifications	ETL / cETL Listed
standards	UL1598/CSA C22.2 No. 250.0; UL 8750/CSA C22.2 No. 250.13/IES LM-79/LM-80
power consumption	43W (1100 lm)
dimming	0-10V (10%)

Due to continuous development and improvements, specifications are subject to change without notice. FC Lighting reserves the right to change lab test details or specifications without notice. Product use certifies agreement to FC terms and conditions.



US Commercial Lighting Manufacturer Since 1982

**Specification Sheet**



# Ordering Information

## PART NUMBER

FCSL510					CRI85	11L					
SERIES	VOLTAGE		CCT		CRI		LUMENS		FINISH		OPTIONS
FCSL510	120V	120 VAC	27K	2700K	CRI85	85 CRI	11L	1100 lm (43W)	BKE	Black	LD 0-10V Dimming (Standard)
	277V	277 VAC	3K	3000K					BRE	Bronze	DWR Drywall Wings (Drywall Applications)
	UNV	120 - 277 VAC	35K	3500K					GRE	Graphite Grey	WPC White Polycarbonate Lens
	347V	347 VAC	4K	4000K					SLE	Silver	LBB Less Back Box (for shipment separate of Back Box)
									WHE	White	
									CCE	Custom Color	

## BACK BOX KITS

**99006C-ETL** Back Box Kit - Complete Back Box shipped in advance of fixture without mounting kit.

## REMOTE DRIVER & BATTERY BACKUP

FCSL510R		UNV			CRI85		11L						
Series		Voltage		CCT		CRI		LUMENS		Finish		Options	
FCSL510R†	UNV	120 - 277 VAC	27K	2700K	CRI85	85 CRI	11L	1100 lm (43W)	BKE	Black	LD	0-10V Dimming (Standard)	
			3K	3000K					BRE	Bronze	DWR	Drywall Wings (Drywall Applications)	
			35K	3500K					GRE	Graphite Grey	WPC	White Polycarbonate Lens	
			4K	4000K					SLE	Silver	BBUR¹	Battery Backup Remote (Indoor)	
									WHE	White	BBUX²	Battery Backup Remote (Outdoor)	
								CCE	Custom Color	N/A	Leave Blank for Remote Driver Only (without Battery Backup)		

† LED DRIVER REMOTE (INDOOR) IP20, IK08, NEMA 1, -20°C to +50°C, 30" MAX Distance with 12AWG.

\*Consult factory for outdoor remote driver only.

<sup>1</sup> LED DRIVER REMOTE (INDOOR) IP20, IK08, NEMA 1, -20°C to +50°C, 30' MAX Distance with 12AWG.

\*Consult factory for outdoor remote driver only.

<sup>1</sup> Battery Back-up & LED Driver Remote (INDOOR), IP20, IK08, NEMA 1, 0°C to +48°C, 30' MAX Distance with 12AWG (w/UNV Option Only)

<sup>2</sup> Battery Back-up & LED Driver Remote (OUTDOOR), IP67, IK10, NEMA 4X, -20°C to +55°C, 30' MAX Distance with 12AWG (w/UNV Option Only)

## Consult Factory for other options and configurations.

To ensure you receive proper configurations for your lighting specifications, contact us directly about any unique application requirements. This may include but not be limited to lumen output, mounting needs, or electrical requirements.


Due to continuous development and improvements, specifications are subject to change without notice. FC Lighting reserves the right to change lab test details or specifications without notice. Product use certifies agreement to FC terms and conditions.

 US Commercial Lighting Manufacturer Since 1982

© FC Lighting 3609 Swenson Ave. • St. Charles, IL • 60174 | fcighting.com | 800.900.1730

Specification Sheet


AG-DM-062923



# Dimensions


## PRODUCT DIMENSIONS - STANDARD PRODUCT

width	11.75" W
height	13.75" H
depth	4.75" D



## MOUNTING - *j-box sold by others*

back box width	10.75" W
back box height	12.75" H
back box depth	4.75" D




back box mounts inside brick masonry: faceplate in front of surface - see installation instructions for proper mounting.

Due to continuous development and improvements, specifications are subject to change without notice. FC Lighting reserves the right to change lab test details or specifications without notice. Product use certifies agreement to FC terms and conditions.



US Commercial Lighting Manufacturer Since 1982






# Photometry

## OPTICAL DISTRIBUTION

lumen output	963 lm @ 4000K
power consumption	43W

Illuminance at a Distance			
	Center Beam fc	Beam Width	
1.7R	34.5 fc	1.6 ft	1.9 ft
3.3R	9.16 fc	3.1 ft	3.6 ft
5.0R	3.99 fc	4.7 ft	5.4 ft
6.7R	2.22 fc	6.3 ft	7.3 ft
8.3R	1.45 fc	7.8 ft	9.0 ft
10.0R	1.00 fc	9.4 ft	10.9 ft
<div> <div></div> Vert. Spread: 50.3°                 <div></div> Horiz. Spread: 57.1°             </div>			



illuminations testing labroatory : Report #1090

Due to continuous development and improvements, specifications are subject to change without notice. FC Lighting reserves the right to change lab test details or specifications without notice. Product use certifies agreement to FC terms and conditions.

 US Commercial Lighting Manufacturer Since 1982


© FC Lighting 3609 Swenson Ave. • St. Charles, IL • 60174 | fcighting.com | 800.900.1730

Specification Sheet


AG-DM-062923

## BATTERY BACK-UPS

**BBUR - BATTERY BACK-UP & LED DRIVER REMOTE (INDOOR), IP20, IK08, NEMA 1, 0°C to +48°C, 30' MAX Distance with 12AWG (w/UNV Option Only)**



**BBUX - BATTERY BACK-UP & LED DRIVER REMOTE (OUTDOOR), IP67, IK10, NEMA 4X, -20°C to +55°C, 30' MAX Distance with 12AWG (w/UNV Option Only)**



Due to continuous development and improvements, specifications are subject to change without notice. FC Lighting reserves the right to change lab test details or specifications without notice. Product use certifies agreement to FC terms and conditions.

# LED-25W Series

## Fixed Output and Dimmable Switch Mode LED Drivers

Thomas Research Products

Rev 09-24-2021

### Electrical Specifications

Input Voltage Range:	100-277 Vac Nom. (90-305 V Min/Max)
Input Over-Voltage:	Can endure 320Vac for 48 Hrs, 350Vac for 2 Hrs
Frequency:	50/60 Hz Nom. (47-63 Hz Min/Max)
Power Factor:	>0.90 @ full load, 100V through 277V
Inrush Current:	< 12A @120Vac, 50% Duration < 750 mSec < 15A @277Vac, 50% Duration < 750 mSec
Input Current (Max):	0.25 Amps max @ 120 Vac
Maximum Power:	25W
Current Accuracy:	± 1% Over input line variation
Load Regulation:	± 3%
THD:	≤ 20% @ full load
Turn-On Delay:	<1.0 Sec. @ full output; 1-4 Sec. @ full dim
Leakage Current:	400 µA Typical
Hold Up Time:	Half Cycle

LABEL - F

LED25W-72-C0350



### Protections

Over-voltage	Output
Over-current	Output
Short Circuit	Auto Recovery

### Environmental Specifications

Max Case Life Temp: (5 year warranty)	72°C
Maximum Case Temp (UL):	90°C
Minimum Starting Temp:	-30°C
Storage Temperature:	-40°C to +85°C
Humidity:	5% to 95%
Cooling:	Convection
Vibration Frequency:	5 to 55 Hz/2g, 30 minutes
Sound Rating:	Class A
MTBF:	482,000 Hours at full load and 40°C ambient conditions per MIL-217F Notice 2
EMC:	FCC 47CFR Part 15 Class B compliant

### Constant Current Models

Model	Current Out (mA ±3%)	Voltage Out Range (Vdc)	Max Power (W)	Typical Efficiency
LED25W-72-C0350-XX	350	24-72	25	86%
LED25W-40-C0350-XX	350	13-40	14	84%
LED25W-28-C0350-XX	350	10-28	9.8	83%
LED25W-62-C0400-XX	400	21-62	24.8	85%
LED25W-56-C0450-XX	450	19-56	25	84%
LED25W-40-C0500-XX	500	13-40	20	84%
LED25W-40-C0620-XX	620	13-40	24.8	84%
LED25W-36-C0700-XX	700	12-36	25	84%
LED25W-28-C0850-XX	850	10-28	23.8	83%
LED25W-24-C1040-XX	1040	8-24	25	83%
LED25W-20-C1250-XX	1250	7-20	25	83%
LED25W-18-C1400-XX	1400	6-18	25	82%
LED25W-16-C1560-XX	1560	6-16	25	82%
LED25W-14-C1750-XX	1750	5-14	24.5	82%
LED25W-12-C2080-XX	2080	4-12	25	81%

-XX indicates dimming options are available. See options at left. Blank = fixed current output

### Constant Voltage Models

Model	Voltage Out (Vdc ±5%)	Current Out Range (mA)	Max Power (W)	Typical Efficiency
LED25W-12 •	12	520-2080	25	81%
LED25W-14	14	438-1750	24.5	82%
LED25W-16	16	390-1560	25	82%
LED25W-18	18	360-1400	25	82%
LED25W-20	20	313-1250	25	83%
LED25W-24 •	24	260-1040	25	83%
LED25W-28	28	213-850	23.8	83%
LED25W-36	36	175-700	25	84%
LED25W-40	40	155-620	24.8	84%
LED25W-56	56	113-450	25	84%
LED25W-62	62	100-400	24.8	85%
LED25W-72	72	88-350	25	86%

- Total Power: 25 Watts
- Input Voltage: 100-277 Vac Nom.
- UL Dry & Damp Location Rated
- High Power Factor
- UL8750 and Class 2 Compliant, as noted
- Constant Current & Constant Voltage with Isolation
- Black Magic Thermal Advantage™ Plastic Housing
- UL Sign Components Manual (S.A.M. Models)

#### Dimming Option:

0-10V & Resistance dimmable models include an extra two wires +Purple/-Pink on the output side. "-D" Compatible with most quality 0-10V wall dimmers. See page 3 for additional specifications.

#### Note:

LED drivers are designed and intended to operate LED loads only. Non-LED loading may be outside the specified design limits of our LED drivers, and therefore cannot be covered by any warranty. If you desire to use our LED drivers to operate non-LED loads please contact us to discuss compatibility.

• Indicates S.A.M.

Class 2: US/Canada

HUBBELL  
Lighting Components

Hubbell Lighting Components • 1225 Bowes Rd • Elgin, IL 60123  
T 847-515-3057 • F 847-515-3047 • hubbelllightingcomponents.com




# LED-25W Series





Fixed Output and Dimmable Switch Mode LED Drivers

**Thomas Research Products**

## Dimensions



## Power Characteristics



Safety Cert.	Standard
UL/CUL	UL8750
CSA	22.2
CE	EN61347
EMC Standard	Notes
EN61000-3-2	
EN61000-3-3	Class C
FCC, 47CFR Part 15	Class B
EN6100-4-5	2KV L-N, 8/20 $\mu\text{sec}$ Surge Protection

**Note:** The area under the life-temperature curve represents where the driver has highly reliable operation within specification. Driver performance may drift out of published specifications as the hours of operation exceed the curve at a given temperature. Higher operating temperatures increase the chances of a failure to function. Other electrical, mechanical and environmental factors affect driver lifetime but are not represented in this calculation.

## UL Conditions of Acceptability

See website for additional information

LED-25W Series



Fixed Output and Dimmable Switch Mode LED Drivers



“-D” Option: 0-10VDC and Resistance Dimming


Parameters	Minimum	Typical	Maximum
Source Current out of 0-10V Purple Wire	0 mA	—	2 mA
Absolute Voltage Range on 0-10V (+) Purple Wire	-2.0V	—	+15V

Typical Dimming Circuit



- Notes:
- 1. 0-10V dimmable version comes with an extra two wires +Purple/-Pink on the output side.
  - 2. Compatible with most 0-10V dimmers. Recommended dimmer is Leviton IP710 or equivalent
  - 3. 0-10V dimmable version is not intended to dim below about 5% @ 0V or 10% @ 1.0V
  - 4. 0-10V dimmable version output will be 100% with Purple/Pink open and minimum with Purple/Pink Shorted.
  - 5. For units manufactured before Date of January 1<sup>st</sup> 2022, the Dim(-) wire will be gray, not pink.






## SITE LOCATOR MAP

REDEVELOPMENT  
521 E. WASHINGTON AVE., MADISON  
UDC SUBMITTAL | 05.13.2024 | #2379







SITE MAP

## CONTEXT IMAGES

REDEVELOPMENT  
521 E. WASHINGTON AVE., MADISON

UDC SUBMITTAL | 05.13.2024 | #2379








# PORCHLIGHT REDEVELOPMENT

521 E. WASHINGTON AVE. MADISON, WI

PROJECT NUMBER: 2379



G 000	COVER SHEET
C001	EXISTING SURVEY
C100	SITE DEMOLITION PLAN
C101	SITE PLAN
C200	GRADING & EROSION PLAN
C201	ARCHITECTURAL SITE PLAN
C202	SITE LIGHTING PLAN
C203	FIRE DEPARTMENT ACCESS PLAN
C204	LOT COVERAGE
C205	USABLE OPEN SPACE
C300	UTILITY PLAN
C400	DETAILS
L100	LANDSCAPE PLAN
L101	PLANT SCHEDULE & LANDSCAPE POINTS WORKSHEET
AC100	LOWER LEVEL PLAN
AC101	LEVEL 01 PLAN
AC101P	LEVEL 01 GARDEN PLAN
AC102	LEVELS 02-07 PLAN
AC108	LEVEL 08 PLAN
AC109	ROOF PLAN
AC201	EXTERIOR ELEVATIONS
AC202	EXTERIOR ELEVATIONS
AC203	EXTERIOR COLOR ELEVATIONS
AC204	EXTERIOR COLOR ELEVATIONS
AC205	BIRD-SAFE COMPLIANCE
AC206	BIRD-SAFE COMPLIANCE
AC901	RENDER VIEW 01
AC902	RENDER VIEW 02
AC903	RENDER VIEW 03
AC904	RENDER VIEW 04
AC905	RENDER VIEW 05
AC906	RENDER VIEW 06
AC907	RENDER VIEW 07
AC908	MATERIAL BOARD
AC909	MATERIAL PROFILES

UNIT - TOTALS DD	
STUDIO	
70	
TOTAL UNITS: 70	

PARKING COUNT - VEHICLES		
LEVEL	TYPE	
LEVEL 01	ADA PARKING STALL	
1		
LEVEL 01	TYP. PARKING STALL	
7		
LEVEL 01: 8		
TOTAL VEHICLE PARKING COUNT: 8		



PARKING COUNT - BIKES		
LEVEL	TYPE	
LEVEL 01	SITE BIKE STALL	
13		
LEVEL 01: 13		
LOWER LEVEL	F.M. BIKE STALL	
46		
LOWER LEVEL	W.M. BIKE STALL	
19		
LOWER LEVEL: 65		
TOTAL BIKE PARKING COUNT: 78		

GROSS AREAS	
LEVEL	GROSS AREA
LOWER LEVEL	4212 SF
LEVEL 01	4015 SF
LEVEL 02	5451 SF
LEVEL 03	5451 SF
LEVEL 04	5451 SF
LEVEL 05	5451 SF
LEVEL 06	5451 SF
LEVEL 07	5451 SF
LEVEL 08	5350 SF
TOTAL AREA	46281 SF

RENTABLE AREAS		
LEVEL	TYPE	AREA
LOWER LEVEL	PROGRAM	1694 SF
LEVEL 01	PROGRAM	2028 SF
LEVEL 02	UNITS	4233 SF
LEVEL 03	UNITS	4233 SF
LEVEL 04	UNITS	4233 SF
LEVEL 05	UNITS	4233 SF
LEVEL 06	UNITS	4233 SF
LEVEL 07	UNITS	4233 SF
LEVEL 08	UNITS	4132 SF
		33251 SF








BEARINGS ARE BASED UPON THE  
WISCONSIN COUNTY COORDINATE  
SYSTEM, DANE ZONE. THE SE R/W  
LINE OF E. WASHINGTON AVENUE  
MEASURED AS BEARING N44°06'33"E

LEGEND


- MONITORING WELL
- MAILBOX
- SIGN
- BOLLARD
- SANITARY MANHOLE
- SEWER CLEANOUT
- GAS METER
- GAS VALVE
- FIRE HYDRANT
- WATER VALVE
- CURB STOP
- INLETS
- STORM MANHOLE
- STORM ROOF DRAIN
- UTILITY POLE
- ELECTRICAL METER
- ELECTRICAL TRANSFORMER
- AIR CONDITIONING UNIT
- STOP LIGHT
- GUY ANCHOR
- LIGHT POLE
- UTILITY PEDESTAL
- WALL LIGHT
- ELECTRIC MANHOLE
- DECIDUOUS TREE OR BUSH
- CONIFEROUS TREE
- BUILDING FOOTPRINT
- EDGE OF CONCRETE
- EDGE OF ASPHALT
- CHAIN LINK FENCE
- RAILING
- SAN SAN
- 6" SAN 6" SAN
- 8" PVC SANITARY SEWER
- 10" PVC SANITARY SEWER
- WAT WAT
- 6" DUCTILE IRON WATER MAIN
- 10" PVC WATER MAIN
- 12" DUCTILE IRON WATER MAIN
- 12" RCP STORM SEWER
- 14" RCP STORM SEWER
- 15" RCP STORM SEWER
- GAS GAS
- NATURAL GAS LINE
- COMM COMM
- ELECTRIC LINE
- ASPHALT PAVEMENT
- CONCRETE PAVEMENT
- CONTOUR MAJOR
- CONTOUR MINOR



MARCH 07<sup>th</sup>, 2024  
REVISED: MARCH 29<sup>th</sup>, 2024

BENCHMARK TABLE

BM - #	ELEVATION	DESCRIPTION
BM - 1	863.74'	NE BOLT OF FIRE HYDRANT LOCATED ON THE SOUTHEAST SIDE OF E. WASHINGTON AVENUE, 60' ± SOUTHWEST OF THE INTERSECTION WITH S. BLAIR STREET.
BM - 2	861.17'	SE BOLT OF FIRE HYDRANT LOCATED ON THE SOUTHWEST SIDE OF N. BLAIR STREET, 40' ± NORTHWEST OF THE INTERSECTION WITH E. WASHINGTON AVENUE.
BM - 3	875.58'	EAST TAG BOLT "BURY 6-4" OF FIRE HYDRANT LOCATED IN THE SOUTH QUADRANT OF E. WASHINGTON AVE. & S. FRANKLIN ST. ON E. WASHINGTON AVE. FRONTAGE.
BM - 4	874.55'	SOUTH TAG BOLT "BURY 1-0" OF FIRE HYDRANT LOCATED IN THE SOUTH QUADRANT OF E. WASHINGTON AVE. & S. FRANKLIN ST. ON S. FRANKLIN ST. FRONTAGE.



Toll Free (800) 242-8511  
Hearing Impaired TDD (800) 542-2289  
www.DiggersHotline.com

WYSER  
ENGINEERING

PREPARED BY:  
MICHAEL S. MARTY  
300 EAST WISCONSIN STREET  
SUITE 100  
WISCONSIN, WI 53572  
(608) 437-1872 (direct)  
(608) 209-5284 (mobile)  
mike.marty@wyserengineering.com  
www.wyserengineering.com

PREPARED FOR:  
JOHN LEJA  
200 E. WASHINGTON AVENUE  
WISCONSIN, WI 53572

SURVEYED BY: MSM  
DRAWN BY: MSM  
REVIEWED BY: ZMR  
APPROVED BY: MSM

THE NE 1/4 OF LOT 3, AND THE NW 106 FEET OF LOT FOUR, BLOCK 116,  
ORIGINAL PLAT OF MADISON, AS RECORDED IN VOLUME A OF PLATS, ON  
PAGE 3, AS DOCUMENT NUMBER 102, DANE COUNTY REGISTER OF DEEDS,  
EXCEPT THAT PART CONVEYED TO THE CITY OF MADISON IN WARRANTY  
DEED RECORDED AS DOCUMENT NUMBER 1823205, DANE COUNTY  
REGISTER OF DEEDS, LOCATED IN THE NE 1/4-SW 1/4 AND THE SE 1/4-SW 1/4 ALL  
IN FRACTIONAL SECTION 13, TOWNSHIP 07 NORTH, RANGE 09 EAST, IN THE  
CITY OF MADISON, DANE COUNTY, WISCONSIN

Sheet Title:  
**ALTA/NSPS LAND TITLE SURVEY**

521 E. WASHINGTON AVENUE  
MADISON, WI 53703

Revisions:		
No.	Date:	Description:
1	03/29/24	Update Caption and Monumentation Found on Block 116

Graphic Scale  
SCALE: 1"=10' (22"x34"); 1"=20' (11"x17")

Wyser Number	241199
Set Type	ALTA
Date Issued	03/29/2024
Sheet Number	C001












File: W:\2024\241199\_John Leja - Blair & E. Wash. Madison.dwg 241199\_Civil Design.dwg Layout: Grading Plan User: Adam Plotted: Jul 18, 2024 - 8:05am



**LEGEND (PROPOSED)**

- PROPERTY BOUNDARY
- EASEMENT
- BUILDING FOOTPRINT
- 18" CURB AND GUTTER
- PERVIOUS CONCRETE PAVEMENT
- CONCRETE PAVEMENT
- 860 - PROPOSED MAJOR CONTOUR
- 861 - PROPOSED MINOR CONTOUR
- STM - PROPOSED STORM SEWER
- SILT FENCE
- INLET PROTECTION
- SPOT GRADE
- DRAINAGE GRADE BREAK
- DRAINAGE ARROW

**GENERAL NOTES**

- UNDERLYING SITE CONTOURS AND INFORMATION BASED ON TOPOGRAPHIC & UTILITY DATA AS SURVEYED BY WYSER ENGINEERING ON FEBRUARY 9 AND 20, 2024. WYSER ENGINEERING SHALL NOT BE HELD RESPONSIBLE FOR ANY ERRORS OR OMISSIONS THAT MAY ARISE AS A RESULT OF ERRONEOUS OR INCOMPLETE INFORMATION PROVIDED BY OTHERS. CONTRACTOR TO CONFIRM ALL ELEVATIONS, GENERAL DRAINAGE AND EARTHWORK REQUIREMENTS PRIOR TO CONSTRUCTION.
- THE BENCHMARK LOCATIONS ARE SHOWN FOR REFERENCE ONLY ON THIS PLAN. THE BENCHMARKS SHALL BE VALIDATED BY LICENSED LAND SURVEYOR PRIOR TO CONSTRUCTION. CONTRACTOR ASSUMES RISK ASSOCIATED WITH BENCHMARK ELEVATIONS UNTIL CONFIRMED.
- CONTRACTOR TO OBTAIN APPROPRIATE PERMITS FOR STREET OPENINGS & TO WORK WITHIN THE CITY'S LAND IF REQUIRED.
- WYSER ENGINEERING SHALL BE HELD HARMLESS AND DOES NOT WARRANT ANY DEVIATIONS BY THE OWNER OR CONTRACTOR FROM THE APPROVED CONSTRUCTION PLANS THAT MAY RESULT IN DISCIPLINARY ACTIONS BY REGULATORY AGENCIES.
- IF ANY ERRORS, DISCREPANCIES, OR OMISSIONS WITHIN THE PLAN BECOME APPARENT, IT SHALL BE BROUGHT TO THE ATTENTION OF THE ENGINEER PRIOR TO CONSTRUCTION SO THAT CLARIFICATION OR REDESIGN MAY OCCUR.
- ALL MUNICIPAL UTILITY CONNECTIONS, WORK IN ROW, PUBLIC OUTLOTS AND PUBLIC EASEMENTS SHALL BE IN ACCORDANCE WITH CITY OF MADISON STANDARD SPECIFICATIONS FOR PUBLIC WORKS CONSTRUCTION.

**CONSTRUCTION SITE EROSION CONTROL REQUIREMENTS**

- POST WDNR CERTIFICATE OF PERMIT COVERAGE AND MUNICIPAL EROSION CONTROL PERMITS ON SITE AND MAINTAIN UNTIL CONSTRUCTION ACTIVITIES HAVE CEASED. THE SITE IS STABILIZED, AND A NOTICE OF TERMINATION IS FILED WITH WDNR.
- KEEP A COPY OF THE CURRENT EROSION CONTROL PLAN ON SITE THROUGHOUT THE DURATION OF THE PROJECT.
- ENGINEER / CITY OF MADISON / WDNR HAS THE RIGHT TO REQUIRE CONTRACTOR TO IMPLEMENT ADDITIONAL EROSION CONTROL MEASURES AS NECESSARY. CONTRACTOR MUST NOTIFY THE CITY OF MADISON BUILDING INSPECTOR TWO (2) WORKING DAYS IN ADVANCE OF ANY SOIL DISTURBANCE ACTIVITIES.
- SUBMIT PLAN REVISIONS OR AMENDMENTS TO THE WDNR AT LEAST 5 DAYS PRIOR TO FIELD IMPLEMENTATION.
- THE SITE CONTRACTOR IS RESPONSIBLE FOR ROUTINE SITE INSPECTIONS AT LEAST ONCE EVERY 7 DAYS AND WITHIN 24 HOURS AFTER A RAINFALL EVENT OF 0.5 INCHES OR GREATER. KEEP INSPECTION REPORTS ON-SITE AND MAKE THEM AVAILABLE UPON REQUEST.
- INSPECT AND MAINTAIN ALL INSTALLED EROSION CONTROL PRACTICES UNTIL THE CONTRIBUTING DRAINAGE AREA HAS BEEN STABILIZED.
- WHEN POSSIBLE: PRESERVE EXISTING VEGETATION (ESPECIALLY ADJACENT TO SURFACE WATERS). MINIMIZE LAND-DISTURBING CONSTRUCTION ACTIVITY ON SLOPES OF 20% OR MORE. MINIMIZE SOIL COMPACTION, AND PRESERVE TOPSOIL.
- REFER TO THE WDNR STORMWATER CONSTRUCTION TECHNICAL STANDARDS AT [http://dnr.wi.gov/topic/stormwater/standards/const\\_standards.html](http://dnr.wi.gov/topic/stormwater/standards/const_standards.html).
- INSTALL PERIMETER EROSION CONTROLS AND ROCK TRACKING PAD CONSTRUCTION ENTRANCE(S) PRIOR TO ANY LAND-DISTURBING ACTIVITIES, INCLUDING CLEARING AND GRUBBING. USE WDNR TECHNICAL STANDARD STONE TRACKING PAD AND TIRE WASHING #1067 FOR ROCK CONSTRUCTION ENTRANCES(S).
- INSTALL INLET PROTECTION PRIOR TO LAND-DISTURBING ACTIVITIES IN THE CONTRIBUTING DRAINAGE AREA AND/OR IMMEDIATELY UPON INLET INSTALLATION. COMPLY WITH WDNR TECHNICAL STANDARD STORM DRAIN INLET PROTECTION FOR CONSTRUCTION SITES #1060 AND DANE COUNTY REQUIREMENTS FOR FRAMED INLET PROTECTION.
- CONTRACTOR TO PROVIDE SOLID LID OR METAL PLATE ON ALL OPEN MANHOLES DURING CONSTRUCTION TO MINIMIZE SEDIMENT FROM ENTERING THE STORM SEWER SYSTEM.
- STAGE CONSTRUCTION GRADING ACTIVITIES TO MINIMIZE THE CUMULATIVE EXPOSED AREA. CONDUCT TEMPORARY GRADING FOR EROSION CONTROL PER WDNR TECHNICAL STANDARD TEMPORARY GRADING PRACTICES FOR EROSION CONTROL #1067.
- PERMITTING OF GROUNDWATER DEWATERING IS THE RESPONSIBILITY OF THE CONTRACTOR. GROUNDWATER DEWATERING IS SUBJECT TO A DNR WASTEWATER DISCHARGE PERMIT AND A DNR HIGH CAPACITY WELL APPROVAL IF CUMULATIVE PUMP CAPACITY IS 15 TO 75 GPM OR MORE.
- PROVIDE ANTI-SCOUR PROTECTION AND MAINTAIN NON-EROSIVE FLOW DURING DEWATERING. PERFORM DEWATERING OF ACCUMULATED SURFACE RUNOFF IN ACCORDANCE WITH WDNR TECHNICAL STANDARD DE-WATERING #1061.
- COMPLETE AND STABILIZE SEDIMENT BASINS/TRAPS OR WET PONDS PRIOR TO MASS LAND DISTURBANCE TO CONTROL RUNOFF DURING CONSTRUCTION. REMOVE SEDIMENT AS NEEDED TO MAINTAIN 3 FEET OF DEPTH TO THE OUTLET, AND PROPERLY DISPOSE OF SEDIMENT REMOVED DURING MAINTENANCE (REFER TO NR 528). CONSTRUCT AND MAINTAIN THE SEDIMENT BASIN PER WDNR TECHNICAL STANDARD SEDIMENT BASIN #1064 AND SEDIMENT TRAP # 1063.
- CONSTRUCT AND PROTECT THE BIO/FILTRATION BASIN AND VEGETATION FROM RUNOFF AND SEDIMENT DURING CONSTRUCTION. REFERENCE THE WDNR TECHNICAL STANDARD BIORETENTION FOR INFILTRATION # 1004.
- INSTALL AND MAINTAIN SILT FENCING PER WDNR TECHNICAL STANDARD SILT FENCE #1056. REMOVE SEDIMENT FROM BEHIND SILT FENCES AND SEDIMENT BARRIERS BEFORE SEDIMENT REACHES A DEPTH THAT IS EQUAL TO ONE-HALF OF THE FENCE AND/OR BARRIER HEIGHT.
- REPAIR BREAKS AND GAPS IN SILT FENCES AND BARRIERS IMMEDIATELY. REPLACE DECOMPOSED STRAW BALES (TYPICAL BALE LIFE IS 3 MONTHS). LOCATE, INSTALL, AND MAINTAIN STRAW BALES PER WDNR TECHNICAL STANDARD DITCH CHECKS #1062.
- INSTALL AND MAINTAIN FILTER SOCKS IN ACCORDANCE WITH WDNR TECHNICAL STANDARD INTERIM MANUFACTURED PERIMETER CONTROL AND SLOPE INTERRUPTION PRODUCTS # 1071.
- IMMEDIATELY STABILIZE STOCKPILES AND SURROUND STOCKPILES AS NEEDED WITH SILT FENCE OR OTHER PERIMETER CONTROL IF STOCKPILES WILL REMAIN INACTIVE FOR 7 DAYS OR LONGER.
- IMMEDIATELY STABILIZE ALL DISTURBED AREAS THAT WILL REMAIN INACTIVE FOR 14 DAYS OR LONGER, BETWEEN SEPTEMBER 15 AND OCTOBER 15: STABILIZE WITH MULCH, TACKIFIER, AND A PERENNIAL SEED MIXED WITH WINTER WHEAT, ANNUAL OATS, OR ANNUAL RYE, AS APPROPRIATE FOR REGION AND SOIL TYPE. OCTOBER 15 THROUGH COLD WEATHER: STABILIZE WITH A POLYMER AND DORMANT SEED MIX, AS APPROPRIATE FOR REGION AND SOIL TYPE.
- STABILIZE AREAS OF FINAL GRADING WITHIN 7 DAYS OF REACHING FINAL GRADE.
- SWEEP/CLEAN UP ALL SEDIMENT/TRASH THAT MOVES OFF-SITE DUE TO CONSTRUCTION ACTIVITY OR STORM EVENTS BEFORE THE END OF THE SAME WORKDAY OR AS DIRECTED BY THE AUTHORITIES WITH JURISDICTION. SEPARATE SWEEP MATERIALS (SOILS AND TRASH) AND DISPOSE OF APPROPRIATELY.
- THE CONTRACTOR IS RESPONSIBLE FOR CONTROLLING DUST PER WDNR TECHNICAL STANDARD DUST CONTROL ON CONSTRUCTION SITES # 1068.
- PROPERLY DISPOSE OF ALL WASTE AND UNUSED BUILDING MATERIALS (INCLUDING GARBAGE, DEBRIS, CLEANING WASTES, OR OTHER CONSTRUCTION MATERIALS) AND DO NOT ALLOW THESE MATERIALS TO BE CARRIED BY RUNOFF INTO THE RECEIVING CHANNEL.
- COORDINATE WITH THE AUTHORITIES WITH JURISDICTION TO UPDATE THE LAND DISTURBANCE PERMIT TO INDICATE THE ANTICIPATED OR LIKELY DISPOSAL LOCATIONS FOR ANY EXCAVATED SOILS OR CONSTRUCTION DEBRIS THAT WILL BE HAULED OFF-SITE FOR DISPOSAL. THE DEPOSITED OR STOCKPILED MATERIAL NEEDS TO INCLUDE PERIMETER SEDIMENT CONTROL MEASURES (SUCH AS SILT FENCE, HAY BALES, FILTER SOCKS, OR COMPACTED EARTHEN BERM).
- FOR NON-CANALIZED FLOW ON DISTURBED OR CONSTRUCTED SLOPES, PROVIDE CLASS I TYPE B EROSION CONTROL MATTING. INSTALL AND MAINTAIN PER WDNR TECHNICAL STANDARD NON-CHANNEL EROSION MAT #1052.
- FOR CHANNELIZED FLOW ON DISTURBED OR CONSTRUCTED AREAS, PROVIDE CLASS II TYPE B EROSION CONTROL MATTING UNLESS OTHERWISE SPECIFIED ON THE PLAN. INSTALL AND MAINTAIN PER WDNR TECHNICAL STANDARD CHANNEL EROSION MAT #1053.
- MAKE PROVISIONS FOR WATERING DURING THE FIRST 8 WEEKS FOLLOWING SEEDING OR PLANTING OF DISTURBED AREAS WHENEVER MORE THAN 7 CONSECUTIVE DAYS OF DRY WEATHER OCCUR.
- THE CONTRACTOR IS RESPONSIBLE FOR COMPLYING WITH ALL APPLICABLE WDNR REMEDIATION AND WASTE MANAGEMENT REQUIREMENTS FOR HANDLING AND DISPOSING OF CONTAMINATED MATERIALS. SITE-SPECIFIC INFORMATION FOR AREAS WITH KNOWN OR SUSPECTED SOIL AND/OR GROUNDWATER CONTAMINATION CAN BE FOUND ON WDNR'S BUREAU OF REMEDIATION AND REDEVELOPMENT RACKING SYSTEM (BRRS) PUBLIC DATABASE AT: <http://dnr.wi.gov/brrs/>.
- INSTALL AND MAINTAIN A CONCRETE WASHOUT BASIN PER EPA 833-F-11-006: <https://www3.epa.gov/npdes/pubs/concretestwashout.pdf>. REQUIRE USE BY ALL CONCRETE CONTRACTORS. LIQUID MAY BE REUSED IN CONCRETE MIXING, EVAPORATED, OR DISPOSED OF AS WASTEWATER.

**WYSER ENGINEERING**

**Toll Free (800) 242-8511 -or- 811**  
Hearing Impaired TDD (800) 542-2289  
[www.DiggersHotline.com](http://www.DiggersHotline.com)

**DIGGERS HOTLINE**

BENCHMARK TABLE		
BM - #	ELEVATION	DESCRIPTION
BM - 1	863.74	NE BOLT OF FIRE HYDRANT LOCATED ON THE SOUTHEAST SIDE OF E. WASHINGTON AVENUE, 40' SOUTHWEST OF THE INTERSECTION WITH S. BLAIR STREET.
BM - 2	861.27	SE BOLT OF FIRE HYDRANT LOCATED ON THE SOUTHWEST SIDE OF S. BLAIR STREET, 40' NORTHWEST OF THE INTERSECTION WITH E. WASHINGTON AVENUE.
BM - 3	875.58	EAST TAG BOLT "BURY 6-0" OF FIRE HYDRANT LOCATED IN THE SOUTH QUADRANT OF E. WASHINGTON AVE. & S. FRANKLIN ST. ON E. WASHINGTON AVE. FRONTAGE.
BM - 4	874.95	SOUTH TAG BOLT "BURY 7-0" OF FIRE HYDRANT LOCATED IN THE SOUTH QUADRANT OF E. WASHINGTON AVE. & S. FRANKLIN ST. ON S. FRANKLIN ST. FRONTAGE.

**GRADING, SEEDING & RESTORATION NOTES**

- ALL GRADES SHOWN ARE FINAL FINISHED SURFACE GRADES.
- AREAS TO BE SEEDED SHALL HAVE A MINIMUM 6 INCHES TOPSOIL UNLESS OTHERWISE NOTED.
- AREAS NOT RESTORED WITH EROSION MATTING OR OTHER STABILIZATION MEASURES SHALL BE STABILIZED WITH MULCH.
- APPLY ANIONIC POLYMER TO DISTURBED AREAS IF EROSION BECOMES PROBLEMATIC.
- CONTRACTOR SHALL CHISEL-PLOW OR DEEP TILL WITH DOUBLE TINES THE STORMWATER MANAGEMENT FACILITY JUST PRIOR TO SEEDING AND MULCHING TO PROMOTE INFILTRATION.
- MULCH SHALL BE WEED-FREE STRAW AND SHALL BE INSTALLED AT THE RATE OF 2 TONS PER ACRE PER SECTION 627 OF "STANDARD SPECIFICATIONS FOR HIGHWAY AND STRUCTURE CONSTRUCTION" (WISDOT 2014)
- PERMANENT SEEDING SHALL NOT OCCUR BETWEEN SEPTEMBER 15TH AND APRIL 15TH. ALTERNATE SEEDING/PLANTING METHODS AND/OR EROSION PROTECTION MAY BE NECESSARY FOR SEEDING/PLANTING THAT OCCURS DURING THAT TIME. COORDINATE WITH THE OWNER AS NECESSARY.
- TEMPORARY STABILIZATION SHALL CONSIST OF ONE OR MORE OF THE FOLLOWING OPTIONS:
  - TEMPORARY SEEDING CONSISTING OF ANNUAL RYE GRASS APPLIED AT A RATE OF 1.5 LBS PER 1000 SQUARE FEET.
  - WISDOT PAL CLASS I TYPE B URBAN EROSION CONTROL MAT.



1. THE APPLICANT SHALL REPLACE ALL SIDEWALK AND CURB AND GUTTER THAT ABUTS THE PROPERTY THAT IS DAMAGED BY THE CONSTRUCTION, OR ANY SIDEWALK AND CURB AND GUTTER WHICH THE CITY ENGINEER DETERMINES NEEDS TO BE REPLACED BECAUSE IT IS NOT AT A DESIRABLE GRADE, REGARDLESS OF WHETHER THE CONDITION EXISTED PRIOR TO BEGINNING CONSTRUCTION.

3. ALL DAMAGE TO THE PAVEMENT ON CITY STREETS, AND ADJACENT TO THIS DEVELOPMENT SHALL BE RESTORED IN ACCORDANCE WITH THE CITY OF MADISON'S PAVEMENT PATCHING CRITERIA.


5. AS DEFINED BY THE SECTION 107.13 OF CITY OF MADISON STANDARD SPECIFICATIONS FOR PUBLIC WORKS CONSTRUCTION: NO EXCAVATION IS PERMITTED WITHIN 5 FEET OF THE TRUNK OF THE STREET TREE OR WHEN CUTTING ROOTS OVER 3 INCHES IN DIAMETER. IF EXCAVATION IS NECESSARY, THE CONTRACTOR SHALL CONTACT MADISON CITY FORESTRY (266-4816) PRIOR TO EXCAVATION. CITY OF MADISON FORESTRY PERSONNEL SHALL ASSESS THE IMPACT TO THE TREE AND TO ITS ROOT SYSTEM PRIOR TO WORK COMMENCING. TREE PROTECTION SPECIFICATIONS CAN BE FOUND ON THE FOLLOWING WEBSITE: [CITYOFMADISON.COM/BUSINESS/PW/SPECS.CFM](http://CITYOFMADISON.COM/BUSINESS/PW/SPECS.CFM)

7. SECTION 107.13(G) OF CITY OF MADISON STANDARD SPECIFICATIONS FOR PUBLIC WORKS CONSTRUCTION ADDRESSES SOIL COMPACTION NEAR STREET TREES AND SHALL BE FOLLOWED BY CONTRACTOR. THE STORAGE OF PARKED VEHICLES, CONSTRUCTION EQUIPMENT, BUILDING MATERIALS REFUSE, EXCAVATED SPOILS OR DUMPING OF POISONOUS MATERIALS ON OR AROUND TREES AND ROOTS WITHIN FIVE (5) FEET OF THE TREE OR WITHIN THE PROTECTION ZONE IS PROHIBITED.

9. STREET TREE PRUNING SHALL BE COORDINATED WITH MADISON FORESTRY AT A MINIMUM OF TWO WEEKS PRIOR TO THE START OF CONSTRUCTION FOR THIS PROJECT. ALL PRUNING SHALL FOLLOW THE AMERICAN NATIONAL STANDARDS INSTITUTE (ANSI) A300 - PART 1 STANDARDS FOR PRUNING.

11. APPROVAL OF PLANS FOR THIS PROJECT DOES NOT INCLUDE ANY APPROVAL TO PRUNE, REMOVE, OR PLANT TREES IN THE PUBLIC RIGHT-OF-WAY. PERMISSION FOR SUCH ACTIVITIES MUST BE OBTAINED FROM THE CITY FORESTER (266-4816).

12. THE PUBLIC RIGHT-OF-WAY IS THE SOLE JURISDICTION OF THE CITY OF MADISON AND IS SUBJECT TO CHANGE AT ANY TIME. NO ITEMS SHOWN ON THIS SITE PLAN IN THE RIGHT-OF-WAY ARE PERMANENT AND MAY NEED TO BE REMOVED AT THE APPLICANTS EXPENSE UPON NOTIFICATION BY THE CITY.



Phone: 8401 Greenway Blvd, STE 900  
608.836.3690 Middleton, WI 53562

PROJECT TITLE

**PORCHLIGHT  
REDEVELOPMENT**

SHEET TITLE  
ARCHITECTURAL  
SITE PLAN

# C201

PROJECT NUMBER 2379

© Knothe & Bruce Architects, LLC





knothe & bruce  
ARCHITECTS

Phone: 8401 Greenway Blvd. STE 900  
608.836.3690 Middleton, WI 53562

ISSUED  
LU & UDC SUBMITTAL - 05-13-2024  
UDC RESUBMITTAL - 07-22-2024

PROJECT TITLE  
**PORCHLIGHT  
REDEVELOPMENT**


521 E. WASHINGTON AVE.  
MADISON, WI  
SHEET TITLE  
**SITE LIGHTING  
PLAN**








SHEET NUMBER

**C202**  
PROJECT NUMBER  
**2379**


© Knothe & Bruce Architects, LLC

LIGHT LEVEL STATISTICS						
DESCRIPTION	SYMBOL	AVG.	MAX.	MIN.	MAX. / MIN.	AVG. / MIN.
Covered Parking	+	1.7 fc	4.1 fc	0.2 fc	13.0:1	5.7:1
Outdoor Seating Area	+	3.0 fc	18.7 fc	0.6 fc	31.2:1	5.0:1
E Wash Entrance Area	+	1.9 fc	4.3 fc	0.0 fc	N/A	N/A
Drive Aisle and Parking Area	+	1.1 fc	4.1 fc	0.2 fc	20.5:1	5.5:1



LUMINAIRE SCHEDULE							
SYMBOL	LABEL	QTY.	MANUF.	CATALOG	DESCRIPTION	FILE	MOUNTING
	A	2	LITHONIA LIGHTING	WPX1 LED P1 30K Mvolt	WPX1 LED wallpack 1500lm 3000K color temperature 120-277 Volts	WPX1_LED_P1_30K_Mvolt.ies	10'-0" ABOVE GRADE ON BUILDING
	B	1	LITHONIA LIGHTING	DSX0 LED P1 AMBLW AMCRI T3M	D-SERIES SIZE 0 AREA LUMINAIRE, P1 PERFORMANCE PACKAGE, FORWARD OPTICS, LIMITED WAVELENGTH AMBER, AMBER CRI, TYPE 3 MEDIUM	DSX0_LED_P1_A_MBLW_AMCRI_T3M.IES	16'-0" POLE ON 2'-0" TALL CONC. BASE
	C	4	LITHONIA LIGHTING	WF3 LED 27K	3" Matte White LED Ultra-Thin Wafer Downlight, 2700K CCT	WF3_LED_27K.ies	9'-3" ABOVE GRADE CANOPY CANS
	D	2	LITHONIA LIGHTING	WF4 LED 50K	4" Ultra-Thin LED Wafer Downlight, 5000K CCT, 120V	WF4_LED_50K.ies	9'-0" ABOVE GRADE CANOPY CANS
	E	3	FC/SSL Lighting	FCSL510	Exterior Die-Cast Aluminum Steplight for Masonry Applications.	L004005FCSL5404K.ies	3'-0" ABOVE GRADE ON BUILDING
	F	N/A	THOMAS RESEARCH PRODUCTS	LED-25W	FIXED OUTPUT AND DIMMABLE SWITCH MODE LED DRIVERS	N/A	1'-6" ABOVE GRADE ON OUTDOOR BENCH
<div><div>EXAMPLE LIGHT FIXTURE DISTRIBUTION</div><div><div><div>ISOLUX CONTOUR = 0.25 FC</div><div>ISOLUX CONTOUR = 0.5 FC</div><div>ISOLUX CONTOUR = 1.0 FC</div><div>LIGHT FIXTURE</div></div></div></div>							





#### FIRE ACCESS DATA

BUILDING PERIMETER	295 LINEAR FEET
26' WIDE AERIAL APPARATUS FIRE LANE	74 LR. FT. REQUIRED (25%) # LR. FT. PROVIDED
20' WIDE FIRE ACCESS LANE	
250' MAX. HOSE LAY FROM 20' FIRE ACCESS LANE	
500' MAX. HOSE LAY FROM HYDRANT TO FAR END OF AERIAL APPARATUS LANE	

ISSUED  
LU & UDC SUBMITTAL - 05-13-2024  
UDC RESUBMITTAL - 07-22-2024

PROJECT TITLE  
**PORCHLIGHT  
REDEVELOPMENT**



521 E. WASHINGTON AVE.  
MADISON, WI  
SHEET TITLE

**FIRE  
DEPARTMENT  
ACCESS PLAN**


SHEET NUMBER

**C203**  
PROJECT NUMBER  
**2379**


© Knothe & Bruce Architects, LLC







LOT COVERAGE	
ZONING	UMX
MAXIMUM LOT COVERAGE	90% (9,474 S.F.)
LOT AREA	10,527 S.F.
PROPOSED COVERAGE	81.5% (8578 S.F.)



ISSUED  
LU & UDC SUBMITTAL - 05-13-2024  
UDC RESUBMITTAL - 07-22-2024



PROJECT TITLE  
**PORCHLIGHT  
REDEVELOPMENT**

521 E. WASHINGTON AVE.  
MADISON, WI  
SHEET TITLE  
**LOT COVERAGE**

SHEET NUMBER

**C204**  
PROJECT NUMBER **2379**

© Knothe & Bruce Architects, LLC























<h1>LEGEND:</h1>	
	<p>PROPERTY LINE</p> <p><math>1\frac{1}{2}</math>" DIAMETER, WASHED, DECORATIVE STONE MULCH</p>
<p>NOTES:</p> <ol style="list-style-type: none"> <li>1. SEE C102 FOR SITE DEMOLITION PLAN.</li> <li>2. SEE C201 FOR SITE PLAN.</li> <li>6. SEE C202 FOR SITE LIGHTING PLAN.</li> <li>7. SEE C203 FOR FIRE ACCESS PLAN.</li> <li>8. SEE C204 FOR LOT COVERAGE PLAN.</li> <li>9. SEE C300 FOR GRADING AND EROSION CONTROL PLAN.</li> <li>10. SEE C400 FOR SITE UTILITIES PLAN.</li> <li>11. ANY NEW TREES WITHIN PUBLIC ROW SHALL BE DETERMINED BY THE CITY FORESTER.</li> <li>12. LAWN AREAS WITHIN STREET TERRACE SHALL BE SEEDED.</li> <li>13. ALL PLANT BEDS SHALL RECEIVE 3" OF SHREDDED HARDWOOD BARK MULCH.</li> </ol>	



knothe ■ bruce  
ARCHITECTS

Phone: 8401 Greenway Blvd. STE 900  
608.836.3690 Middleton, WI 53562



**FIGUREGROUND**  
jporter@figureground-design.com  
608-345-5101

ISSUED  
LU & UDC SUBMITTAL - 05-13-2024  
UDC RESUBMITTAL - 07-22-2024  
  
NOT FOR CONSTRUCTION

PROJECT TITLE

PORCHLIGHT  
REDEVELOPMENT

521 E. WASHINGTON  
AVE. MADISON, WI

---

SHEET TITLE

LANDSCAPE PLAN

SHEET NUMBER

L100  
PROJECT NUMBER 2379

© Knothe & Bruce Architects, LLC



City of Madison, WI Landscape Worksheet - 521 E. Washington Ave.

5/13/2024

Zoning: Regional Mixed-Use (RMX)

Developed Area (SF)	Landscape Points Required	Landscape Points Achieved			
10,527	175	617			
Points Tabulation					
Plant Type/Element	Points	Quantity	Points Achieved		
Overstory deciduous trees	35	2	70		
Tall evergreen trees	35	6	210		
Ornamental trees	15	0	0		
Upright evergreen shrubs	10	3	30		
Shrubs, deciduous	3	15	45		
Shrubs, evergreen	4	0	0		
Ornamental grasses/perennials	2	73	146		
Decorative fencing/wall	4/LF	29	116		
Existing specimen tree	14/cal. inch	0	0		
Landscape furniture (public)	5/seat	0	0		
Total Points Achieved			617		
Development Frontage Landscaping	Frontage (LF)	Overstory Trees Required	Overstory Trees Proposed/Existing	Shrubs Required	Shrubs Proposed/Existing
(1) overstory deciduous tree and (5) shrubs /30 LF					
*(2) ornamental trees or (2) evergreen trees may be used in place of (1) overstory deciduous tree					
E. Washington Ave.	90	3	1.5 (3) evergreen trees]	15	6
S. Blair St.	106	4	1.5 (3) evergreen trees]	18	9

\*Interior Parking Lot Landscaping (for lots with 20 or more parking spaces) - N/A


(No surface parking lots with 20 or more parking spaces)

\*\*In cases where development frontage landscaping cannot be provided due to site constraints, the zoning administrator may waive the requirement or substitute alternative screening methods for the required landscaping.

(Insufficient area for substantial landscaping between building and sidewalks)


PLANT SCHEDULE

SYMBOL	CODE	BOTANICAL NAME	COMMON NAME	SIZE	STOCK	HEIGHT	QTY
EVERGREEN TREES							
	JVT	Juniperus virginiana 'Taylor'	Taylor Eastern Redcedar	See Height	B&B	8'	6
OVERSTORY DECIDUOUS TREES							
	GD	Gleditsia triacanthos inermis 'Draves'	Street Keeper® Honey Locust	3" Cal.	B&B	12'	2
DECIDUOUS SHRUBS							
	Dxko	Diervilla x 'Kodiak Orange'	Kodiak® Orange Diervilla	#2	Container	24"	7
	Hpl	Hydrangea paniculata 'Limelight'	Limelight Panicle Hydrangea	#5	Container	42"	1
	Sjg	Spiraea japonica 'Goldmound'	Goldmound Japanese Spirea	#3	Container	24"	7
EVERGREEN SHRUBS							
	Tbj	Thuja occidentalis 'BailJohn' TM	Technito Arborvitae	#5	Container	48"	3
GRASSES & SEDGES							
	cff	Carex x 'FeatherFalls'	Feather Falls Sedge	#1	Container	N/A	11
	msg	Miscanthus sinensis 'Gracillimus'	Gracillimus Eulalia Grass	#1	Container	N/A	11
HERBACEOUS PERENNIALS							
	cmw	Calamintha nepeta 'Montrose White'	Montrose White Calamint	#1	Container	N/A	12
	gxd	Geranium x 'Dilys'	Dilys Geranium	#1	Container	N/A	12
	hhr	Hemerocallis x 'Happy Returns'	Happy Returns Daylily	#1	Container	N/A	13
	nfpb	Nepeta x faassenii 'Purrsian Blue'	Purrsian Blue Catmint	#1	Container	N/A	13
	pals	Perovskia atriplicifolia 'Little Spire' TM	Little Spire Russian Sage	#1	Container	N/A	6
VINES							
	adp	Aristolochia durior	Dutchman's Pipe	#1	Container	N/A	8
	cnm	Clematis x 'Nelly Moser'	Nelly Moser Clematis	#1	Container	N/A	6



knothe & bruce  
ARCHITECTS

Phone: 608.836.3690 8401 Greenway Blvd, STE 900  
Middleton, WI 53562



FIGUREGROUND  
jporter@figureground-design.com  
608-345-5101

ISSUED  
LU & UDC SUBMITTAL - 05-13-2024  
UDC RESUBMITTAL - 07-22-2024  
NOT FOR CONSTRUCTION

PROJECT TITLE  
PORCHLIGHT  
REDEVELOPMENT

521 E. WASHINGTON  
AVE. MADISON, WI

SHEET TITLE  
PLANT SCHEDULE  
& LANDSCAPE  
POINTS  
WORKSHEET

SHEET NUMBER

L101  
PROJECT NUMBER 2379



knothe ■ bruce  
ARCHITECTS

Phone: 8401 Greenway Blvd, Suite 900  
608.836.3690 Middleton, WI 53562

ISSUED  
LU & UDC SUBMITTAL - 05-13-2024  
UDC RESUBMITTAL - 07-22-2024

PROJECT TITLE  
PORCHLIGHT  
REDEVELOPMENT


521 E. WASHINGTON  
AVE. MADISON, WI  
SHEET TITLE  
LOWER LEVEL  
PLAN

SHEET NUMBER

AC100

PROJECT NUMBER  
2379

© Knothe & Bruce Architects, LLC



1 LOWER LEVEL PLAN  
AC100 1/4" = 1'-0"



ISSUED  
LU & UDC SUBMITTAL - 05-13-2024  
UDC RESUBMITTAL - 07-22-2024


PROJECT TITLE  
**PORCHLIGHT  
REDEVELOPMENT**

521 E. WASHINGTON  
AVE. MADISON, WI  
SHEET TITLE  
**LEVEL 01 PLAN**


SHEET NUMBER  
**AC101**  
PROJECT NUMBER  
**2379**



1 LEVEL 01 PLAN  
AC101 1/4" = 1'-0"







L-SHAPED LED BENCH




RAISED PLANTER w/ VINE TRELLIS



GARDEN RENDER VIEW

ISSUED  
LU & UDC SUBMITTAL - 05-13-2024  
UDC RESUBMITTAL - 07-22-2024



1 LEVEL 01 PLAZA PLAN  
AC101P 1/2" = 1'-0"

PROJECT TITLE  
**PORCHLIGHT  
REDEVELOPMENT**

521 E. WASHINGTON  
AVE. MADISON, WI  
SHEET TITLE  
**LEVEL 01 GARDEN  
PLAN**

SHEET NUMBER  
**AC101P**  
PROJECT NUMBER  
**2379**





knothe ■ bruce  
ARCHITECTS

Phone: 8401 Greenway Blvd, Suite 900  
608.836.3690 Middleton, WI 53562

ISSUED  
LU & UDC SUBMITTAL - 05-13-2024  
UDC RESUBMITTAL - 07-22-2024

PROJECT TITLE  
PORCHLIGHT  
REDEVELOPMENT

521 E. WASHINGTON  
AVE. MADISON, WI  
SHEET TITLE  
LEVELS 02-07  
PLAN


SHEET NUMBER

AC102


PROJECT NUMBER

2379

© Knothe & Bruce Architects, LLC



1 LEVELS 02-07 PLAN  
AC102 1/4" = 1'-0"





knothe ■ bruce  
ARCHITECTS

Phone: 8401 Greenway Blvd, Suite 900  
608.836.3690 Middleton, WI 53562

ISSUED  
LU & UDC SUBMITTAL - 05-13-2024  
UDC RESUBMITTAL - 07-22-2024

PROJECT TITLE  
PORCHLIGHT  
REDEVELOPMENT


521 E. WASHINGTON  
AVE. MADISON, WI  
SHEET TITLE  
LEVEL 08 PLAN

SHEET NUMBER


AC108

PROJECT NUMBER  
2379

© Knothe & Bruce Architects, LLC



1 LEVEL 08 PLAN  
AC108 1/4" = 1'-0"





knothe & bruce  
ARCHITECTS

Phone: 608.836.3690 8401 Greenway Blvd, Suite 900 Middleton, WI 53562

ISSUED  
LU & UDC SUBMITTAL - 05-13-2024  
UDC RESUBMITTAL - 07-22-2024

PROJECT TITLE  
PORCHLIGHT  
REDEVELOPMENT

521 E. WASHINGTON  
AVE. MADISON, WI  
SHEET TITLE  
ROOF PLAN


SHEET NUMBER

AC109

PROJECT NUMBER


2379

© Knothe & Bruce Architects, LLC



1 ROOF PLAN  
AC109 1/4" = 1'-0"





EXTERIOR MATERIAL SCHEDULE			
MARK	BUILDING ELEMENT	MANUFACTURER	COLOR
1A	MTL HORIZONTAL REVEAL PANEL	PAC-CLAD	SLATE GRAY
1B	MTL HORIZONTAL REVEAL PANEL	PAC-CLAD	COLONIAL RED
3	STANDING SEAM VERTICAL SIDING	PAC-CLAD	MIDNIGHT-BRONZE
4	BOX RIB 1 - SCREEN WALL	PAC-CLAD	SLATE GRAY
5	BRICK VENEER	SUMMIT BRICK	THISTLEDOWN
6	BRICK VENEER - SOLDIER COURSE	SUMMIT BRICK	THISTLEDOWN
7	CAST STONE BANDS & SILLS	ROCKCAST	RIESLING
8	COMPOSITE WINDOWS	TBD	DARK BRONZE
9	ALUM. STOREFRONT	TBD	DARK BRONZE
10	CABLE GUARD RAILING	TBD	DARK BRONZE

ELEVATION NOTES:

1. HATCH INDICATES BIRD-SAFE GLAZING:

2. HATCH INDICATES FROSTED GLASS:

ISSUED  
LU & UDC SUBMITTAL - 05-13-2024  
UDC RESUBMITTAL - 07-22-2024

PROJECT TITLE  
PORCHLIGHT  
REDEVELOPMENT

521 E. WASHINGTON  
AVE. MADISON, WI  
SHEET TITLE  
EXTERIOR  
ELEVATIONS

SHEET NUMBER

AC201

PROJECT NUMBER  
2379





knothe & bruce  
ARCHITECTS

Phone: 608.836.3690 8401 Greenway Blvd, Suite 900 Middleton, WI 53562

ISSUED  
LU & UDC SUBMITTAL - 05-13-2024  
UDC RESUBMITTAL - 07-22-2024

PROJECT TITLE  
PORCHLIGHT  
REDEVELOPMENT

521 E. WASHINGTON  
AVE. MADISON, WI  
SHEET TITLE  
EXTERIOR  
ELEVATIONS

SHEET NUMBER

AC202

PROJECT NUMBER

2379

© Knothe & Bruce Architects, LLC



2 CITY ELEVATION - SOUTH WEST  
1/8" = 1'-0"



1 CITY ELEVATION - SOUTH EAST  
1/8" = 1'-0"

EXTERIOR MATERIAL SCHEDULE			
MARK	BUILDING ELEMENT	MANUFACTURER	COLOR
1A	MTL HORIZONTAL REVEAL PANEL	PAC-CLAD	SLATE GRAY
1B	MTL HORIZONTAL REVEAL PANEL	PAC-CLAD	COLONIAL RED
3	STANDING SEAM VERTICAL SIDING	PAC-CLAD	MIDNIGHT-BRONZE
4	BOX RIB 1 - SCREEN WALL	PAC-CLAD	SLATE GRAY
5	BRICK VENEER	SUMMIT BRICK	THISTLEDOWN
6	BRICK VENEER - SOLDIER COURSE	SUMMIT BRICK	THISTLEDOWN
7	CAST STONE BANDS & SILLS	ROCKCAST	RIESLING
8	COMPOSITE WINDOWS	TBD	DARK BRONZE
9	ALUM. STOREFRONT	TBD	DARK BRONZE
10	CABLE GUARD RAILING	TBD	DARK BRONZE

ELEVATION NOTES:	
1. HATCH INDICATES BIRD-SAFE GLAZING:	
2. HATCH INDICATES FROSTED GLASS:	

ISSUED  
LU & UDC SUBMITTAL - 05-13-2024  
UDC RESUBMITTAL - 07-22-2024

PROJECT TITLE  
PORCHLIGHT  
REDEVELOPMENT

521 E. WASHINGTON  
AVE. MADISON, WI  
SHEET TITLE  
EXTERIOR COLOR  
ELEVATIONS

SHEET NUMBER

AC203  
PROJECT NUMBER  
2379



2 CITY ELEVATION - NORTH EAST COLOR  
AC203 1/8" = 1'-0"



1 CITY ELEVATION - NORTH WEST COLOR  
AC203 1/8" = 1'-0"

EXTERIOR MATERIAL SCHEDULE			
MARK	BUILDING ELEMENT	MANUFACTURER	COLOR
1A	MTL HORIZONTAL REVEAL PANEL	PAC-CLAD	SLATE GRAY
1B	MTL HORIZONTAL REVEAL PANEL	PAC-CLAD	COLONIAL RED
3	STANDING SEAM VERTICAL SIDING	PAC-CLAD	MIDNIGHT-BRONZE
4	BOX RIB 1 - SCREEN WALL	PAC-CLAD	SLATE GRAY
5	BRICK VENEER	SUMMIT BRICK	THISTLEDOWN
6	BRICK VENEER - SOLDIER COURSE	SUMMIT BRICK	THISTLEDOWN
7	CAST STONE BANDS & SILLS	ROCKCAST	RIESLING
8	COMPOSITE WINDOWS	TBD	DARK BRONZE
9	ALUM. STOREFRONT	TBD	DARK BRONZE
10	CABLE GUARD RAILING	TBD	DARK BRONZE

ELEVATION NOTES:

1. HATCH INDICATES BIRD-SAFE GLAZING:

2. HATCH INDICATES FROSTED GLASS:



ISSUED  
LU & UDC SUBMITTAL - 05-13-2024  
UDC RESUBMITTAL - 07-22-2024

PROJECT TITLE  
PORCHLIGHT  
REDEVELOPMENT

521 E. WASHINGTON  
AVE. MADISON, WI  
SHEET TITLE  
EXTERIOR COLOR  
ELEVATIONS

SHEET NUMBER

AC204

PROJECT NUMBER  
2379



1 CITY ELEVATION - SOUTH EAST COLOR  
1/8" = 1'-0"



2 CITY ELEVATION - SOUTH WEST COLOR  
1/8" = 1'-0"

EXTERIOR MATERIAL SCHEDULE			
MARK	BUILDING ELEMENT	MANUFACTURER	COLOR
1A	MTL HORIZONTAL REVEAL PANEL	PAC-CLAD	SLATE GRAY
1B	MTL HORIZONTAL REVEAL PANEL	PAC-CLAD	COLONIAL RED
3	STANDING SEAM VERTICAL SIDING	PAC-CLAD	MIDNIGHT-BRONZE
4	BOX RIB 1 - SCREEN WALL	PAC-CLAD	SLATE GRAY
5	BRICK VENEER	SUMMIT BRICK	THISTLEDOWN
6	BRICK VENEER - SOLDIER COURSE	SUMMIT BRICK	THISTLEDOWN
7	CAST STONE BANDS & SILLS	ROCKCAST	RIESLING
8	COMPOSITE WINDOWS	TBD	DARK BRONZE
9	ALUM. STOREFRONT	TBD	DARK BRONZE
10	CABLE GUARD RAILING	TBD	DARK BRONZE

ELEVATION NOTES:

1. HATCH INDICATES BIRD-SAFE GLAZING:

2. HATCH INDICATES FROSTED GLASS:



2 NORTH EAST - BIRD-SAFE GLAZING  
1/8" = 1'-0"


FOR NON-RESIDENTIAL USES AT GROUND FLOOR LEVEL, WINDOWS AND DOORS OR OTHER OPENINGS SHALL COMPRISE AT LEAST SIXTY PERCENT (60%) OF THE LENGTH AND AT LEAST (40%) OF THE AREA OF THE GROUND FLOOR OF THE PRIMARY STREET FACADE. AT LEAST FIFTY PERCENT (50%) OF THE WINDOWS ON THE PRIMARY STREET FACADE SHALL HAVE THE LOWER SILL WITHIN THREE (3) FEET OF GRADE. FOR RESIDENTIAL USES AT GROUND LEVEL, A MINIMUM OF FIFTEEN PERCENT (15%) OF THE GROUND LEVEL OF RESIDENTIAL FACADES OR SIDE AND REAR FACADES NOT FRONTING A PUBLIC STREET SHALL CONSIST OF WINDOWS AND DOOR OPENINGS. ON UPPER STORIES, WINDOW OR BALCONY OPENINGS SHALL OCCUPY A MINIMUM OF FIFTEEN PERCENT (15%) OF THE UPPER-STORY WALL AREA.

GLASS AREA SHALL BE MEASURED AS ONE (1) CONTINUOUS PANEL OF GLASS OR OTHER TRANSPARENT MATERIAL, OR A SET OF TWO (2) OR MORE SUCH PANELS DIVIDED BY MULLIONS OF SIX (6) INCHES IN WIDTH OR NARROWER. PANELS SURROUNDED ON ALL SIDES BY SOLID WALLS OR MULLIONS WIDER THAN SIX (6) INCHES SHALL BE CONSIDERED INDIVIDUAL WINDOWS. SPANDREL OR OPAQUE GLASS WITH REFLECTIVITY OF 14% OR LESS SHALL NOT BE INCLUDED IN THE CALCULATION OF GLASS AREA.

FOR BUILDING FACADES WHERE THE FIST SIXTY (60) FEET FROM GRADE ARE COMPRISED OF LESS THAN FIFTY PERCENT (50%) GLASS:  
A. AT LEAST EIGHTY-FIVE PERCENT (85%) OF THE GLASS ON GLASS AREAS FIFTY (50) SQUARE FEET OR OVER MUST BE TREATED; AND  
B. OF ALL GLASS AREAS OVER FIFTY (50) SQUARE FEET, ANY GLASS WITHIN FIFTEEN (15) FEET OF A BUILDING CORNER MUST BE TREATED

FOR BUILDINGS AND STRUCTURES OF ANY SIZE, ALL AT-GRADE GLASS FEATURES SUCH AS SOUND WALLS OR GLASS SCREENS MUST BE TREATED.

- INDICATES BIRD-SAFE GLAZING
- INDICATES BIRD-SAFE GLAZING NOT REQ'D
- INDICATES FROSTED GLAZING



1 NORTH WEST - BIRD-SAFE GLAZING  
1/8" = 1'-0"

FACADE AREA: 4,434 S.F.  
GLASS AREA: 1,006 S.F. (22.7% OF FACADE)  
FIRST FLOOR: 410 S.F. (50% OF FLOOR)  
SECOND-SIXTH FLOOR: 152 S.F. (21.2% OF FLOOR)

ISSUED  
LU & UDC SUBMITTAL - 05-13-2024  
UDC RESUBMITTAL - 07-22-2024

PROJECT TITLE  
PORCHLIGHT  
REDEVELOPMENT

521 E. WASHINGTON  
AVE. MADISON, WI  
SHEET TITLE  
BIRD-SAFE  
COMPLIANCE

SHEET NUMBER

AC205

PROJECT NUMBER

2379





2 SOUTH WEST - BIRD-SAFE GLAZING  
AC206 1/8" = 1'-0"

FOR NON-RESIDENTIAL USES AT GROUND FLOOR LEVEL, WINDOWS AND DOORS OR OTHER OPENINGS SHALL COMPRISE AT LEAST SIXTY PERCENT (60%) OF THE LENGTH AND AT LEAST (40%) OF THE AREA OF THE GROUND FLOOR OF THE PRIMARY STREET FACADE. AT LEAST FIFTY PERCENT (50%) OF THE WINDOWS ON THE PRIMARY STREET FACADE SHALL HAVE THE LOWER SILL WITHIN THREE (3) FEET OF GRADE. FOR RESIDENTIAL USES AT GROUND LEVEL, A MINIMUM OF FIFTEEN PERCENT (15%) OF THE GROUND LEVEL OF RESIDENTIAL FACADES OR SIDE AND REAR FACADES NOT FRONTING A PUBLIC STREET SHALL CONSIST OF WINDOWS AND DOOR OPENINGS. ON UPPER STORIES, WINDOW OR BALCONY OPENINGS SHALL OCCUPY A MINIMUM OF FIFTEEN PERCENT (15%) OF THE UPPER-STORY WALL AREA.

GLASS AREA SHALL BE MEASURED AS ONE (1) CONTINUOUS PANEL OF GLASS OR OTHER TRANSPARENT MATERIAL, OR A SET OF TWO (2) OR MORE SUCH PANELS DIVIDED BY MULLIONS OF SIX (6) INCHES IN WIDTH OR NARROWER. PANELS SURROUNDED ON ALL SIDES BY SOLID WALLS OR MULLIONS WIDER THAN SIX (6) INCHES SHALL BE CONSIDERED INDIVIDUAL WINDOWS. SPANDREL OR OPAQUE GLASS WITH REFLECTIVITY OF 14% OR LESS SHALL NOT BE INCLUDED IN THE CALCULATION OF GLASS AREA.

FOR BUILDING FACADES WHERE THE FIST SIXTY (60) FEET FROM GRADE ARE COMPRISED OF LESS THAN FIFTY PERCENT (50%) GLASS:  
A. AT LEAST EIGHTY-FIVE PERCENT (85%) OF THE GLASS ON GLASS AREAS FIFTY (50) SQUARE FEET OR OVER MUST BE TREATED; AND  
B. OF ALL GLASS AREAS OVER FIFTY (50) SQUARE FEET, ANY GLASS WITHIN FIFTEEN (15) FEET OF A BUILDING CORNER MUST BE TREATED

FOR BUILDINGS AND STRUCTURES OF ANY SIZE, ALL AT-GRADE GLASS FEATURES SUCH AS SOUND WALLS OR GLASS SCREENS MUST BE TREATED.

- INDICATES BIRD-SAFE GLAZING
- INDICATES BIRD-SAFE GLAZING NOT REQ'D
- INDICATES FROSTED GLAZING



1 SOUTH EAST - BIRD-SAFE GLAZING  
AC206 1/8" = 1'-0"

ISSUED  
LU & UDC SUBMITTAL - 05-13-2024  
UDC RESUBMITTAL - 07-22-2024

PROJECT TITLE  
PORCHLIGHT  
REDEVELOPMENT


521 E. WASHINGTON  
AVE. MADISON, WI  
SHEET TITLE  
BIRD-SAFE  
COMPLIANCE

SHEET NUMBER

AC206

PROJECT NUMBER  
2379






VIEW FROM STREET INTERSECTION

PORCHLIGHT REDEVELOPMENT  
521 E. WASHINGTON AVE. MADISON, WI

UDC RESUBMITTAL | 07.22.2024 | #2379









VIEW FROM S. BLAIR STREET





VIEW FROM STREET INTERSECTION





VIEW FROM E. WASHINGTON AVENUE

PORCHLIGHT REDEVELOPMENT  
521 E. WASHINGTON AVE. MADISON, WI

UDC RESUBMITTAL | 07.22.2024 | #2379








## DISTANCE VIEW 1 FROM E. WASHINGTON AVENUE







## DISTANCE VIEW 2 FROM E. WASHINGTON AVENUE

PORCHLIGHT REDEVELOPMENT  
521 E. WASHINGTON AVE. MADISON, WI

UDC RESUBMITTAL | 07.22.2024 | #2379








DISTANCE VIEW 3 FROM WEBSTER ST.

PORCHLIGHT REDEVELOPMENT  
521 E. WASHINGTON AVE. MADISON, WI

UDC RESUBMITTAL | 07.22.2024 | #2379







VIEW FROM INTERSECTION ALONG E. WASHINGTON AVE.

EXTERIOR MATERIAL SCHEDULE			
MARK	BUILDING ELEMENT	MANUFACTURER	COLOR
1A	MTL HORIZONTAL REVEAL PANEL	PAC-CLAD	SLATE GRAY
1B	MTL HORIZONTAL REVEAL PANEL	PAC-CLAD	COLONIAL RED
3	STANDING SEAM VERTICAL SIDING	PAC-CLAD	MIDNIGHT-BRONZE
4	BOX RIB 1 - SCREEN WALL	PAC-CLAD	SLATE GRAY
5	BRICK VENEER	SUMMIT BRICK	THISTLEDOWN
6	BRICK VENEER - SOLDIER COURSE	SUMMIT BRICK	THISTLEDOWN
7	CAST STONE BANDS & SILLS	ROCKCAST	RIESLING
8	COMPOSITE WINDOWS	TBD	DARK BRONZE
9	ALUM. STOREFRONT	TBD	DARK BRONZE
10	CABLE GUARD RAILING	TBD	DARK BRONZE


\*PLEASE NOTE THAT COLOR MAY DIFFER SLIGHTLY FROM HOW IT APPEARS ON YOUR SCREEN DUE TO VARYING MONITOR SETTINGS.



1B 1A 3




WINDOW LOUVER EXAMPLES



1A 1B

\*HORIZONTAL REVEAL PANEL



3

\*STANDING SEAM VERTICAL SIDING

\*PROFILE ONLY, NOT COLOR

PROFILES & WINDOW LOUVERS