





LEGEND

-  **CARPET SQUARES:**
REMOVE & DISPOSE OF EXISTING CARPET FURNISH & INSTALL LEES FACULTY IV CARPET SQUARES, 426T ARUBA BLUE, AROUND 7,550 GROSS SQ. FT.
-  **RUBBER FLOOR TILE:**
REMOVE & DISPOSE OF EXISTING RUBBER FLOOR TILE, CLEAN & PREPARE FLOOR SURFACE, INSTALL OWNER FURNISHED RUBBER FLOOR TILE
-  RUBBER TRANSITIONAL MOULDING JOHNSONITE COLOR 40-BLACK
-  INSTALL RUBBER FLOOR TILE OWNER FURNISHED/ CONTRACTOR INSTALLED

GENERAL NOTES

1. REMOVE & DISPOSE EXISTING CARPET
2. EXISTING BASEBOARDS TO REMAIN
3. NO CARPET SUBSTITUTIONS
4. THE OWNER WILL BE RESPONSIBLE FOR REMOVING ALL PERSONAL AND LOOSE ITEMS FROM PANELS, WORK SURFACES, UPPER BINS, & TACK BOARDS; BOXING UP ALL ITEMS, AND DISCONNECTING AND RECONNECTING ELECTRICAL POWER AND DATA TO ELECTRONIC EQUIPMENT.
5. THE CONTRACTOR SHALL INCLUDE PANEL LIFTING OF SYSTEMS FURNITURE AND MOVING ALL FREESTANDING FURNITURE AND BOXES
6. ALL WORK SHALL BE PERFORMED AFTER NORMAL BUSINESS HOURS 4:00PM TO 12:00AM, MONDAY THRU FRIDAY
7. CONTACT CAPT. JAY LENGFELD FOR MATERIAL DELIVERIES AND STORAGE
8. CONTACT INFORMATION SERVICES FOR DISCONNECTING COMPUTERS, COPIERS, FAX MACHINES
9. COORDINATE AREAS OF WORK AND INSTALLATION DATES WITH CAPT. JAY LENGFELD
10. PRIOR TO BIDDING THE CONTRACTOR SHALL FIELD SURVEY THE EXISTING CONDITIONS AT THE JOBSITE TO IDENTIFY FURNITURE THAT WILL NEED TO BE MOVED DURING THE COARSE OF WORK

**CARPET REPLACEMENT
WEST DISTRICT POLICE STATION**

1/8" = 1'-0"
JULY 1, 2011
JAMES WHITNEY, CITY ARCHITECT

WEST DISTRICT POLICE STATION
1710 McKENNA BLVD.
MADISON, WI 53711

