Mediago.

Madison Landmarks Commission

APPLICATION

City of Madison Planning Division

215 Martin Luther King Jr. Blvd. I Room LL.100 I P.O. Box 2985 I Madison, WI 53701-2985

1	LC	7	Λ	TI	^	n	ı
	<u> </u>	<u> </u>	_	<u> </u>	<u> </u>	<u> </u>	¥

Project Address: 402 N. THORN	TON AUG	Aldermanic District: 2
2. PROJECT		Date Submitted: 7/16/12
Project Title / Description: PENOUL /	reparent t	TENYET PARK PRIDGE
	TO COLOT COL	Con the transfer of the transf
This is an application for: (check all that apply)		
☐ Alteration / Addition to a Designate	ed Madison Landmark	
\square Alteration / Addition to a building a	djacent to a Designated M	adison Landmark
\square Alteration / Addition to a building in	n a Local Historic District (s	pecify):
□ Mansion Hill	□ Third Lake Ridge	☐ First Settlement
□ University Heights	☐ Marquette Bungalows	•
□ New Construction in a Local Historic	c District (specify):	
□ Mansion Hill	□ Third Lake Ridge	☐ First Settlement
□ University Heights	☐ Marquette Bungalows	
□ Demolition		•
□ Variance from the Landmarks Ordir	nance	
☐ Referral from Common Council, Pla	0.00	erral
	ii Commission, or other re-	• • •
□ Other (specify):		
3. <u>APPLICANT</u>		•
Applicant's Name: KAP ROTUETCE	S Company: $oldsymbol{arphi}$	LADISON PARKS DIVISION
Address: CCB SUITE ICH		21504, WI. Zip: 53701
Telephone: (608) 266-4714		tge ecity & madison com
Property Owner (if not applicant): 54416		7 7
Address:	City/State:	Zip:
1/2 7/	(-) H	Date: 7-16-12
Property Owner's Signature:	· Marian	Date.
CENTED AL CUIDANTTAL DECUMPEMENTS		
GENERAL SUBMITTAL REQUIREMENTS Twelve (12) collated paper copies and electronic (.pdf) fil	es of the following: (Note the fil	ing deadline is 4:30 PM on the filing day)
■ Application		
■ Brief narrative description of the project		Questions? Please contact the Historic Preservation Planner:
■ Scaled plan set reduced to 11" x 17" or smaller pages.	Please include:	Amy Scanlon
Site plan showing all property lines and structuresBuilding elevations, plans and other drawings as neede	ed to illustrate the project	Phone: 608.266.6552
 Building elevations, plans and other drawings as neede Photos of existing house/building 	a to mustrate the project	Email: ascanlon@cityofmadison.com
- Contextual information (such as photos) of surroundin	g properties	
■ Any other information that may be helpful in commun		and how it complies with the Landmarks

NOTICE REGARDING LOBBYING ORDINANCE: If you are seeking approval of a development that has over 40,000 square feet of non-residential space, or a residential development of over 10 dwelling units, or if you are seeking assistance from the City with a value of \$10,000 (including grants, loans, TIF or similar assistance), then you likely are subject to Madison's lobbying ordinance (Sec. 2.40, MGO). You are required to register and report your lobbying. Please consult the City Clerk's Office for more information. Failure to comply with the lobbying ordinance may result in fines.

Ordinance, including the impacts on existing structures on the site or on nearby properties.

Tenney Park Maintenance Bridge Removal/Replacement

Narrative Description

Description of the Project

The City of Madison Parks Division is applying for an Individual Permit from the Wisconsin Department of Natural Resources to remove and replace one of the 5 bridges in Tenney Park that provide access to the island in the center of the park. The bridge we hope to replace is known as the Thornton Ave. Bridge. The bridge is approximately 300' east of the intersection of Sherman Ave. and Thornton Ave. and crosses the lagoon from north to south, accessing the northwest corner of the island.

Tenney Park is one of Madison's oldest parks. The park totals approximately 44 acres. It has frontage on Lake Mendota to the west and the Yahara River bisects it to the north. There is also a man made lagoon in the center of the park proper that creates a +/- 9 acre island. History tells us that most of the park is man-made.

The following excerpts are from "A History of the Parks" of Madison by Henry Behrnd:

"Prior to development, the park area was primarily low lying marsh land and required filling by dredging the lake bottom near the shoreline"

"The park was designed by O.C. Simonds of Chicago but his original design was later altered by John Nolen"

"The park lagoons are all artificial, having been dug by horsepower"

And from "Madison - A History of the Formative Years" by David V. Mollenhoff:

"Rather than build the canal across the waist line of the isthmus, he decided to make his attempt in the low marshy land where the Yahara River meandered from lake to lake......"
"Therefore in early 1849 he built a dam at the outlet where the Tenney Park Lock is today located and cleared out debris from the outlet of Lake Monona..."

In 1999, the Tenney Park/Yahara River Parkway was nominated for and granted inclusion into the National Register of Historic Places. All of the bridges in Tenney Park are considered contributing structures to that determination and therefore are considered historic structures. Only one of them (the Marston St. bridge), is/was adequate to drive maintenance vehicles over to the island. At approximately the same time, it was determined by a consultant that the Marston St. bridge was in need of repair and a weight limit was put on the bridge that stopped all truck traffic from using the bridge. For the last 10-15 years, our maintenance staff has had to park large vehicles on Marston St. and take mowers and cushman type vehicles across to do maintenance. Maintenance that requires crossing the bridge with larger vehicles, (tree trimming, athletic field lighting maintenance, asphalt repair) have required us to verify vehicle weight to be sure we are under the weight limit and at times required multiple trips across with smaller vehicles at a larger cost to the taxpayer. At some point in the future, there will be a need for a major replacement project on the island that will require larger vehicle use.

After careful analysis it was decided that it was more cost effective to remove/replace the Thornton Ave. bridge as an option to access the island rather than re-build the Marston St. bridge. Finally, in 2011, money was budgeted to remove and replace one of the bridges in Tenney Park with a new bridge that would serve as a bike/pedestrian crossing as well as one for maintenance

vehicles. The Parks Division hired Bloom Companies, LLC to design a bridge to replace the original Thornton Ave. structure.

New bridge design:

The proposed bridge is a single-span, 30'-6" long, 12'-6" wide, concrete arch founded on modified WisDOT semi-expansion abutments (Type A1). The length of the arch matches existing. The bridge width provides 10 feet of horizontal clearance necessary for vehicles and is about 4 feet wider than existing.

The abutments are supported by piles. Concrete wing walls are attached to the abutments that are oriented parallel to the service road. A combination concrete parapet with ornamental steel rail is attached to the concrete arch and parallel wings. The exterior fascia of the arch, wing walls, and concrete parapet will be clad with natural stone or concrete form liner painted to simulate stone. The ornamental steel rail will be patterned to reflect other rails in the park area.

The arched bridge has a curved profile that lengthened the existing profile and reduced the steepness of the roadway approaches in order to meet ADA standards. The height of the bridge was maintained approximately the same as existing in order to provide 5 feet of navigation clearance under the arch. The lengthening of the north approach was accommodated by a shift in the horizontal alignment of Thorton Avenue. The profile grade line of Thorton was also raised 1°-3" in order to reduce the amount of lengthening in the north approach. The lengthening of the south approach was to accommodate the existing path alignment. The horizontal alignment of the bridge was also rotated about 10 degrees in order to eliminate the existing horizontal curve and align the roadway so it is perpendicular to Thornton Avenue.

Due to the realignment of the bridge and roadway the hydraulic opening of the bridge will be shifted south. The length of the hydraulic opening will remain the same as existing. Fill will be removed from the south side of the existing bridge and placed on the north side of the bridge. The net difference in fill placed in the lagoon will be minimal. Some additional fill will be required because the new bridge will be about 4 feet wider than the existing bridge.

Methods, Materials, and Equipment

Access to the site of work will be from the intersection of Sherman Ave. and Thornton Ave. All work will be staged from the Thornton Ave. right of way. The work will be carried out using typical construction equipment. Methods will ultimately be determined by the contractor selected but typical construction methods for a bridge of this type would be as follows:

- The roadway approaches and the waterway will be closed to traffic during construction.
- Piles will be driven for the abutments by a crane from the Thornton Ave. side.
- Sheet pile or sand bags will be used as a cofferdam at the abutments. The area inside the cofferdam will be excavated (if necessary) and dewatered so the abutments can be poured in dry conditions.
- The reinforced concrete abutments and wing walls will be poured first.
- The reinforced concrete arch will be poured second.
- The concrete parapets will be poured third.
- If the faces are clad with natural stone this will be installed after all of the concrete is poured.
- Fill can be placed and compacted at the abutments after the concrete and stone work is completed.

- The rails will be installed after all of the concrete and stone work is completed.
- The roadway approaches will be paved with asphalt after the bridge is completed.

Restoration Plan

It is anticipated that there will be minimal disturbance for this project. All disturbed areas around and adjacent to the bridge will be seeded with our athletic turf mix and matted with erosion matting, Class II, Type B.

Schedule and Sequence of Work


Demolition of the existing Thornton Ave. bridge is anticipated to start early or mid August, with construction of the new bridge to start immediately after. Completion of the project is expected to be in November, 2012. Accompanying this narrative is a complete project schedule.


Temporary and Permanent Erosion Control Measures


See attached Erosion Control Plan. Temporary silt socks will be placed along the side of the maintenance path during construction. Temporary turbidity barrier will be placed in the water to surround the bridge and cofferdam.


A City of Madison Engineering Stormwater and Erosion Control Permit has been received for this project.


Permanent wetland emergent plants and wet prairie plants will be planted at the water's edge after construction is completed.
























GENERAL NOTES

DRAWINGS SHALL NOT BE SCALED.

BAR STEEL REINFORCEMENT SHALL BE EMBEDDED 2" CLEAR UNLESS SHOWN OR NOTED OTHERWISE.

THE EXISTING GROUND LINE SHALL BE BE THE UPPER LIMITS OF EXCAVATION FOR STRUCTURES.

THE FIRST DIGIT OF A THREE DIGIT BAR MARK AND THE FIRST TWO DIGITS OF A FOUR DIGIT MARK SIGNIFY THE BAR SIZE.

AT THE BACKFACE OF ABUTMENT ALL VOLUME WHICH CANNOT BE PLACE BEFORE ABUTMENT CONSTRUCTION AND IS NOT OCCUPIED BY THE NEW STRUCTURE SHALL BE BACKFILLED WITH STRUCTURE BACKFILL.

ALL DIMENSIONS ARE IN FEET AND INCHES, UNLESS OTHERWISE NOTED.

ALL STATIONS AND ALL ELEVATIONS ARE IN FEET. ELEVATIONS ARE REFERENCED TO THE NORTH AMERICAN VERTICAL DATUM (NAVD) 1988.


PROTECTIVE SURFACE TREATMENT SHALL BE APPLIED TO THE TOP SURFACE OF THE DECK AND TOP AND INSIDE FACE OF THE PARAPETS.

BEVEL EXPOSED EDGES OF CONCRETE 34" UNLESS NOTED OTHERWISE.

THE EXISTING STRUCTURE IS A SINGLE SPAN CONCRETE ARCH BRIDGE, TO BE REMOVED.

TOTAL ESTIMATED QUANTITIES

BIO ITEM NO.	BID ITEMS	UNIT	TOTAL
203.0500.5	REMOVING OLD STRUCTURE OVER WATERWAY STA 11+50.00	LS	ı
206,1000	EXCAVATION FOR STRUCTURE, BRIDGES	LS	i
206,5000	COFFERDAMS (STRUCTURE)	LS	1
210.0100	BACKFILL STRUCTURE	CY	120
502,0100	CONCRETE MASONRY BRIDGES	CY	85
505,0405	BAR STEEL REINFORCEMENT HS BRIDGES	LB	6,500
505.0605	BAR STEEL REINFORCEMENT HS COATED BRIDGES	LB	6,500
51L21I0	PILING STEEL DELIVERED AND DRIVEN HP 12-INCH X 53 LB	LF	420
516.0500	RUBBERIZED MEMBRANE WATERPROOFING	SY	9
612,0406	PIPE UNDERORAIN WRAPPED 6-INCH	LF	100
SPV.0090.01	STEEL RAILING SPECIAL	LF	97
SPV.0180.01	CONCRETE PAVEMENT APPROACH SLAB, SPECIAL	SY	23



BENCH MARK INFORMATION

BM NO.	DESCRIPTION	ELEVATION
выт ххх		xxx
BM2 XXX		xxx

NO. DATE REVISION BY

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION
STRUCTURES DESIGN SECTION

STRUCTURE B-XX-XXX

DRAWN AJA PLANS JRS


TYPICAL SECTION
& QUANTITIES


SHEET 2 OF 10

ð

PER TABLE: valStructural_rev.tbl

DATE: 6/14/2012 10:15:01 AV







Printed by patim on 3/2/2012 at 8:26:31 AM NUE. PRELIMINARY TESICN

1" 1001