| Project Engineers | LeAnne Hannan | 266-4057 |
|------------------------------------|---|---|
| | | |
| Project Limits | Langlois St - Old Middleton Rd. | |
| Street | Existing | Proposed |
| Project Type | rural section | Assessable-install curb & pav't |
| Last Surfaced | 1948 | |
| Pavement Rating | 5 | |
| Curb Rating | 0 | |
| Width | 26-28' | 28' |
| Surface Type | seal coat | asphalt |
| Traffic (Average Vehicles per Day) | unavailable | unchanged |
| Hame (Average venicles per Day) | | unchangeu |
| Sidewalk | Existing | Proposed |
| Work Required | none | none proposed |
| | | |
| Tree Information | | |
| | numerous | tbd, possible conflicts with trees on |
| | | top of bank |
| Other | | |
| | Neighborhood meeting held 2/14/13 attended by 17 people. | |
| | Concerned about drainage and parking that may overflow from new | |
| | development on University/Whitney | 7. Tree concerns |
| Storm Sewer | Existing | Proposed |
| Work Required | none | install storm and connect to |
| Size | none | |
| Material | | existing system at Old Middleton RCP |
| | | RCP |
| Year | | |
| Sanitary Sewer | Existing | Proposed |
| Work Required | | complete replacement |
| Size | 8" | 8" |
| Material | V.P. | PVC |
| Year | 1941 | |
| | | |
| Nater Main | Existing | Proposed |
| Work Required | | |
| Size | 6" | tbd |
| Material | C.I., D.I., SACI | DI |
| Year | 1958, 1976, 1940 | |
| Parking | Existing | Proposed |
| Parking Parking Conditions | both sides | |
| Farking Conditions | DOUTSIDES | no change |
| Street Lighting | Existing | Proposed |
| | On MG&E wood poles | Same |
| Street Lighting | | |
| Street Lighting | | |
| Street Lighting | \$890,000 | |
| Street Lighting | \$890,000 \$182,355 | |

Assessment Policy

Homeowners assessed 100% of the cost to install new drive aprons, curb and gutter and for a cost equivalent to 4' of the roadway. The City pays for the intersections, storm sewer, sanitary repairs, and the remainder of the street cost. The City will pay for 75% of the cost to replace the sanitary sewer lateral from the main to the property line.

| Schedule | | | |
|--------------------------|---|--------------|--|
| Start Date | | 5/28/2013 | |
| Length of Project | | 2.5 months | |
| Traffic Calming | | | |
| | | none planned | |
| Traffic Detours | | | |
| | none | | |
| Real Estate Requirements | | | |
| | Not Required. | | |
| Correspondence | | | |
| | Ngbhd Mtg 2/14/13 Mt. Olive Lutheran Church | | |
| | 17 registrants | | |

1 phone call--no name or address, in favor of project.