

W/ MG&E Poles interior Streets

Project Engineer	Lisa Coleman 266-4093 lcoleman@cityofmadisc	on.com
Project Limits	Royster Oaks Drive	From Cottage Grove Rd. to N. end
	Olbrich Avenue	From Royster Ave to Royster Oaks
	Silas Street	From Pinney St to Olbrich Ave
	Pinney Street	From Silas Street to Dempsey Rd
	Alley	From Pinney to Royster Oaks
	Cottage Grove Road and Dempsey Drive	Sidewalk only adjacent to plat
Street	Existing	Proposed
Project Type	New Plat - all Street, Sidewalk, Utilities	
Widths	Royster Oaks - 36' Wide (S. of Roundabout) and 32' Wide (N. of Roundabout) Silas Street - 32' Wide	
	Pinney Street - 32' Wide (W. of Roundabout) and 36' Side (E. of Roundabout) Olbrich Avenue - 32' Wide	
	Alley - 12' asphalt width + 18" wide alley curbs	
Surface Type	None	Asphalt Pavement

Sid<u>ewalk</u>

Work Required: New sidewalk throughout plat & Replace sidewalk adjacent to plat on Dempsey Road and Cottage Grove Road

Storm Sewer	Existing	Proposed
Work Required	None	Install new
Design Storm		10 year
Size	None	12-24"
Material	None	Concrete
Year Installed	None	2014-2015
Sanitary Sewer	Existing	Proposed
Work Required	None	Install new
Size	None	8-10 Inch
Material	None	PVC
Year	None	2014-2015
Water Main	Existing	Proposed
Work Required	None	Install new
Size	None	8 inch
Material	None	Ductile Iron
Year	None	2014-2015
		Must sign waiver.
Parking	Existing	Proposed
Parking Conditions	None	Both Sides interior streets
Street Lighting	Existing	Proposed

Street Lighting Follow-up Projects

Royster Avenue to be reconstructed separately in 2014 as an assessable project. Improvements for Royster Corners lots fronting on this street will be assessed separately w/ Royster Ave project. Cottage Grove Road and Dempsey Road to be reconstructed separately in 2014 as an assessable project. Improvements (except sidewalk) for Royster Corners lots with frontage on these streets will be assessed separately with Cottage Grove & Dempsey project.

Cost

Total Cost	\$3,900,000
Adjacent Property Assessments	\$3,900,000
City Share	\$0

Assessment Policy

Curb & Gutter, Sidewalk
Pavement
Owner 100% / City 0%
Sanitary Laterals & Main
Owner 100% / City 0%
Storm Sewer
Owner 100% / City 0%
Stormwater Pond
Owner 100% / City 0%
Water Main & Services
Owner 100% / City 0%
Street Lighting
Owner 100% / City 0%

None

Assessments payable in one lump sum or over a period of 8 years, with 3.5% interest charged on unpaid balance

Schedule

Bid Contract July 11, 2014
Tentative Start Date September 29, 2014

Duration of Project Some utils in Fall, finish utils & streets Spring/Summer 2015

Traffic Calming None

Traffic Detours N/A, new streets

See reverse for map

