

URBAN DESIGN COMMISSION APPLICATION CITY OF MADISON

This form may also be completed online at: http://www.cityofmadison.com/planning/documents/UDCapplication.pdf

215 Martin Luther King Jr. Blvd; Room LL-100 PO Box 2985; Madison, Wisconsin 53701-2985 Phone: 608.266.4635 | Facsimile: 608.267.8739

Please complete all sections of the application, including the desired meeting date and the type of action requested.

Date Submitted: November 12, 2014	X Informational Presentation
UDC Meeting Date: November 19, 2014	Initial Approval
Combined Schedule Plan Commission Date (if applicable):	Final Approval
1. Project Address: 1701 Wright Street, Madison, WI 53704	
Project Title (if any): Madison College Culinary Addition and Renovation	
2. This is an application for (Check all that apply to this UDC application): ☐ New Development ☐ AGENDA ITEM # AGENDA ITEM # CLEGISTAR # 310183	
A. Project Type:	ALD. DIST. 10
Project in an Urban Design District* (public hearing-\$300 fee)	
Project in the Downtown Core District (DC) or Urban Mixed-Use District (UMX) (\$150 fee, Minor Exterior Alterations)	
Similiban Employment Center (SEC) or Campus Institutional District (CI) or Employment Comput District (Ci)	
Tranned Development (PD)	, 40 U''
General Development Plan (GDP)	MON 15 5014
Specific Implementation Plan (SIP)	MON 15 co.
☐ Planned Multi-Use Site or Planned Residential Comple	white .
B. Signage:	aning & Comment
Comprehensive Design Review* (public hearing-\$300 fee)	Street Graphics Variance* (public hearing \$200 homic Development hearing \$300 fee)
Sollar	hearing-\$300 fee)
C. Otner:	
Please specify:	
3. Applicant, Agent & Property Owner Information:	
Applicant Name: Mike Stark	Company: Madison College
Street Address: 1701 Wright Street	City/State: Madison, WI Zip: 53704
Telephone: (608) 246-6263 Fax: (608) 246-6331	Email: mmstark@madisoncollege.edu
Project Contact Person: Hamid Noughani	Company: Assemblage Architects
Street Address: 7427 Elmwood Avenue	City/State: Middleton, WI zip: 53562
Telephone:(608) 827-5047 Fax:(608) 827-6960	Email: noughani@assemblagearchitects.com
Project Owner (if not applicant) :	
Street Address:	City/State:Zip:
Telephone:()Fax:()	Email:
4. Applicant Declarations:	
	November 10, 2014
(name of staff person) (date of meeting) B. The applicant attests that all required materials are included in this submittal and understands that if any required information is not provided by the application deadline, the application will not be placed on an Urban Design Commission agenda for consideration.	
Name of Applicant Mike Stark	Relationship to Property Owner
Authorized Signature Mike Shorrix	Date 11/12/14

Madison College

Culinary Addition and Renovation


Project Narrative

The project is designed to accommodate the expansion and renovation of the culinary and baking programs. The project will fill a courtyard space between the existing trux building and the existing administration building expanding eastward to accommodate a relocated entrance and meeting spaces.

The addition will be a one story building, 21' tall, and will reflect material and architecture of the Gateway addition that was completed in 2013. The building exterior will utilize solar shading strategies to minimize heat gain, ample glazing to provide daylighting, and relocates the plaza to service students' outdoor activities and gatherings.

The site improvement will include modest modifications to the parking areas to accommodate public transportation bus service, and better pedestrian access. The landscaping adjacent to the building will be reconfigured to reflect the new addition and reconfigured access patterns.

The total addition is approximately 50,000 SF.



























ADMINISTRATIVE BUILDING - EAST FACE



ENTRANCE TO GYMNASIUM STAIRWELL



VIEW NORTH INTO MAIN PLAZA



VIEW NORTH TO MAIN ENTRANCE



ADMINISTRATIVE BUILDING - SOUTH FACE



OPEN GREEN SPACE



ADMINISTRATIVE BUILDING - NORTH FACE



VIEW EAST TO DRIVEWAY EXIT







ADMINISTRATIVE BUILDING - NORTH FACE




BIKE PARKING AREA





MADISON COLLEGE - TRUAX BUILDING CULINARY ADDITION AND RENOVATIONS






EXTERIOR MATERIAL TO BE SIMILAR TO THE EXISTING GATEWAY BUILDING MATERIAL

SOUTH ELEVATION ADDITION





LEGEND (PROPOSED)

TREE REMOVAL



GENERAL NOTES

- 1. REFER TO THE BOUNDARY, TOPOGRAPHIC, & UTILITY SURVEY FOR EXISTING CONDITIONS NOTES AND LEGEND.
- 2. ALL WORK IN THE ROW AND/OR PUBLIC EASEMENTS SHALL BE IN ACCORDANCE WITH THE CITY OF MADISON STANDARD SPECIFICATIONS FOR PUBLIC WORKS CONSTRUCTION AND SHALL BE PERFORMED BY A CITY—LICENSED CONTRACTOR.
- 3. JSD SHALL BE HELD HARMLESS AND DOES NOT WARRANT ANY DEVIATIONS BY THE OWNER/CONTRACTOR FROM THE APPROVED CONSTRUCTION PLANS THAT MAY RESULT IN DISCIPLINARY ACTIONS BY ANY OR ALL REGULATORY AGENCIES.
- 4. NO SITE GRADING OUTSIDE OR DOWNSLOPE OF PROPOSED SILT FENCE LOCATION. NO LAND DISTURBANCE BEYOND PROPERTY LINES UNLESS OTHERWISE SHOWN.
- 5. DRAWING FOR REVIEW NOT FOR CONSTRUCTION UNLESS OTHERWISE NOTED IN THE TITLE BLOCK.

SITE PLAN NOTES


- 1. ALL DIMENSIONS TO FACE OF CURB UNLESS OTHERWISE NOTED.
- 2. ALL RADII TO FACE OF CURB UNLESS OTHERWISE NOTED.
- 3. CONTRACTOR SHALL PROVIDE CONTROL JOINTS AND CONSTRUCTION JOINTS OF ONE—QUARTER CONCRETE THICKNESS AT AN EQUAL RATIO OF LENGTH TO WIDTH WHEREVER POSSIBLE WITH A MAXIMUM LENGTH BETWEEN JOINTS OF 8' ON CENTER.
- 4. CONTRACTOR SHALL PROVIDE EXPANSION JOINTS IN SIDEWALKS AT A MAXIMUM 24' ON CENTER
- 5. EXTERIOR CONCRETE SURFACES SHALL BE BROOM FINISHED.
- 6. ALL CONCRETE SURFACES TO BE SEALED WITH TYPE TK-26UV CONCRETE SEALANT.
- 7. USE 4" WIDE, HIGH VISIBILITY YELLOW LATEX PAINT FOR PARKING LOT STRIPING LINES.
- 8. MARK AND STRIPE ADA PARKING SPACES APPROPRIATELY.

DEMOLITION NOTES


- 1. THIS PLAN INDICATES ITEMS ON THE PROPERTY INTENDED FOR DEMOLITION BASED ON THE CURRENT SITE DESIGN THAT HAVE BEEN IDENTIFIED BY A REASONABLE OBSERVATION OF THE EXISTING CONDITIONS THROUGH FIELD SURVEY RECONNAISSANCE, "DIGGER'S HOTLINE" LOCATION, AND GENERAL "STANDARD OF CARE". THERE MAY BE ADDITIONAL ITEMS THAT CAN NOT BE IDENTIFIED BY A REASONABLE ABOVE GROUND OBSERVATION, OF WHICH THE ENGINEER WOULD HAVE NO KNOWLEDGE OR MAY BE A PART OF ANOTHER DESIGN DISCIPLINE. IT IS THE CONTRACTOR'S/BIDDER'S RESPONSIBILITY TO REVIEW THE PLANS, INSPECT THE SITE AND PROVIDE HIS OWN DUE DILIGENCE TO INCLUDE IN HIS BID WHAT ADDITIONAL ITEMS, IN HIS OPINION, MAY BE NECESSARY FOR DEMOLITION. ANY ADDITIONAL ITEMS IDENTIFIED BY THE CONTRACTOR/BIDDER SHALL BE IDENTIFIED IN THE BID AND REPORTED TO THE ENGINEER OF RECORD. JSD TAKES NO RESPONSIBILITY FOR ITEMS ON THE PROPERTY THAT COULD NOT BE LOCATED BY A REASONABLE OBSERVATION OF THE PROPERTY OR OF WHICH THEY WOULD HAVE NO KNOWLEDGE.
- 2. CONTRACTOR SHALL KEEP ALL STREETS AND PRIVATE DRIVES FREE AND CLEAR OF ALL CONSTRUCTION RELATED DIRT, DUST AND DEBRIS.
- 3. ALL TREES WITHIN THE CONSTRUCTION LIMITS SHALL BE REMOVED UNLESS SPECIFICALLY CALLED OUT FOR PROTECTION. ALL TREES TO BE REMOVED SHALL BE REMOVED IN THEIR ENTIRETY AND STUMPS SHALL BE GROUND TO PROPOSED SUBGRADE.
- 4. PERFORM TREE PRUNING IN ALL LOCATIONS WHERE PROPOSED PAVEMENT AND/OR UTILITY INSTALLATION ENCROACH WITHIN THE EXISTING DRIP LINE OF THE TREES TO REMAIN. ALL TRENCHING WITHIN THE EXISTING DRIP LINE OF THE TREES TO REMAIN SHALL BE DONE RADIALLY AWAY FROM THE TRUNK IF ROOTS IN EXCESS OF 1" DIAMETER ARE EXPOSED. ROOTS MUST BE CUT BY REPUTABLE TREE PRUNING SERVICE PRIOR TO ANY TRANSVERSE TRENCHING.
- 5. ALL LIGHT POLES TO BE REMOVED SHALL BE REMOVED IN THEIR ENTIRETY, INCLUDING BASE AND ALL APPURTENANCES. SALVAGE FOR RELOCATION. COORDINATE RELOCATION AND/OR ABANDONMENT OF ALL ELECTRIC
- LINES WITH ELECTRICAL ENGINEER AND OWNER PRIOR TO DEMOLITION.

 6. ABANDONED/REMOVED ITEMS SHALL BE DISPOSED OF OFF SITE UNLESS OTHERWISE NOTED.
- 7. THE CONTRACTOR SHALL INSTALL A PEDESTRIAN FENCE AROUND ALL EXCAVATIONS TO BE LEFT OPEN OVERNIGHT AS
- 10. CONTRACTOR TO REPLACE ALL SIDEWALK AND CURB AND GUTTER ABUTTING THE PROPERTIES, WHICH IS DAMAGED BY THE CONSTRUCTION, OR ANY SIDEWALK AND CURB AND GUTTER THAT THE CITY ENGINEER DETERMINES NEEDS TO BE REPLACED BECAUSE IT IS NOT AT A DESIRABLE GRADE REGARDLESS OF WHETHER THE CONDITION EXISTED PRIOR TO BEGINNING CONSTRUCTION.
- 11. GRANULAR BACKFILL MATERIALS ARE REQUIRED IN ALL UTILITY TRENCHES UNDER SIDEWALKS AND PROPOSED PAVED AREAS, ALL UTILITY TRENCH BACKFILL SHALL BE COMPACTED PER SPECIFICATIONS.
- 12. PRIOR TO CONSTRUCTION, THE CONTRACTOR IS RESPONSIBLE FOR: * EXAMINING ALL SITE CONDITIONS RELATIVE TO THE CONDITIONS INDICATED ON THE ENGINEERING DRAWINGS. ANY DISCREPANCIES ARE TO BE REPORTED TO THE ENGINEER AND RESOLVED PRIOR TO THE START OF
- CONSTRUCTION.

 * VERIFYING UTILITY ELEVATIONS AND NOTIFYING ENGINEER OF ANY DISCREPANCIES. NO WORK SHALL BE PERFORMED UNTIL THE DISCREPANCIES ARE RESOLVED.
- NOTIFYING ALL UTILITIES PRIOR TO THE REMOVAL OF ANY UNDERGROUND UTILITIES.
 NOTIFYING THE DESIGN ENGINEER AND LOCAL CONTROLLING MUNICIPALITY 48 HOURS PRIOR TO THE START OF CONSTRUCTION TO ARRANGE FOR APPROPRIATE CONSTRUCTION INSPECTION.
- 9. ANY SANITARY SEWER, SANITARY SEWER SERVICES, WATER MAIN, WATER SERVICES, STORM SEWER, OR OTHER UTILITIES, WHICH ARE DAMAGED BY THE CONTRACTORS, SHALL BE REPAIRED TO THE OWNER'S SATISFACTION AT THE CONTRACTOR'S EXPENSE.
- 10. CONTRACTOR IS RESPONSIBLE FOR SITE SAFETY DURING THE CONSTRUCTION OF THESE IMPROVEMENTS.
- 11. CONTRACTOR TO COORDINATE PRIVATE UTILITY REMOVAL / ABANDONMENT AND NECESSARY RELOCATION WITH RESPECTIVE UTILITY COMPANY. COORDINATION REQUIRED PRIOR TO CONSTRUCTION.
- 12. ALL DEMOLITION SHALL BE IN ACCORDANCE WITH THE APPROVED CITY OF MADISON RECYCLING PLAN.
- 13. ANY CONTAMINATED SOILS SHALL BE REMOVED IN ACCORDANCE WITH FEDERAL AND STATE REGULATIONS TO AN APPROVED LANDFILL.









MADISON COLLEGE TRUAX BUILDING CULINARY ADDITION AND RENOVATION

Madison, Wisconsin

Issued for: SCHEMATICS

Issue date: 10-17-2014

AA Project No.: 2014-04

MC Project No.:

Bid Pkg No.:

REVISION DATE

ARCHITECTS
7427 Elmwood Avenue
Middleton, WI 53562
T 608.827.5047

Professional Services, Inc.
• Engineers • Surveyors • Planners

MADISON REGIONAL OFFICE

161 HORIZON DRIVE, SUITE 101

MADISON MILWAUKEE
KENOSHA APPLETON
www.jsdinc.com

VERONA, WISCONSIN 53593

608.848.5060 PHONE 608.848.2255 FAX


SCALE

SHEET TITLE

DEMO PLAN/SITE PLAN

SHEET NUMBER

C201



LEGEND (PROPOSED)

------ EASEMENT LINE ----- SAWCUT BUILDING LINE ----- EDGE OF PAVEMENT

—o—o—o— CONSTRUCTION FENCE 18" STANDARD CONCRETE CURB & GUTTER

PROPOSED CONCRETE PAVEMENT PROPOSED ASPHALT PAVEMENT



1. REFER TO THE BOUNDARY, TOPOGRAPHIC, & UTILITY SURVEY FOR EXISTING CONDITIONS NOTES AND LEGEND.


- 2. ALL WORK IN THE ROW AND/OR PUBLIC EASEMENTS SHALL BE IN ACCORDANCE WITH THE CITY OF MADISON STANDARD SPECIFICATIONS FOR PUBLIC WORKS CONSTRUCTION AND SHALL BE PERFORMED BY A CITY-LICENSED CONTRACTOR.
- 3. JSD SHALL BE HELD HARMLESS AND DOES NOT WARRANT ANY DEVIATIONS BY THE OWNER/CONTRACTOR FROM THE APPROVED CONSTRUCTION PLANS THAT MAY RESULT IN DISCIPLINARY ACTIONS BY ANY OR ALL REGULATORY AGENCIES.
- 4. NO SITE GRADING OUTSIDE OR DOWNSLOPE OF PROPOSED SILT FENCE LOCATION. NO LAND DISTURBANCE BEYOND PROPERTY LINES UNLESS OTHERWISE SHOWN.
- 5. DRAWING FOR REVIEW NOT FOR CONSTRUCTION UNLESS OTHERWISE NOTED IN THE TITLE BLOCK.

1. ALL DIMENSIONS TO FACE OF CURB UNLESS OTHERWISE NOTED.


- 2. ALL RADII TO FACE OF CURB UNLESS OTHERWISE NOTED.
- 3. CONTRACTOR SHALL PROVIDE CONTROL JOINTS AND CONSTRUCTION JOINTS OF ONE-QUARTER CONCRETE THICKNESS AT AN EQUAL RATIO OF LENGTH TO WIDTH WHEREVER POSSIBLE WITH A MAXIMUM LENGTH BETWEEN JOINTS OF 8' ON CENTER.
- 4. CONTRACTOR SHALL PROVIDE EXPANSION JOINTS IN SIDEWALKS AT A MAXIMUM 24' ON CENTER
- 5. EXTERIOR CONCRETE SURFACES SHALL BE BROOM FINISHED.
- 6. ALL CONCRETE SURFACES TO BE SEALED WITH TYPE TK-26UV CONCRETE SEALANT.
- 7. USE 4" WIDE, HIGH VISIBILITY YELLOW LATEX PAINT FOR PARKING LOT STRIPING LINES.
- 8. MARK AND STRIPE ADA PARKING SPACES APPROPRIATELY.

DEMOLITION NOTES

- THIS PLAN INDICATES ITEMS ON THE PROPERTY INTENDED FOR DEMOLITION BASED ON THE CURRENT SITE DESIGN THAT HAVE BEEN IDENTIFIED BY A REASONABLE OBSERVATION OF THE EXISTING CONDITIONS THROUGH FIELD SURVEY RECONNAISSANCE, "DIGGER'S HOTLINE" LOCATION, AND GENERAL "STANDARD OF CARE". THERE MAY BE ADDITIONAL ITEMS THAT CAN NOT BE IDENTIFIED BY A REASONABLE ABOVE GROUND OBSERVATION, OF WHICH THE ENGINEER WOULD HAVE NO KNOWLEDGE OR MAY BE A PART OF ANOTHER DESIGN DISCIPLINE. IT IS THE CONTRACTOR'S/BIDDER'S RESPONSIBILITY TO REVIEW THE PLANS, INSPECT THE SITE AND PROVIDE HIS OWN DUE DILIGENCE TO INCLUDE IN HIS BID WHAT ADDITIONAL ITEMS, IN HIS OPINION, MAY BE NECESSARY FOR DEMOLITION. ANY ADDITIONAL ITEMS IDENTIFIED BY THE CONTRACTOR/BIDDER SHALL BE IDENTIFIED IN THE BID AND REPORTED TO THE ENGINEER OF RECORD. JSD TAKES NO RESPONSIBILITY FOR ITEMS ON THE PROPERTY THAT COULD NOT BE LOCATED BY A REASONABLE OBSERVATION OF THE PROPERTY OR OF WHICH THEY WOULD HAVE NO KNOWLEDGE.
- 2. CONTRACTOR SHALL KEEP ALL STREETS AND PRIVATE DRIVES FREE AND CLEAR OF ALL CONSTRUCTION RELATED DIRT, DUST AND DEBRIS.
- 3. ALL TREES WITHIN THE CONSTRUCTION LIMITS SHALL BE REMOVED UNLESS SPECIFICALLY CALLED OUT FOR PROTECTION. ALL TREES TO BE REMOVED SHALL BE REMOVED IN THEIR ENTIRETY AND STUMPS SHALL BE GROUND TO PROPOSED SUBGRADE.
- WITHIN THE EXISTING DRIP LINE OF THE TREES TO REMAIN. ALL TRENCHING WITHIN THE EXISTING DRIP LINE OF THE TREES TO REMAIN SHALL BE DONE RADIALLY AWAY FROM THE TRUNK IF ROOTS IN EXCESS OF 1" DIAMETER ARE EXPOSED. ROOTS MUST BE CUT BY REPUTABLE TREE PRUNING SERVICE PRIOR TO ANY TRANSVERSE TRENCHING.
- 5. ALL TERRACE STORM SEWER, INLETS, CATCH BASINS AND STRUCTURES TO BE REMOVED FROM TERRACE WITHIN THE CURRENT BUILDING FOOTPRINT. STORAGE AND REUSE OF INLETS, CATCH BASINS, ETC. TO BE COORDINATED WITH CONSTRUCTION PLANS AND OWNER.
- 6. ALL LIGHT POLES TO BE REMOVED SHALL BE REMOVED IN THEIR ENTIRETY, INCLUDING BASE AND ALL
- APPURTENANCES. SALVAGE FOR RELOCATION. COORDINATE RELOCATION AND/OR ABANDONMENT OF ALL ELECTRIC LINES WITH ELECTRICAL ENGINEER AND OWNER PRIOR TO DEMOLITION.
- 7. ABANDONED/REMOVED ITEMS SHALL BE DISPOSED OF OFF SITE UNLESS OTHERWISE NOTED.
- 8. THE CONTRACTOR SHALL INSTALL A PEDESTRIAN FENCE AROUND ALL EXCAVATIONS TO BE LEFT OPEN OVERNIGHT AS
- 10. CONTRACTOR TO REPLACE ALL SIDEWALK AND CURB AND GUTTER ABUTTING THE PROPERTIES, WHICH IS DAMAGED BY THE CONSTRUCTION, OR ANY SIDEWALK AND CURB AND GUTTER THAT THE CITY ENGINEER DETERMINES NEEDS TO BE REPLACED BECAUSE IT IS NOT AT A DESIRABLE GRADE REGARDLESS OF WHETHER THE CONDITION EXISTED PRIOR TO
- 11. GRANULAR BACKFILL MATERIALS ARE REQUIRED IN ALL UTILITY TRENCHES UNDER SIDEWALKS AND PROPOSED PAVED AREAS, ALL UTILITY TRENCH BACKFILL SHALL BE COMPACTED PER SPECIFICATIONS.
- 12. PRIOR TO CONSTRUCTION, THE CONTRACTOR IS RESPONSIBLE FOR: * EXAMINING ALL SITE CONDITIONS RELATIVE TO THE CONDITIONS INDICATED ON THE ENGINEERING DRAWINGS. ANY DISCREPANCIES ARE TO BE REPORTED TO THE ENGINEER AND RESOLVED PRIOR TO THE START OF
- CONSTRUCTION. * VERIFYING UTILITY ELEVATIONS AND NOTIFYING ENGINEER OF ANY DISCREPANCIES. NO WORK SHALL BE PERFORMED UNTIL THE DISCREPANCIES ARE RESOLVED. * NOTIFYING ALL UTILITIES PRIOR TO THE REMOVAL OF ANY UNDERGROUND UTILITIES.
- CONSTRUCTION TO ARRANGE FOR APPROPRIATE CONSTRUCTION INSPECTION. 9. ANY SANITARY SEWER, SANITARY SEWER SERVICES, WATER MAIN, WATER SERVICES, STORM SEWER, OR OTHER
- UTILITIES, WHICH ARE DAMAGED BY THE CONTRACTORS, SHALL BE REPAIRED TO THE OWNER'S SATISFACTION AT THE
- 10. CONTRACTOR IS RESPONSIBLE FOR SITE SAFETY DURING THE CONSTRUCTION OF THESE IMPROVEMENTS. 11. CONTRACTOR TO COORDINATE PRIVATE UTILITY REMOVAL / ABANDONMENT AND NECESSARY RELOCATION WITH
- RESPECTIVE UTILITY COMPANY. COORDINATION REQUIRED PRIOR TO CONSTRUCTION.
- 13. ANY CONTAMINATED SOILS SHALL BE REMOVED IN ACCORDANCE WITH FEDERAL AND STATE REGULATIONS TO AN









MADISON COLLEGE TRUAX BUILDING **CULINARY ADDITION AND** RENOVATION

Madison, Wisconsin

ssued for: SCHEMATICS 10-17-2014 lssue date: 2014-04 AA Project No.: MC Project No.:

Bid Pkg No.:

EVISION

assemblage ARCHITECTS 7427 Elmwood Avenue Middleton, WI 53562 T 608.827.5047

ISI Professional Services, Inc. • Engineers • Surveyors • Planners MADISON REGIONAL OFFICE

161 HORIZON DRIVE, SUITE 101 VERONA, WISCONSIN 53593 608.848.5060 PHONE 608.848.2255 FAX MADISON MILWAUKEE KENOSHA APPLETON www.jsdinc.com

SCALE

SHEET TITLE DEMO PLAN/SITE PLAN

SHEET NUMBER

C200