Larkin St, Glenway St, Hillcrest Dr, Zwerg Dr & Ross St Resurf. w/ Utiliities

Project Limits

oject Limits Mineral Point-Hillcrest, Speedway-Regent, Larkin-Glenway, Glenway-Franklin, Glenway-Franklin

Ald. Shiva Bidar-Sielaff & Ald. Chris Schmidt

Street	Existing	Proposed
Project Type		Resurfacing w/Utility replacement
Last Surfaced	1981, 1986, 1998, 2000	
Pavement Rating	3, 4 5	
Curb Rating	6,7	
Width	28, 30, 36	same
Surface Type	asphalt	Asphaltic
Traffic (Average Vehicles per Day)	no data available	Same
manic (Average venicies per Day)	no data avallable	Same
idewalk	Existing	Proposed
Work Required		Replace As Necessary
Storm Sewer	Existing	Proposed
Work Poguirod		add inlets Larkin/Hammersley
Work Required		add mets Larkin/Hammersley
Design Storm		TOD
Size		TBD
Material		RCP
Year		2015
anitary Sewer	Existing	Proposed
Work Required		Replacement, move from terrace
·		& backyard to street
Size	6" & 8"	8 Inch
Material	VP	PVC
Year	1946-1948	2015
Vater Main	Existing	Proposed
Work Required		Replace on Larkin, Zwerg & Ross
		Glenway, north of booster station
		eliminate backyard main on Larkin
Size	6"	8"
Material	SACI UL	ductile iron
Year	1927-1948	2015
i eai	1327-1340	2013
Parking	Existing	Proposed
Parking Conditions	Parking one side	Same
Street Lighting	Existing	Proposed
Street Lighting	On MG&E wood poles	Same
Cost		
Total Cost	\$2,604,000	street \$849K, storm \$28K
Adjacent Property Assessments	\$219,000	sanitary \$927K, water \$800K
City Share	\$2,385,000	
	ψ2,000,000	

Assessment Policy	
Street Concrete Items	Owner 50% / City 50%
Sanitary Sewer Lateral Replacements	Owner 25% / City 75%
Assessments payable in one lump sur	m or over a period of 8 years, with 3.5% interest charged on unpaid balance
Rain Gardens, if installed	Owner 25% / City 75%
All remaining contract items to be paid	for by the City of Madison
Schedule	

Start Date Length of Project	mid April 3-4 months
Traffic Calming	none
Traffic Detours	none
Real Estate Requirements	Not Required
Tree Information	Forestry has identified 6 trees that need to be removed with the project. 2 Ash and 5 for condition issues. In addition, Forestry has or will be removing 3 additional trees.
Correspondence	
	PIM held 2/2, attended by 32 people. Most were there for info, no opposition to project.