Official Project Name	Walter St & Sargent St Assessment District-2016		
Project Engineer	LeAnne Hannan	266-4057	
Project Limits Ald. David Ahrens	Hargrove StMiwaukee St, Walter St-Dennett Dr		
Street	Existing	Proposed	
Project Type		Reconstruction	
Last Surfaced	1995 (Walter) 1988 (Sargent)		
Pavement Rating	4-5 (Walter) 4 (Sargent)		
Curb Rating	6 (Walter) 7 (Sargent)		
Width	36' (Walter) 30' (Sargent)	same	
Surface Type	asphalt	Asphaltic	
Traffic (Average Vehicles per Day)	4250 (Walter) n/a (Sargent)	Same	
Sidewalk	Existing	Proposed	
Work Required		Replace As Necessary	
Storm Source	Eviation	Drenegad	
Storm Sewer	Existing	Proposed inlets/leads, additional storm from	
		Hargrove to Richard. Storm easement	
Work Required		between 3514/3522 Sargent	
Design Storm			
Size	12"	TBD	
Material	RCP	RCP	
	1949-1951, 2011 (Walter)		
Year	1948(Sargent)	2017	
Rain Gardens	Existing	Proposed	
Work Required		The terraces on Walter St & Sargent	
		St are not wide enough to accommoda	
		-	
		the installation of rain gardens, need a min, of 10' from face of curb to SW	
Sanitary Sewer	Existing	Proposed	
		Replace between Hargrove & Richard,	
		replace from 46 Walter St to Milwauker remainder of Walter was lined in 2013.	
Work Dogwired		Replace on Sargent	
Work Required		15", 8" (north end of Walter) 10" on	
Size	8 Inch (Substandard)	Sargent	
Material	VP	PVC	
Year	1948-1949	2017	
Water Main	Existing	Proposed	
Work Required	Exioting	Complete Replacement	
Size	6"	8"	
Material	SACI UL	ductile iron	
Year	1948	2017	
Parking	Existing	Proposed	
Parking Conditions	Parking both sides	Same	
Street Lighting	Existing	Proposed	
Street Lighting	On MG&E wood poles	Same	
S ₁ = 1			
LOST			
	\$2,548,550	street \$875K_storm \$324.1K	
Cost Total Cost Adjacent Property Assessments	\$2,548,550 \$254,180	street \$875K, storm \$324.1K sanitary \$693K, water \$653.7K	

Assessment Policy			
Street Concrete Items	Owner 50% / City 50%		
Sanitary Sewer Lateral Replacements Owner 25% / City 75%			
Assessments payable in one lump sum or over a period of 8 years, with 3.0% interest charged on unpaid balance			
Rain Gardens, if installed	Owner 25% / City 75%		
All remaining contract items to be paid	I for by the City of Madison		

Schedule		
Start Date	Spring 2017	postponed to 2017 to avoid conflict
Length of Project	3.5-4 months	with Cottage Grove Rd/Dempsey construction
Traffic Calming	traffic circles & islands	replaced if removed for utility work
Traffic Detours	none	buses will use Fair Oaks & Dempsey
Real Estate Requirements	Not Required	
	Forestry has identified 20 trees (including 18 Ash)for removal with the project and 4 (including 1 Ash) that will	
Tree Information	be removed prior to construction.	
Public Informational Meeting	Oct. 19, 2015	9 attendees plus Ald. Ahrens
Correspondence		

Thomas Frank, 213 Walter

notice typo in spreadsheet and had questions about lateral replacement.