PROJECT SUMMARY AND FACT SHEET:

Hugh Place Storm Relief and Resurfacing

Project Engineer: Glen Yoerger, 261-9177

Alder: Sheri Carter, Dist 14

Project Limits: Hughes Place from Cypress Way to S Park Street

1981 & 2001

No Proposed Work

Villager Mall Alley

McDonalds Storm Sewer Easement

Project Summary: The Proposed Project includes improvement of Hughes Place and installation of new storm sewer from Hughes

Place to Badger Road/Park Street intersection to alleviate flooding issues at Hughes Place including the alley

adjacent to the Villager Mall.

| Street: Hughes Place | Existing | Proposed |
|----------------------|----------------------|---|
| Project Type: | | Resurfacing |
| Surface Type | Asphalt Pavement | Asphalt Pavement |
| Street Width | 32 ft - face to face | 32 ft - face to face |
| Parking | Parking Allowed | No Proposed Changes |
| Street Lighting | Wood & Steel Poles | No Proposed Changes |
| Sidewalk | Concrete | No Proposed Changes |
| Storm Sewer | Existing | Proposed |
| Work Required | | Construct new storm sewer with concrete pipe in Hughes PL, Alley & Easement |
| Design Storm | | 10 Year |
| Size | 12 - 30 Inches | 12 - 42 Inches |
| Material | RCP | RCP |

2017

| Water Main | Existing | Proposed | |
|-----------------------|--------------------------|--|--|
| Work Required | | Construct new water main om Hughes Place | |
| Size | 6-Inch | 8 Inches | |
| Material | Cast Iron | Ductile Iron | |
| Year | 1955 | 2017 | |
| Project Costs | | | |
| Street Costs: | \$480,000.00 | | |
| Storm Sewer Cost: | \$340,000.00 | | |
| Water Main Costs: | \$200,000.00 | | |
| Total Cost: | \$1,020,000.00 | | |
| City of Madison Cost: | \$1,020,000.00 | | |
| Schedule | | | |
| Start Date | June, 2017 | | |
| Project Duration | Approximately 2.5 Months | | |

Traffic Calming: None

Year

Sanitary Sewer

Traffic Detours: No Posted Detours are planned. Hughes Place will be closed to through traffic, but accesss will be maintained

to businesses.

Real Estate Requirements: Storm Sewer Easement Required through McDonald's Property

Tree Information: Approximatly three tree will be removed on from Metro's South Transfer Point Parcel.

Project Location:

