	Official Project Name	S Stoughton Rd Frontage Rd, Remington Rd & Blossom Ln Assm't Dist-201	1
--	-----------------------	---	---

Project EngineerLeAnne Hannan266-4057

City Share

Project Limits Ald. DeMarb	Blossom-N End, Stoughton Service Rd -E End, Stoughton Service Rd-Remington	
Street	Existing	Proposed
Project Type		Resurfacing/Rural to Urban
r reject rype	1967 (Stoughton) 1951 (Remington)	rtocarracing, rtararto croarr
Last Surfaced	1981 (Blossom)	
Pavement Rating	3 to 5	
, and the second	8 on Stoughton & Blossom, no curb on	
Curb Rating	Remington	add curb on Remington
3	32 (Stoughton) 28 (Remington) 36	32 (Stoughton) 32 (Remington) 36
Width	(Blossom)	(Blossom)
Surface Type	asphalt	Asphaltic
Traffic (Average Vehicles per Day)	not available	Same
, 5		
Sidewalk	Existing	Proposed
Work Required	none	none
Storm Sewer	Existing	Proposed
Work Required	Blossom/Remington to the east	extend to Stoughton/Remington
Design Storm	Bloodon, Komington to the date	oxiona to otoaginoi (n tonnington
Size	18"	18"
Material	RCP	RCP
Material		
Year	1981	2017
Sanitary Sewer	Existing	Proposed
-		line existing mains on Blossom &
Work Required		Remington via separate contract
Size	8"	
Material	VP	
Year	1952	
Water Main	Existing	Proposed
Trace: main		
Work Required		replace main, reconnect laterals
Size	6"	•
Material	CI	
	1956 (Stoughton) 1965 (Remington,	
Year	Blossom)	2017
Cost		
Total Cost	\$680,000	street \$280K, storm \$30K
Adjacent Property Assessments	\$46,465	water \$370K
City Share	\$633 535	

\$633,535

Assessment Policy

Street Concrete Items (Reconstruct) Owner 50% / City 50%

Rural to Urban Property owner pays for curb and cost equivalent to 4" of the roadway.

Sanitary Sewer Lateral Replacements Owner 25% / City 75%

Assessments payable in one lump sum or over a period of 8 years, with 3.0% interest charged on unpaid balance

All remaining contract items to be paid for by the City of Madison

Schedule

Start Date 12-Jun-17 Length of Project 2 months

Traffic Calming none planned

Traffic Detours none

Real Estate Requirements Not Required

Forestry has identified 8 Ash trees for removal with the project plus 3 cedar

trees/shrubs located between

Tree Information Stoughton Rd and the frontage road

Public Informational Meeting Feb. 21, 2017 1 attendee- plus Ald. DeMarb

Correspondence

none