A	GEN	IDA	#	
	OLIV	DA	Ħ	

### City of Madison, Wisconsin

REPORT OF: FAÇADE IMPROVEMENT GRANT STAFF TEAM

TO:

**URBAN DESIGN COMMISSION** 

Façade Improvement Grant Application:

1: 111-117 S. Pinckney/ 107-111 King Street

**AUTHOR:** 

Craig Wilson

Office of Economic Revitalization Economic Development Division

DATED:

June 13, 2017

### **SUMMARY:**

On October 3, 2000, the Common Council adopted Resolution No. 61179, approving the Objectives and Criteria for the Façade Improvement Grant Program. The resolution specifies that all Façade Improvement proposals be referred to the Urban Design Commission for comments and recommendations.

Attached for your review is the following Facade Improvement proposal:

1. 111-117 S. Pinckney/ 107-111 King Street

**Grantee: Richard Fritz** 

The scope of the exterior work will include:

- a. Knock down existing stucco. Re-skim coat and re-paint.
- b. Refurbish signage bands.
- c. Install new pillar lights.
- d. Restoration of marble storefront bases.
- e. Replace aluminum entry doors with historically accurate wood doors.
- f. Install new lintel over King Street entrance and refinish balcony.

- ${f g.}\,$  Remove awning and metal screening covering transoms from Pinckney street side.
- h. Install new operable transoms.
- i. Remove chimney.

### **See Attachments for Specifications**

Total project cost for 111-117 S. Pinckney/ 107-111 King Street exterior work is estimated at \$217,750. Façade Improvement Grant not to exceed \$20,000.

### **RECOMMENDATION:**

The Landmarks Commission at its June 19<sup>th</sup> meeting will review this project. Our recommendation will be contingent upon the Landmarks Commission granting a Certificate of Appropriateness for the scope of work covered in this report.

The above Façade Improvement Grant proposal has been reviewed by the Façade Improvement Grant Program staff team and meets the requirements of the program. The Staff Team recommends approval of the above Facade Improvement Grant proposal.



## CITY OF MADISON FAÇADE IMPROVEMENT GRANT PROGRAM

Building and beautifying Madison, one storefront at a time



Department of Planning & Community & Economic Development **Economic Development Division** 

215 Martin Luther King Jr., Boulevard Craig Wilson, 266-6557 cwilson@cityofmadison.com

PROGRAM APPLICATION
Applicant: Richard Fritz Phone: 608. 575,9885
Business Name: Fritz Properties
Building Name: Pinckney Street Arcade (Same bldg as 107-113 King St.
Business Address: 111 South finckney Zip Code 53703
E-mail Address: irfritz @ Sbc global.com
Property Owner: Richard Fritz
Address: P.O. Box 6067 Madison, W1 53716
Name of Grantee: Richard Fritz
Lease Terms:
Definition of Project Scope: Restoration of the two story facade
including removal of expanded metal second story elements.
runoval of cementious conting over existing masonry, replacing of single strength or missing second story "eyebrow" windows with insulated units  ATTACHMENT
Please provide photographs and copy of lease, land contract, or deed. Tenants must provide owner's written authorization.
PROJECT BUDGET
List Individual Project Elements Total Cost Grant \$ Private \$ (Awning, sign, painting of trim, etc.)
tibel = discovery is
needed to determine
work.
A

Total:



### CITY OF MADISON FAÇADE IMPROVEMENT GRANT PROGRAM

### Building and beautifying Madison, one storefront at a time



Department of Planning & Community & Economic Development
Economic Development Division
215 Martin Luther King Jr., Boulevard
Craig Wilson, 266-6557

cwilson@cityofmadison.com

Contractor/Supplier: TRI-NORTH BUILDERS **ATTACHMENT** \* Bids, estimates, and/or contracts, product brochures, locater map and design drawings, if appropriate. REMARKS \_\_\_\_\_ APPLICANT'S CERTIFICATION The Applicant certifies that all information in this application and all information furnished in support of this application is given for the purpose of obtaining a grant under the City of Madison Façade Grant Program and is true and complete to the best of the applicant's knowledge and belief. Signature: Signature: Please send this completed application, accompanying materials, and application fee of \$100 to: **Economic Development Division** Attn: Craig Wilson 215 Martin Luther King Jr. Boulevard, Room 312 P.O. Box 2983

Madison, WI 53701-2983



608.271.8717 F: 608.271.3354

June 9, 2017

Melissa Destree AIA, IIDA Destree Design Architects, Incorporated 222 West Washington Avenue #310 Madison, WI 53703

RE: Pinckney / King Street Arcade Building Exterior Renovation Cost Estimate Summary

Dear Melissa,

The following is the initial cost estimate for the proposed exterior renovation work for the aforementioned building. Please review and comment as needed.

Phase of Work	Estimate
King Street lintel and soffit repair	\$ 10,400
Remove Splatter texture on Pinckney Street, Sounding / Repair of	\$ 49,000
loose cementious materials and recoat of removed materials	
Skim-coat Pinckney Street Elevation	\$ 18,000
Remove "decorative" metal window boxes on Pinckney Street	\$ 4,200
Replace 18 eyebrow windows on Pinckney Street	\$ 14,400
Paint exterior wood window mullion	\$ 13,750
Remove masonry stack from rooftop / roof patch	\$ 7,600
New retail space doors and hardware	\$ 12,000
Refinish King Street balcony, new door and hardware	\$ 7,800
Eight (8) new electrical fixtures	\$ 2,500
Remove bronze colored sign band and repair holes to refinish	\$ 4,200
Signage allowance	\$ 15,000
Marble below windows on exterior	\$ 9,000
Interior finishes (entry flooring and column repair)	\$ 2,500
Design and Permitting allowance	\$ 10,000
General Conditions (supervision, direct project OHD costs)	\$ 14,400



P: 608,271.8717 F: 608,271.3354

Overhead and Markup (12%) Total estimated costs

\$ 23,000 \$217,750

We look forward to moving this project forward as the approvals allow. We will coordinate the initial stabilization work with you and the owner. Respectfully,

Bernie Lange, Client Services

Tri-North Builders

# **Arcade Building**

107-113 King Street 111 South Pickney

Historic Condition Report & Recommendations - May 31, 2017







Knock-down stucco, re-skim-coat and re-paint stucco

Recommendation to refurbish signage band below Context – to historic proportion

Window – existing wood trim prep and paint

Exterior pillar lights to be replaced with Historic light per image

Parapet cracking – historic balustrade buried in parapet wall (refer to historic Photo)

'Artificial Stone' Cornice band painted. Paint is failing. Assuming it is a cast concrete product. Cast stone will be repaired and stabilized, skim-coated, and re-painted

Arch is painted brick. Paint is failing. Stabilize and re-paint

Storefront base – Appears to be Marble (drawings state Marble) with paint (failing). Option to remove paint and restore Marble.

Paint scheme – Propose new paint scheme for monochromatic 'original' tone



Metal trim piece (lintel) is collapsing – wet entered top side of deck. Corner with cracking at brickline. Stabilization is required immediately.

 $2^{nd}$  floor door not historic – This is used as an exiting 'jump balcony'. The door will be replaced with a new 36" wide door that mimics the original 2ft wide door and sidelight. Interior partition work may be required to access the replacement.

Aluminum storefront at entry doors to be replaced with historically accurate system, wood doors and element that acknowledges the original revolving door. Add historic gold painted signage on window.

Reinstall the 'hotel' historic marker into the interior of the arcade.

Reinstall the 'Arcade' historic marker with the refurbishment of the column/stucco.




Close-up of Condition

Metal trim piece is collapsing – wet entered top side of deck. Corner with cracking at brickline Balcony structure to be reviewed – need access to topside Possible rusted off clips.



Operable transoms were original to building Refurbish wood trim and paint



Knock-down stucco, re-skim-coat and re-paint stucco

Recommendation to refurbish signage band to historic proportion

Window – existing wood trim prep and paint

Exterior pillar lights to be replaced with Historic light per image

Parapet cracking – historic balustrade buried in parapet wall (refer to historic Photo)

'Artificial Stone' Cornice band painted. Paint is failing. Assuming it is a cast concrete product. Cast stone will be repaired and stabilized, skim-coated, and re-painted

Arch is painted brick. Paint is failing. Stabilize and re-paint

Storefront base – Appears to be Marble (drawings state Marble) with paint (failing). Option to remove paint and restore Marble.

Paint scheme - Propose new paint scheme for monochromatic 'original' tone

**Update Signage** 

Aluminum storefronts to remain



Suggestion for Aluminum drip cap to align wood and alum trim.

Remove paint from marble

Replace Wood doors with New Oak stained doors to match Historic profile with ADA hardware (quantity = 3)





Secondary façade on Pickney Street -

Knock-down stucco, re-skim-coat and re-paint stucco

Recommendation to refurbish signage band to historic proportion

2<sup>nd</sup> floor screening to be removed and historic transoms replaced with Graham alum system

Exterior pillar lights to be replaced with Historic light per image

'Artificial Stone' Cornice band painted. Paint is failing. Assuming it is a cast concrete product. Cast stone will be repaired and stabilized, skim-coated, and re-painted

Storefront base - maintenance to 117 wood storefront

Arcade Entry Storefront - Aluminum storefront at entry doors to be replaced with historically accurate system, wood doors and element that acknowledges the original revolving door. Add historic gold painted signage on window.


Paint scheme – Propose new paint scheme for monochromatic 'original' tone Update Signage at Arcade Entry (remove awning)
Remove large chimney



Image cementitious material. Knock-down and re-skimcoat



Pickney stucco texture/cementitious material is very 'loose' compared to King Street texture. Recommendation to retain material, skim coat with 'smoother' texture, similar to King Street.



Area to Test the removal of the cementitious material. Hard fired brick face has spalled off while removing concrete product. This product is not stucco.



Historic vestibule – flooring is not original. Recommendation to create a perimeter mosaic tile with walk-off carpet inset at both vestibules on Pickney and King Street. Replace ceiling light with new historic acorn style light.

# 0 BUILDING LOCATION

# KING STREET ARCADE

# FACADE RENOVATION

# 107-111 KING STREET & 111-117 S PINCKNEY ST

MADISON, WI

**ARCHITECTURAL** 

EXTERIOR ELEVATIONS EXTERIOR ELEVATIONS

### **KEYPLAN** NOT TO SCALE

SYMBOL LEGEND:

BUILDING OR WALL SECTION CALLOUT

ROOM IDEN-

### **DEFINITIONS:**

ACOUSTICAL CEILING TILE AL/ALUM ALUMINUM

CAB CABINET CARPET CSWK CASEWORK CLG

CL COORDINATE

CENTERLINE

DBL **DOUBLE ELEV** ELEVATION

COOR

EQ XTG

FEC FIRE EXTINGUISHER CABINET FD FLUORESCENT FLUOR

FURNISHED BY OWNER, INSTALLED BY CONTRACTOR FURNISHED BY OWNER, INSTALLED BY OWNER FOIO

GA

GENERAL CONTRACTOR GC

GL

**GWB** GYPSUM WALL BOARD

HDWD HVAC

HEATING, VENTILATION, AND AIR CONDITIONING

HGT

HOLLOW METAL

MECHANICAL, ELECTRICAL, PLUMBING MEP

MTL

NOT IN CONTRACT NOT TO SCALE OVHG **OVERHANG** 


PLASTIC LAMINATE PLAM REQ REQUIRED

STAINLESS STEEL

UNLESS OTHERWISE NOTED UON

VIF VERIFY IN FIELD

WDB WOOD BASE WOOD/WOOD VENEER



222 WEST WASHINGTON AVE. SUITE 310

MADISON, WI 53703 PH: 608.268.1499

FAX: 608.268.1498

KING ST



MADISON, WI 53703 PH: 608.268.1499 vw.Destreearchitects.

VG STREET ARCADE CADE RENOVATION 3 STREET & 111-117 S PINCKNEY S MADISON, WI

ISS	UANCES:
LAN	NDMARKS/UDC 06.19.17
_	
_	
_	
_	
_	
_	
_	
_	
_	
_	

### Schematic Design Phase

This drawing indicates the scale and relationship of the project components. This drawing is not for construction.

PROJECT #: 170427.00



- 1. SEE TOOD FOR OVERALL FLOOR PLAN
- 2. SEE 1/A301 FOR PROPOSED ENTRY ALTERNATE ELEVATION

### **KEYNOTES - FLOOR PLAN**

1  $\frac{\text{FLOOR PLAN}}{1/4" = 1'-0" @ 24"X36"}$ 

- 1 ROUGH IN FOR FUTURE ADA OPERATOR
- 2 XTG DR REMAIN OPEN
- 3 NEW DOOR


KEY PLAN


**KEY PLAN** 


4 NEW 40" DOOR

### **KEYNOTES - DEMO PLAN**

- A DEMO WALL
- B DEMO DOOR
- c DEMO WINDOW







@ JY"YZY"



222 WEST WASHINGTON AVE. SUITE 310 MADISON, WI 53703 PH: 608.268.1499 www.Destreearchitects.com

KING STREET ARCADE FACADE RENOVATION 107-111 KING STREET & 111-117 S PINCKNEY ST MADISON, WI

- 1	
	ISSUANCES:
	LANDMARKS/UDC 06.19.17
١	_
	-
	_
	_
	_
1	_
1	-
1	_
ı	_
١	_
١	_
- 1	
-1	

Schematic Design Phase:

This drawing indicates the scale and relationship of the project components. This drawing is not for construction.

PROJECT #: 170427.00 SHEET NUMBER

A100





222 WEST WASHINGTON AVE. SUITE 310 MADISON, WI 53703 PH: 608.268.1499 www.Destreearchitects.com

DESTREE DESIGN ARCHITECTS, NC.
HOLDS ALL RIGHTS INCLUDING THE
COPPRIGHT OF THIS DOCUMENT, AS
WELL AS THE CONCEPTS AND DESIGNS
INCORPORATED HEREN AS AN
HISTRUMENT OF SERVICE. AS PROPERTY
OF DESTREE DESIGN ARCHITECTS, INC., IT
S NOT TO BE COPED, DISTRIBUTED, OR
EXPRESS WEITHER CONSENT OF DESTREE
DESIGN ARCHITECTS, INC., IT

KING STREET ARCADE
FACADE RENOVATION
107-111 KING STREET & 111-117 S PINCKNEY ST
MADISON, WI

ISSUANCES:	
LANDMARKS/UDC 06.	19.17
_	
_	
-	
_	
_	
_	
_	
_	
_	
_	
_	

### Schemalic Design Phase:

This drawing indicates the scale and relationship of the project components. This drawing is not for construction.

PROJECT #: 170427.00 SHEET NUMBER

A300



4'-5"±

BASE WORK TO RETAIN EXISTING ALUMINUM STORE FRONT

8" STONE PROFILED BASE RAISED PANEL WOOD INSE DESTREE grehitecture & design

222 WEST WASHINGTON AVE. SUITE 310 MADISON, WI 53703 PH: 608.268.1499 www.Destreearchilects.com

DESIREE DESIGN ARCHITECTS, NC.
HOLDS ALL RIGHTS INCLUDING THE
COPPRIGHT OF THIS DOCUMENT, AS
WELL AS THE CONCEPTS AND DESIGNS
INCORPORATED HERBIN AS AN
HISTRUMENT OF SERVICE. AS PROPERTY
OF DESTREE DESIGN ARCHITECTS, INC., IT
IS NOT TO SE COPED, DISTRIBUTED, OR
USED IN WINCHE OF PART WITHOUT THE
EXPRESS WRITTEN CONSISTIN OF DESIREE
DESIGN ARCHITECTS, INC., IT
DESIGN ARCHITECTS, INC.

EY ST

KING STREET ARCADE
FACADE RENOVATION
107-111 KING STREET & 111-117 S PINCKNEY ST
MADISON, WI

ISSUANCES:	
LANDMARKS/UDC	06.19.17
_	
_	
_	
_	
-	
_	
_	
_	
_	
_	
_	

### Schematic Design Phase:

This drawing indicates the scale and relationship of the project components.
This drawing is not for construction.

PROJECT #: 170427.00 SHEET NUMBER

A301

0' 2' 4'

1 KING STREET ELEVATION - PROPOSED ENTRY ALTERNATE









### **HIN4545**

Shown in dark bronze patina

4 ½ " x 4 ½ "

0.134" thickness

Supplied with #12 x 1 1/4" screws

Hinge supplied with flat ends but can be ordered with any one of the finials as shown below the hinge

### **Options**

Available in 3 standard patinas, with your choice of levers or knobs.

Visit www.ashleynorton.com to view more options.

(973) 835-4027 ashleynorton.com info@ashleynorton.com



# **Available Patina Options**







(973) 835-4027 ashleynorton.com info@ashleynorton.com

### **Lighting Options**

https://www.acuitybrands.com/products/detail/249156/Antique-Street-Lamps/EAB5-Wall-Brackets/Eurotique-EAB5-Large-Pendant-Wall-Brackets-Cast-Aluminum

### https://www.rejuvac

enation.com/catalog/products/medford \$170 on sale



# **Product Specifications Specification**

Detail

Item#

A1950

Web Configuration ID

4f830e60e694aa13aa00003e

Finish

Black Enamel

Socket Type

Incandescent

Selected Shade(s)

B9164 OP 10 in

Max Wattage Per Socket

100 W

**UL Listing** 

UL Listed Wet

Canopy Width

6-3/4"

Overall Width

12.18"

Overall Length

15.53"

**Overall Projection** 

18.7"

Shade Height

9"

### Exterior and Interior Vestibule:

 $\underline{https://brasslightgallery.com/lighting/carlton-one-light-semi-flush-ceiling-fixture-with-3-14-shade-holder}$ 


### Finish black



### Hardware

### Dark Bronze Ashley Norton

http://www.ashleynorton.com/product-details/Tubular-Entrysets-SQLES-Escutcheon.aspx



Lever Colonial #490 with 13" backplate and dead bolt at retail entry doors. 8" high bronze kick plate both sides, flat head screws, Bronze hinges with round finial. Coordinating Push/Pull #1155 with deadbolt on Arcade entry doors.



http://www.baldwinhardware.com/products/details/accessories/door-accessories/kick-plate-2000-102



### Entry doors:

Andersen Rectangular #193 or equal – 2 1/2" red oak, beveled glass – custom Size, ORB closers



# **Pickney Street Facade**



SW 2839

SW 7530

SW 0024

SW 7068

SW 6992

# **King Street Facade**



SW 7530

SW 0024

SW 7068

SW 6992