



		Overstory Tree Req. (or x2 for		
Interior Parking Lots	SF	Orn./Evrgrn. Tree Sub.)		
Total Parking Lot Area	71,570			
Min. Parking Lot Islands (5%)	3,579	22		
		Quantity	Quantity	
Element	Point Value	Proposed	Existing	Points Achieved
Overstory Deciduous Tree	35	19		665
Ornamental Tree	15	9		135
Evergreen Tree	15	0		0
Shrub, deciduous	2	147		294
Shrub, evergreen	3	0		0
Ornamental Grass	2	216		432
		Interior Parking Lots Points Total		1526

General Site, Foundation,	Screening			
Element	Point Value	Quantity Proposed	Quantity Existing	Points Achieved
Overstory Deciduous Tree	35	3		105
Ornamental Tree	15	1		15
Evergreen Tree	15	13		195
Shrub, deciduous	2	10		20
Shrub, evergreen	3	2		6
Ornamental Grass	2	93		186
Omamental/Decorative Fence or Wall (4 pts/10 LF)	4	0		0
		General Site Plantings Total	527	
		TOTAL LANDSCAPE POINTS		34

NOTES

- 1. IT IS THE CONTRACTOR'S RESPONSIBILITY TO FIELD VERIFY SURVEY INFORMATION AND SITE CONDITIONS PRIOR TO START OF CONSTRUCTION AND REPORT ANY DISCREPANCIES. CONTRACTOR SHALL CONTACT DIGGER'S HOTLINE TO LOCATE ALL PUBLIC AND PRIVATE UTILITIES PRIOR TO START OF CONSTRUCTION. ANY DAMAGE CAUSED TO EXISTING UTILITIES, EITHER SHOWN OR NOT, SHALL BE REPAIRED AND PAID FOR AT THE CONTRACTOR'S EXPENSE.
- 2. CONTRACTOR SHALL PROTECT BENCHMARKS.
- 3. ALL TREES SHOWN TO BE RETAINED WITHIN THE LIMITS OF CONSTRUCTION SHALL BE PROTECTED WITH TREE PROTECTION FENCING. ALL TREE PROTECTION FENCING SHALL BE IN PLACE PRIOR TO ANY SITE WORK. SEE SPECIFICATION 31 13 16, "SELECTIVE TREE AND SHRUB PROTECTION AND TRIMMING" FOR PROTECTION REQUIREMENTS.
- 4. ALL EXISTING PLANT MATERIAL IS SHOWN AT EXISTING, APPROXIMATED SIZE PER CITY OF MADISON STANDARDS.
- 5. ALL WRAPPINGS, WIRE BASKETS, BURLAP, AND OTHER MISCELLANEOUS MATERIAL SHALL BE COMPLETELY REMOVED FROM ALL SHRUB AND TREE ROOT BALLS PRIOR TO INSTALLATION.
- 6. ALL LAWN AREAS DISTURBED BY CONSTRUCTION ACTIVITIES SHALL BE RE-SEEDED AT NO COST TO
- 7. CONTRACTOR IS RESPONSIBLE FOR WATERING AND MAINTENANCE OF PLANT MATERIAL - SEE SPECIFICATIONS FOR MORE INFORMATION.
- 8. FORESTRY WILL ISSUE A REMOVAL PERMIT FOR TWO STREET TREEES: 19" ASH AND 22" ASH ON S. PATERSON ST. DUE TO CITY FORESTRY AND CONSTRUCTION IMPACT REQUEST. PLEASE CONTACT BRAD HOFMANN: bhofmann@cityofmadison.com OR 608-266-4816 TO OBTAIN THE STREET TREE REMOVAL PERMIT.
- 9. CONTRACTOR SHALL CONTACT CITY FORESTRY (BRAD HOFMANN) AT LEAST ONE WEEK PRIOR TO PLANTING TO SCHEDULE INSPECTING THE NURSERY STOCK, REVIEW PLANTING SPECIFICATIONS AND INDICATE PLANTING LOCATIONS WITH THE LANDSCAPE CONTRACTOR.
- 10. CONTRACTOR SHALL INSTALL TREE PROTECTION FENCING IN THE AREA BETWEEN THE CURB AND SIDEWALK AND EXTEND IT AT LEAST 5-FEET FROM BOTH SIDES OF THE TREE ALONG THE LENGTH OF THE TERRACE. NO EXCAVATION IS PERMITTED WITHIN 5-FEET OF THE OUTSIDE EDGE OF A TREE TRUNK. IF EXCAVATION WITHIN 5-FEET OF ANY TREE IS NECESSARY, CONTRACTOR SHALL CONTACT CITY FORESTRY (BRAD HOFMANN) PRIOR TO EXCAVATION TO ASSESS THE IMPACT TO THE TREE AND ROOT SYSTEM. TREE PRUNING SHALL BE COORDINATED WITH CITY FORESTRY. TREE PROTECTION SPECIFICATIONS CAN BE FOUND IN SECTION 107.13 OF CITY OF MADISON STANDARD SPECIFICATIONS FOR PUBLIC WORKS CONSTRUCTION. ANY TREE REMOVALS THAT ARE REQUIRED FOR CONSTRUCTION AFTER THE DEVELOPMENT PLAN IS APPROVED WILL REQUIRE AT LEAST 72-HOUR WAIT PERIOD BEFORE A TREE REMOVAL PERMIT CAN BE ISSUED BY FORESTRY, TO NOTIFY THE ALDER OF THE CHANGE IN THE TREE PLAN.

© 2013 Potter Lawson Architects





LANDSCAPE ARCHITECTS

303 S. PATERSON SUITE ONE MADISON, WI 53703 Phone: 608 251-3600 Fax: 608 251-2330 www.ksd-la.com

Notes:



901 Boutique Hotel East Washington Ave.

Madison, Wisconsin

Project #: 2016.36.01

Date	Issuance/Revisions	Symb		
07/19/17	Madison Land Use App	lication		
10/04/17	Urban Design Submittal			
10/25/17	Urban Design Submittal Update			

LANDSCAPE PLAN

100