

**Center for Industry and Commerce: New Construction - 2018**

<b>Project Engineer</b>	Andrew Zwieg 266-9219	Alder: Baldeh
<b>Project Limits</b>	Ronald Reagan Ave John Wall Dr.	Hoepker Rd to Merchant Street Ronald Reagan Ave to Manufacturers Dr.
<b>Street</b>	<b>Existing</b>	<b>Proposed</b>
Project Type: New Construction		
Last Surfaced	NA	NA
Pavement Rating	NA	New Pavement
Curb Rating	NA	New Curb & Gutter
Width	NA	36'
Surface Type	NA	Asphalt
<b>Sidewalk &amp; Terraces</b>		
Terraces	NA	8.5' Grass
Sidewalks	NA	New 5' Sidewalk
<b>Storm Sewer</b>		
Work Required: Install New Storm Sewer		
Size	NA	New 15", 18", 24", 36" & 48" Pipes
Material	NA	Concrete
Year	NA	2018
<b>Sanitary Sewer</b>		
Work Required: Install New Sanitary Sewer		
Size	NA	New 8" and 10" Pipes
Material	NA	PVC
Year	NA	2018
<b>Water Main</b>	<b>Existing</b>	<b>Proposed</b>
Work Required: Install New Water main		
Size	NA	New 10" and 16" Pipes
Material	NA	Ductile Iron
Year	NA	2018
<b>Parking</b>		
Existing Parking Conditions: NA		
Proposed Parking: Parking On Both Sides of the Street		
<b>Street Lighting</b>	<b>Existing</b>	<b>Proposed</b>
Area Street Lighting	NA	New Street Lights (ME)
Pedestrian Lighting	NA	NA
<b>Infrastructure Removals</b>		
Lot 3: Sanitary and storm sewer in conflict with the new layout of Lot 3 will be removed and assessed to the property owner.		
Lot 4: Sanitary sewer, water main, storm sewer, street lights, gas/telephone/electric lines and Merchant street in conflict with the new layout of Lot 4 will be removed and assessed to the property owner.		
<b>Mass Grading</b>		
Lot 3 will be regraded to accommodate Ronald Reagan Avenue and the drainage ditch relocation.		
Lot 4: will be regrading to accommodate Ronald Reagan Avenue, the drainage ditch relocation and the removal of Merchant Street.		
<b>Trees</b>		
Existing trees on the vacant land in conflict with the new street, Lot 3 & 4 will be removed. There is no proposed tree plantings planned. Trees will be planted once the lots are developed and driveway entrances are established.		
<b>Cost</b>		
Total Cost	\$5,288,054	
<b>Schedule</b>		
Start Date	April 2, 2018	
Project duration	Approx. 4 Months	
<b>Correspondence</b>	NA	
see map on reverse		

